

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	100 CY		
0007	0141000000-E	240	BERM DITCH CONSTRUCTION	120 LF		
0008	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (VII)	500 TON		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	630 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	1,980 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	3,176 LF		
0012	0335300000-E	305	18" DRAINAGE PIPE	1,040 LF		
0013	0335400000-E	305	24" DRAINAGE PIPE	828 LF		
0014	0335500000-E	305	30" DRAINAGE PIPE	320 LF		
0015	0335600000-E	305	36" DRAINAGE PIPE	328 LF		
0016	0354000000-E	310	***** RC PIPE CULVERTS, CLASS ***** (96", III)	120 LF		
0017	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	152 LF		
0018	0414000000-E	310	60" RC PIPE CULVERTS, CLASS III	36 LF		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0420000000-E	310	66" RC PIPE CULVERTS, CLASS III	128		LF
002C	0995000000-E	340	PIPE REMOVAL	935		LF
0021	1077000000-E	SP	#57 STONE	15		TON
0022	1121000000-E	520	AGGREGATE BASE COURSE	2,896		TON
0023	1220000000-E	545	INCIDENTAL STONE BASE	1,200		TON
0024	1275000000-E	600	PRIME COAT	238		GAL
002E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	1,600		SY
002E	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	500		SY
0027	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,960		TON
002E	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,490		TON
002E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	60		TON
003C	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,260		TON
0031	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	340		TON
0032	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	180		TON
003E	1704000000-E	SP	PATCHING EXISTING PAVEMENT	10		TON
0034	2220000000-E	838	REINFORCED ENDWALLS	26.4		CY
003E	2275000000-E	SP	FLOWABLE FILL	45		CY
003E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	74		EA

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	114 CY		
003E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	33.1 LF		
003E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	25 EA		
004C	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	5 EA		
0041	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0042	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	21 EA		
0043	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	20 EA		
0044	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
004E	2418000000-E	SP	FRAME WITH GRATES, DRIVEWAY DROP INLET	60 LF		
004E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	8,090 LF		
0047	2612000000-E	848	6" CONCRETE DRIVEWAY	880 SY		
004E	2619000000-E	850	4" CONCRETE PAVED DITCH	11 SY		
004E	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		
005C	3030000000-E	862	STEEL BM GUARDRAIL	100 LF		
0051	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0052	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0053	3628000000-E	876	RIP RAP, CLASS I	35 TON		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	3635000000-E	876	RIP RAP, CLASS II	627	TON	
005E	3649000000-E	876	RIP RAP, CLASS B	131	TON	
005E	3651000000-E	SP	BOULDERS	200	TON	
0057	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	730	SY	
005E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
005E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	865	SF	
006C	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
0061	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	90	SF	
0062	4430000000-N	1130	DRUMS	300	EA	
006E	4445000000-E	1145	BARRICADES (TYPE III)	64	LF	
0064	4455000000-N	1150	FLAGGER	100	DAY	
006E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	10	EA	
006E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	500	LF	
0067	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	12,177	LF	
006E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	50	LF	
006E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	72	LF	
007C	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	30	EA	
0071	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,000	LF	

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	140 EA		
0073	6000000000-E	1605	TEMPORARY SILT FENCE	5,165 LF		
0074	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	21 TON		
0075	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	500 TON		
0076	6012000000-E	1610	SEDIMENT CONTROL STONE	462 TON		
0077	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0078	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	30 LB		
0079	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1 TON		
0080	6024000000-E	1622	TEMPORARY SLOPE DRAINS	70 LF		
0081	6029000000-E	SP	SAFETY FENCE	100 LF		
0082	6030000000-E	1630	SILT EXCAVATION	1,100 CY		
0083	6036000000-E	1631	MATTING FOR EROSION CONTROL	400 SY		
0084	6037000000-E	SP	COIR FIBER MAT	100 SY		
0085	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	30 SY		
0086	6042000000-E	1632	1/4" HARDWARE CLOTH	2,000 LF		
0087	6045000000-E	SP	*** TEMPORARY PIPE (18")	150 LF		
0088	6070000000-N	1639	SPECIAL STILLING BASINS	1 EA		
0089	6071010000-E	SP	WATTLE	150 LF		
0090	6071030000-E	1640	COIR FIBER BAFFLE	375 LF		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6071050000-E	SP	*** SKIMMER (1-1/2")	5	EA	
0092	6084000000-E	1660	SEEDING & MULCHING	3	ACR	
0093	6111000000-E	SP	IMPERVIOUS DIKE	400	LF	
0094	6114500000-N	1667	SPECIALIZED HAND MOWING	20	MHR	
009E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	28	EA	
009E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (30 + 80 -L-)	Lump Sum	L.S.	
1116/Jan11/Q63091.5/D305533090000/E96			Total Amount Of Bid For Entire Project :			

Contract No. **C202025**

County (ies): **Lincoln**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General