

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (22 + 60.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	60 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	800 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	261 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	455 SY		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	84 LF		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	340 LF		
0014	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	328 LF		
0015	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	32 LF		
0016	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	32 LF		
0017	0995000000-E	340	PIPE REMOVAL	208 LF		
0018	1099500000-E	505	SHALLOW UNDERCUT	70 CY		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	380 TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0021	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 3")	930 SY		
0022	1330000000-E	607	INCIDENTAL MILLING	830 SY		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	430 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0B	350 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	695 TON		
0026	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	80 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0028	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0029	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0030	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0031	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0032	2077000000-E	815	6" OUTLET PIPE	6 LF		
0033	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	10 EA		
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4 EA		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	4 EA		
0037	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,030 LF		
0038	2556000000-E	846	SHOULDER BERM GUTTER	8 LF		
0039	2591000000-E	848	4" CONCRETE SIDEWALK	300 SY		
0040	2605000000-N	848	CONCRETE CURB RAMP	3 EA		
0041	2612000000-E	848	6" CONCRETE DRIVEWAY	120 SY		
0042	2830000000-N	858	ADJUSTMENT OF MANHOLES	3 EA		
0043	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
0044	3030000000-E	862	STEEL BM GUARDRAIL	62.5 LF		
0045	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0046	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	4 EA		
0047	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0048	3360000000-E	863	REMOVE EXISTING GUARDRAIL	230 LF		
0049	3569000000-E	867	BARBED WIRE FENCE RESET	60 LF		
0050	3572000000-E	867	CHAIN LINK FENCE RESET	70 LF		
0051	3635000000-E	876	RIP RAP, CLASS II	31 TON		
0052	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0053	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	502 SY		
0054	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	456 SF		

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
005E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	155	SF	
0057	4430000000-N	1130	DRUMS	50	EA	
005E	4435000000-N	1135	CONES	50	EA	
005E	4445000000-E	1145	BARRICADES (TYPE III)	160	LF	
006C	4450000000-N	1150	FLAGGER	640	HR	
0061	4510000000-N	SP	LAW ENFORCEMENT	200	HR	
0062	4516000000-N	1180	SKINNY DRUM	70	EA	
006E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	48	EA	
0064	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	11,450	LF	
006E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	20	LF	
006E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	14	EA	
0067	5326600000-E	1510	16" WATER LINE	685	LF	
006E	5558600000-E	1515	16" VALVE	3	EA	
006E	5589200000-E	1515	2" AIR RELEASE VALVE	1	EA	
007C	5692000000-E	1520	30" SANITARY GRAVITY SEWER	120	LF	
0071	5776000000-E	1525	5' DIA UTILITY MANHOLE	1	EA	
0072	5777000000-E	1525	6' DIA UTILITY MANHOLE	1	EA	
007E	5782000000-E	1525	UTILITY MANHOLE WALL, 5' DIA	7.2	LF	

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	5783000000-E	1525	UTILITY MANHOLE WALL, 6' DIA	8.5	LF	
0075	5810000000-E	1530	ABANDON 16" UTILITY PIPE	681	LF	
0076	5814000000-E	1530	ABANDON 30" UTILITY PIPE	128	LF	
0077	5828000000-N	1530	REMOVE UTILITY MANHOLE	2	EA	
0078	5835000000-E	1540	**" ENCASEMENT PIPE (48")	110	LF	
0079	5836000000-E	1540	24" ENCASEMENT PIPE	192	LF	
008C	5871900000-E	1550	TRENCHLESS INSTALLATION OF 16" IN SOIL	96	LF	
0081	5871910000-E	1550	TRENCHLESS INSTALLATION OF 16" NOT IN SOIL	96	LF	
0082	6000000000-E	1605	TEMPORARY SILT FENCE	1,110	LF	
0083	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	250	TON	
0084	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	140	TON	
008E	6012000000-E	1610	SEDIMENT CONTROL STONE	125	TON	
008E	6015000000-E	1615	TEMPORARY MULCHING	3	ACR	
0087	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
008E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5	TON	
008E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
009C	6029000000-E	SP	SAFETY FENCE	100	LF	
0091	6030000000-E	1630	SILT EXCAVATION	400	CY	
0092	6036000000-E	1631	MATTING FOR EROSION CONTROL	4,000	SY	

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	6037000000-E	SP	COIR FIBER MAT	30	SY	
0094	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,907	SY	
0095	6042000000-E	1632	1/4" HARDWARE CLOTH	455	LF	
0096	6071030000-E	1640	COIR FIBER BAFFLE	165	LF	
0097	6071050000-E	SP	*** SKIMMER (1-1/2")	3	EA	
0098	6084000000-E	1660	SEEDING & MULCHING	3	ACR	
0099	6087000000-E	1660	MOWING	3	ACR	
010C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0101	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0102	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75	LB	
0103	6108000000-E	1665	FERTILIZER TOPDRESSING	2	TON	
0104	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
010E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	

STRUCTURE ITEMS

010E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22 + 60.00-L-)	Lump Sum	L.S.	
0107	8096000000-E	450	PILE EXCAVATION IN SOIL	66	LF	
010E	8097000000-E	450	PILE EXCAVATION NOT IN SOIL	66	LF	
010E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (22 + 60.00-L-)	Lump Sum	L.S.	

County : Mecklenburg

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	8156000000-E	SP	CONCRETE WEARING SURFACE	4,049 SF		
0111	8161000000-E	420	GROOVING BRIDGE FLOORS	4,739 SF		
0112	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	51 CY		
0113	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	84.1 CY		
0114	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22 + 60.00-L-)	Lump Sum	L.S.	
011E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	12,081 LB		
011E	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	2,025 LB		
0117	8364000000-E	450	HP12X53 STEEL PILES	260 LF		
011E	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	220 LF		
011E	8482000000-E	460	THREE BAR METAL RAIL	159 LF		
012C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	535 TON		
0121	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	595 SY		
0122	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0123	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	1,748.34 LF		

1357/Jan10/Q62743.39/D530924290000/E123

Total Amount Of Bid For Entire Project :

Contract No **C202777**

County (ies): **Mecklenburg**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General