

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS



STATE PROJECT REFERENCE NO.	SHEET NO.
R-2414B	TCP-1

**PLAN FOR TEMPORARY
TRAFFIC CONTROL, MARKING & DELINEATION
CAMDEN COUNTY**

R-2414B

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT-N.C. DEPARTMENT OF TRANSPORTATION-RALEIGH, N.C., DATED JULY 2006 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1101.02	TEMPORARY LANE CLOSURES
1101.03	TEMPORARY ROAD CLOSURES
1101.04	TEMPORARY SHOULDER CLOSURES
1101.05	WORK ZONE VEHICLE ACCESSES
1101.11	TRAFFIC CONTROL DESIGN TABLES
1110.01	STATIONARY WORK ZONE SIGNS
1110.02	PORTABLE WORK ZONE SIGNS
1115.01	FLASHING ARROW PANELS
1130.01	DRUM
1135.01	CONES
1145.01	BARRICADES
1150.01	FLAGGING DEVICES
1160.01	TEMPORARY CRASH CUSHION
1165.01	TRUCK MOUNTED IMPACT ATTENUATOR
1170.01	PORTABLE CONCRETE BARRIER
1205.01	PAVEMENT MARKINGS - LINE TYPES & OFFSETS
1205.02	PAVEMENT MARKINGS - 2 LANE & MULTILANE ROADWAYS
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.05	PAVEMENT MARKINGS - TURN LANES
1205.06	PAVEMENT MARKINGS - THRU LANE DROPS
1205.08	PAVEMENT MARKINGS - SYMBOLS & WORD MESSAGES
1205.09	PAVEMENT MARKINGS - PAINTED ISLANDS
1205.11	PAVEMENT MARKINGS - RAILROAD CROSSINGS
1250.01	PAVEMENT MARKER SPACING
1251.01	RAISED PAVEMENT MARKERS (TEMPORARY & PERMANENT)

INDEX OF SHEETS

SHEET NO.	TITLE
TCP-1	LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, LEGEND AND INDEX OF SHEETS
TCP-2 THRU TCP-2B	PROJECT NOTES/PAVEMENT MARKING SCHEDULE
TCP-3	PHASE I PHASING
TCP-4 THRU TCP-6	PHASE I OVERVIEW
TCP-7 THRU TCP-9	PHASE I DETAILS
TCP-10	PHASE II PHASING
TCP-11 THRU TCP-13	PHASE II OVERVIEW
TCP-14 THRU TCP-18A	PHASE II DETAILS
TCP-19	PHASE III PHASING
TCP-20 THRU TCP-22	PHASE III OVERVIEW
TCP-23 THRU TCP-30	PHASE III DETAILS
TCP-31	DETAIL FOR PORTABLE CONCRETE BARRIER AT TEMPORARY SHORING LOCATIONS
TCP-31A	TEMPORARY SHORING RECOMMENDATIONS
TCP-32	DETAIL FOR WORK ZONE WARNING SIGNS

LEGEND

- GENERAL**
- DIRECTION OF TRAFFIC FLOW
 - NORTH ARROW
 - PROPOSED PVMT. EXIST. PVMT.
 - WORK AREA
 - REMOVAL OF EXISTING PAVEMENT
- TRAFFIC CONTROL DEVICES**
- TYPE I BARRICADE
 - TYPE II BARRICADE
 - TYPE III BARRICADE
 - CONE
 - DRUM SKINNY DRUM
 - FLASHING ARROW PANEL (TYPE C)
 - STATIONARY SIGN
 - PORTABLE SIGN
 - STATIONARY OR PORTABLE SIGN
 - CRASH CUSHION
 - CHANGEABLE MESSAGE SIGN
 - TRUCK MOUNTED IMPACT ATTENUATOR (TMIA)
 - POLICE
 - FLAGGER
- PAVEMENT MARKINGS**
- CRYSTAL/CRYSTAL PAVEMENT MARKER
 - YELLOW/YELLOW PAVEMENT MARKER
 - CRYSTAL/RED PAVEMENT MARKER
 - PAVEMENT MARKING SYMBOLS

TIP PROJECT:

10/18/2011 10:33:47 AM P:\R-2414B\TrafficControl\TCP\2414b_TCP_pshldgn

**N.C.D.O.T. TRAFFIC CONTROL, MARKING & DELINEATION SECTION
LIST OF CONTACTS**

STUART BOURNE, P.E.	TRAFFIC CONTROL ENGINEER
G. L. GETTIER, P.E.	TRAFFIC CONTROL PROJECT ENGINEER
JAY W. WOOLARD, P.E.	TRAFFIC CONTROL PROJECT DESIGN ENGINEER
	TRAFFIC CONTROL DESIGN ENGINEER / TECHNICIAN

B.A. May **APPROVED:**
DATE: 10/21/11

SEAL

PLAN PREPARED FOR NCDOT BY:

B.A. MAY, P.E. PROJECT ENGINEER

C.L. MULLEN DESIGN ENGINEER

J.C. PENDERGRAFT DESIGN TECHNICIAN



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-2

PROJECT NOTES

GENERAL NOTES

CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS, AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS OR RESULT IN DUPLICATE OR UNDESIRED OVERLAPPING OF DEVICES. MODIFICATION MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING, OR REMOVAL OF DEVICES AS DIRECTED BY THE ENGINEER.

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR DIRECTED BY THE ENGINEER.

TIME RESTRICTIONS

A) DO NOT CLOSE OR NARROW TRAVEL LANES AS FOLLOWS:

ROAD NAME	DAY AND TIME RESTRICTIONS
1. US 158	7:00 AM TO 9:00 AM AND 4:00 PM TO 7:00 PM (MON-FRI)
2. NC 34	7:00 AM TO 9:00 AM AND 4:00 PM TO 7:00 PM (MON-FRI)

B) DO NOT CLOSE OR NARROW TRAVEL LANES DURING HOLIDAYS AND SPECIAL EVENTS AS FOLLOWS:

ROAD NAME
1. US 158
2. NC 34

HOLIDAY

- FOR ANY UNEXPECTED OCCURRENCE THAT CREATES UNUSUALLY HIGH TRAFFIC VOLUMES, AS DIRECTED BY THE ENGINEER.
- FOR NEW YEAR'S, BETWEEN THE HOURS OF 9:00 A.M. DECEMBER 31st TO 7:00 P.M. JANUARY 2ND. IF NEW YEAR'S DAY IS ON A FRIDAY, SATURDAY, SUNDAY, OR MONDAY THEN UNTIL 7:00 P.M. THE FOLLOWING TUESDAY.
- FOR EASTER, BETWEEN THE HOURS OF 9:00 A.M. THURSDAY AND 7:00 P.M. MONDAY.
- FOR MEMORIAL DAY, BETWEEN THE HOURS OF 9:00 A.M. FRIDAY TO 7:00 P.M. TUESDAY.
- FOR INDEPENDENCE DAY, BETWEEN THE HOURS OF 9:00 A.M. THE DAY BEFORE INDEPENDENCE DAY AND 7:00 P.M. THE DAY AFTER INDEPENDENCE DAY.

IF INDEPENDENCE DAY IS ON A FRIDAY, SATURDAY, SUNDAY OR MONDAY THEN BETWEEN THE HOURS OF 9:00 A.M. THE THURSDAY BEFORE INDEPENDENCE DAY AND 7:00 P.M. THE TUESDAY AFTER INDEPENDENCE DAY.

- FOR LABOR DAY, BETWEEN THE HOURS OF 9:00 A.M. FRIDAY AND 7:00 P.M. TUESDAY.
- FOR THANKSGIVING DAY, BETWEEN THE HOURS OF 9:00 A.M. TUESDAY TO 7:00 P.M. MONDAY.
- FOR CHRISTMAS, BETWEEN THE HOURS OF 9:00 A.M. THE FRIDAY BEFORE THE WEEK OF CHRISTMAS DAY AND 7:00 P.M. THE FOLLOWING TUESDAY AFTER THE WEEK OF CHRISTMAS.

C) DO NOT CONDUCT ANY HAULING OPERATIONS AGAINST THE FLOW OF TRAFFIC OF AN OPEN TRAVELWAY UNLESS THE HAULING OPERATION IS PROTECTED BY BARRIER OR GUARDRAIL OR AS DIRECTED BY THE ENGINEER.

LANE AND SHOULDER CLOSURE REQUIREMENTS

- REMOVE LANE CLOSURE DEVICES FROM THE LANE WHEN WORK IS NOT BEING PERFORMED BEHIND THE LANE CLOSURE OR WHEN A LANE CLOSURE IS NO LONGER NEEDED OR AS DIRECTED BY THE ENGINEER.
- WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING WITHIN 5 M OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN SHOULDER USING ROADWAY STANDARD DRAWING NO. 1101.04 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL OR A LANE CLOSURE IS INSTALLED.
- WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING ON THE SHOULDER ADJACENT TO AN UNDIVIDED FACILITY AND WITHIN 1.5 M OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN TRAVEL LANE USING ROADWAY STANDARD DRAWING NO. 1101.02 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL.

WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING ON THE SHOULDER ADJACENT TO A DIVIDED FACILITY AND WITHIN 3 M OF AN OPEN TRAVEL LANE, CLOSE THE NEAREST OPEN TRAVEL LANE USING ROADWAY STANDARD DRAWING NO. 1101.02 UNLESS THE WORK AREA IS PROTECTED BY BARRIER OR GUARDRAIL.

- WHEN PERSONNEL AND/OR EQUIPMENT ARE WORKING WITHIN A LANE OF TRAVEL OF AN UNDIVIDED OR DIVIDED FACILITY, CLOSE THE LANE ACCORDING TO THE TRAFFIC CONTROL PLANS, ROADWAY STANDARD DRAWINGS, OR AS DIRECTED BY THE ENGINEER. CONDUCT THE WORK SO THAT ALL PERSONNEL AND/OR EQUIPMENT REMAIN WITHIN THE CLOSED TRAVEL LANE.
- DO NOT WORK SIMULTANEOUSLY WITHIN 5 M ON BOTH SIDES OF AN OPEN TRAVELWAY, RAMP, OR LOOP WITHIN THE SAME LOCATION UNLESS PROTECTED WITH GUARDRAIL OR BARRIER.
- PROVIDE TRAFFIC CONTROL FOR APPROPRIATE LANE CLOSURES FOR SURVEYING DONE BY THE DEPARTMENT.

PAVEMENT EDGE DROP OFF REQUIREMENTS

- BACKFILL AT A 6:1 SLOPE UP TO THE EDGE AND ELEVATION OF EXISTING PAVEMENT IN AREAS ADJACENT TO AN OPENED TRAVEL LANE THAT HAS AN EDGE OF PAVEMENT DROP-OFF AS FOLLOWS:

10/18/2011 4:34:16 PM FAX-R-2414B-TrafficControl\TCPV-2414B-TCP_psh2.dgn

WETHERILL ENGINEERING
 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: 10/21/11

SEAL

PROJECT NOTES

SCALE: NONE		REVISIONS
DATE: 609		
DWG. BY: CLM		
DESIGN BY: CLM		
REVIEWED BY: BAM		

CADD FILE

PROJECT NOTES (CONT'D)



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-2A

GENERAL NOTES

BACKFILL DROP-OFFS THAT EXCEED 50 MM ON ROADWAYS WITH POSTED SPEED LIMITS OF 45 MPH OR GREATER.

BACKFILL DROP-OFFS THAT EXCEED 75 MM ON ROADWAYS WITH POSTED SPEED LIMITS LESS THAN 45 MPH.

BACKFILL WITH SUITABLE COMPACTED MATERIAL, AS APPROVED BY THE ENGINEER, AT NO EXPENSE TO THE DEPARTMENT.

- K) DO NOT EXCEED A DIFFERENCE OF 50 MM IN ELEVATION BETWEEN OPEN LANES OF TRAFFIC FOR NOMINAL LIFTS OF 40 MM. INSTALL ADVANCE WARNING "UNEVEN LANES" SIGNS (W8-11) IN ADVANCE AND A MINIMUM OF EVERY HALF MILE THROUGHOUT THE UNEVEN AREA.

TRAFFIC PATTERN ALTERATIONS

- L) NOTIFY THE ENGINEER TWENTY ONE (21) CALENDAR DAYS PRIOR TO ANY TRAFFIC PATTERN ALTERATION.

SIGNING

- M) INSTALL ADVANCE WORK ZONE WARNING SIGNS WHEN WORK IS WITHIN 12 M FROM THE EDGE OF TRAVEL LANE AND NO MORE THAN THREE (3) DAYS PRIOR TO THE BEGINNING OF CONSTRUCTION.
- N) PROVIDE PERMANENT SIGNING.
- O) PROVIDE SIGNING AND DEVICES REQUIRED TO CLOSE THE ROAD ACCORDING TO THE ROADWAY STANDARD DRAWINGS AND TRAFFIC CONTROL PLANS.
- PROVIDE SIGNING REQUIRED FOR THE OFF-SITE DETOUR ROUTE AS SHOWN IN THE TRAFFIC CONTROL PLANS.
- P) COVER OR REMOVE ALL SIGNS AND DEVICES REQUIRED TO CLOSE THE ROAD WHEN ROAD CLOSURE IS NOT IN OPERATION.
- COVER OR REMOVE ALL SIGNS REQUIRED FOR THE OFF-SITE DETOUR WHEN THE DETOUR IS NOT IN OPERATION.
- Q) ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.
- R) INSTALL BLACK ON ORANGE "DIP" SIGNS (W8-2) AND/OR "BUMP" SIGNS (W8-1) 500 FT IN ADVANCE OF THE UNEVEN AREA, OR AS DIRECTED BY THE ENGINEER.

TRAFFIC BARRIER

- S) INSTALL TEMPORARY BARRIER ACCORDING TO THE TRAFFIC CONTROL PLANS A MAXIMUM OF TWO (2) WEEKS PRIOR TO BEGINNING WORK IN ANY LOCATION. ONCE TEMPORARY BARRIER IS INSTALLED AT ANY LOCATION PROCEED IN A CONTINUOUS MANNER TO COMPLETE THE PROPOSED WORK IN THAT LOCATION UNLESS OTHERWISE STATED IN THE TRAFFIC CONTROL PLANS OR AS DIRECTED BY THE ENGINEER.

DO NOT PLACE BARRIER DIRECTLY ON ANY SURFACE OTHER THAN ASPHALT OR CONCRETE.

ONCE TEMPORARY BARRIER IS INSTALLED AT ANY LOCATION AND NO WORK IS PERFORMED BEHIND THE TEMPORARY BARRIER FOR A PERIOD LONGER THAN TWO (2) MONTHS, REMOVE/RESET TEMPORARY BARRIER AT NO COST TO THE DEPARTMENT UNLESS OTHERWISE STATED IN THE TRAFFIC CONTROL PLANS, TEMPORARY BARRIER IS PROTECTING A HAZARD, OR AS DIRECTED BY THE ENGINEER.

INSTALL TEMPORARY BARRIER WITH THE TRAFFIC FLOW BEGINNING WITH THE UPSTREAM SIDE OF TRAFFIC. REMOVE TEMPORARY BARRIER AGAINST THE TRAFFIC FLOW BEGINNING WITH THE DOWNSTREAM SIDE OF TRAFFIC.

INSTALL AND SPACE DRUMS NO GREATER THAN TWICE THE POSTED SPEED LIMIT (MPH) TO CLOSE OR KEEP THE SECTION OF THE ROADWAY CLOSED UNTIL THE TEMPORARY BARRIER CAN BE PLACED OR AFTER THE TEMPORARY BARRIER IS REMOVED.

- T) PROTECT THE APPROACH END OF MOVABLE/PORTABLE CONCRETE BARRIER AT ALL TIMES DURING THE INSTALLATION AND REMOVAL OF THE BARRIER BY EITHER A TRUCK MOUNTED IMPACT ATTENUATOR (MAXIMUM 72 HOURS) OR A TEMPORARY CRASH CUSHION.

PROTECT THE APPROACH END OF MOVABLE/PORTABLE CONCRETE BARRIER FROM ONCOMING TRAFFIC AT ALL TIMES BY A TEMPORARY CRASH CUSHION UNLESS THE APPROACH END OF MOVABLE/PORTABLE CONCRETE BARRIER IS OFFSET FROM ONCOMING TRAFFIC AS FOLLOWS OR AS SHOWN IN THE PLANS:

POSTED SPEED LIMIT	MINIMUM OFFSET
40 OR LESS	4.6 M
45 - 50	6 M
55	7.6 M
60 MPH or HIGHER	9 M

TRAFFIC CONTROL DEVICES

- U) SPACE CHANNELIZING DEVICES IN WORK AREAS EQUAL IN METERS TO 2/3rds THE POSTED SPEED LIMIT (MPH), EXCEPT 3 M ON-CENTER IN RADII, AND 1 M OFF THE EDGE OF AN OPEN TRAVELWAY WHEN LANE CLOSURES ARE NOT IN EFFECT. WHEN SKINNY DRUMS ARE ALLOWED REFER TO SECTION 1180 OF STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES OR AS SHOWN IN THE PLANS.
- V) PLACE TYPE III BARRICADES, WITH "ROAD CLOSED" SIGN R11-2 ATTACHED, OF SUFFICIENT LENGTH TO CLOSE ENTIRE ROADWAY.
- W) PLACE ADDITIONAL SETS OF THREE CHANNELIZING DEVICES PERPENDICULAR TO THE EDGE OF TRAVELWAY ON 150 M CENTERS WHEN UNOPENED LANES ARE CLOSED TO TRAFFIC.

PAVEMENT MARKINGS AND MARKERS

- X) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS SHOWN IN THE PAVEMENT MARKING PLAN.
- Y) INSTALL TEMPORARY PAVEMENT MARKINGS AND TEMPORARY PAVEMENT MARKERS ON INTERIM LAYERS OF PAVEMENT AS FOLLOWS:

ROAD NAME	MARKING	MARKER
1. US 158	PAINT	TEMPORARY RAISED
2. -Y- LINES	PAINT	TEMPORARY RAISED

10/18/2011 10:53:56 AM P:\R-2414B\TrafficControl\TCP\2414b_TCP_psh2a.dgn

559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: *10/11/11*

SEAL

PROJECT NOTES

SCALE: NONE		REVISIONS
DATE: 609		
DWG. BY: CLM		
DESIGN BY: CLM		
REVIEWED BY: BAM		

PROJECT NOTES (CONT'D)

GENERAL NOTES

- Z) PLACE ONE APPLICATION OF PAINT FOR TEMPORARY TRAFFIC PATTERNS. PLACE A SECOND APPLICATION OF PAINT SIX (6) MONTHS AFTER THE INITIAL APPLICATION AND EVERY SIX MONTHS AS DIRECTED BY THE ENGINEER.
- AA) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
- BB) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS BY THE END OF EACH DAY'S OPERATION.
- CC) TRACE THE PROPOSED MONOLITHIC ISLAND LOCATIONS WITH PROPER COLOR PAVEMENT MARKINGS PRIOR TO INSTALLATION. PLACE DRUMS TO DELINEATE ANY PROPOSED MONOLITHIC ISLANDS BEFORE INSTALLATION.

TEMPORARY / FINAL SIGNALS

- DD) SHIFT AND REVISE ALL SIGNAL HEADS AS SHOWN ON THE SIGNAL PLANS.

MISCELLANEOUS

- EE) POLICE MAY BE USED TO MAINTAIN TRAFFIC THROUGH THE WORK AREA AND/OR INTERSECTIONS AS DIRECTED BY THE ENGINEER.
- FF) IN THE EVENT A TIE-IN CANNOT BE MADE IN ONE DAY'S TIME, BRING THE TIE-IN AREA TO AN APPROPRIATE ROADWAY ELEVATION AS DETERMINED BY THE ENGINEER. PLACE BLACK ON ORANGE "LOOSE GRAVEL" SIGNS (W8-7) AND BLACK ON ORANGE "PAVEMENT ENDS" SIGNS (W8-3) 1000 FT AND 500 FT RESPECTIVELY IN ADVANCE OF THE UNEVEN AREAS. USE DRUMS TO DELINEATE THE EDGE OF ROADWAY ALONG UNPAVED AREAS.
- GG) ALL WHEELCHAIR RAMP LOCATIONS SHALL BE DERIVED FROM STATIONING SHOWN ON PAVEMENT MARKING PLANS OR AS DIRECTED BY THE ENGINEER IN COORDINATION WITH THE SIGNING AND DELINEATION UNIT.

LOCAL NOTES

- 1) REFER TO SHEET TCP-31 "PORTABLE CONCRETE BARRIER AT TEMPORARY SHORING LOCATIONS" FOR MINIMUM CLEAR DISTANCES AND OFFSETS WHEN INSTALLING PORTABLE CONCRETE BARRIER FOR PROTECTION OF TEMPORARY SHORING.
- 2) COORDINATE WITH THE ENGINEER AND RAILROAD FOR SCHEDULING A WEEKEND ROAD CLOSURE ON US 158 FOR PROPOSED TRACK CROSSING REPLACEMENT AT -L- STA. 52+40+/- (SEE TCP-18A).



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-2B

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM
		TEMPORARY PAVEMENT MARKINGS
CH	YELLOW SINGLE CENTER	COLD APPLIED PLASTIC (100MM) TYPE 4 REMOVABLE TAPE
PA	WHITE EDGELINE (2X)	PAINT(100MM)
PD	0.5 M. WHITE MINISKIP (2X)	
PE	WHITE SOLID LANE LINE (2X)	
PF	3 M. YELLOW SKIP (2X)	
PH	YELLOW SINGLE CENTER (2X)	
PI	YELLOW DOUBLE CENTER (2X)	
PS	WHITE DIAGONAL (2X)	PAINT(200MM)
PV	YELLOW DIAGONAL (2X)	
P1	WHITE GORELINE (2X)	PAINT(300MM)
P3	WHITE LINE, RR X (2X)	PAINT(400MM)
P4	WHITE STOPBAR (2X)	PAINT(600MM)
QI	ALPHANUMERIC CHAR. (1X)	PAINT MARKING CHARACTERS
QA	LEFT TURN ARROW (1X)	PAINT MARKING SYMBOLS
QB	RIGHT TURN ARROW (1X)	
QC	STRAIGHT ARROW (1X)	
QE	COMBO.STRAIGHT/RIGHT (1X)	
QF	COMBO.LEFT/RIGHT (1X)	
MH	YELLOW & YELLOW	MARKERS TEMPORARY RAISED PAVEMENT MARKERS

10/18/2011 4:35:41 PM F:\N-2414B\TrafficControl\TCP\2414b-TCP_psh2B.dgn

559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *Bob A. May* DATE: 10/18/11

PROJECT NOTES AND PAVEMENT MARKING SCHEDULE

SCALE: NONE		REVISIONS
DATE: 609		
DWG. BY: CLM		
DESIGN BY: CLM		
REVIEWED BY: BAM		

CADD FILE



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-3

PHASE I

STEP 1. INSTALL ADVANCED WORK ZONE WARNING SIGNING ON US 158, AND ALL -Y- LINES ACCORDING TO TCP-32.

COORDINATE WITH THE CONTRACTOR ON ADJACENT PROJECT R-2414A FOR ANY OVERLAPPING ADVANCE WORK ZONE SIGNING UNLESS OTHERWISE DIRECTED BY THE ENGINEER.

STEP 2. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, PERFORM PROPOSED UNDERCUT EXCAVATION ALONG PROPOSED -L- WIDENING AREAS ACCORDING TO THE CONSTRUCTION PLANS EXCEPT AT THE THREE PROPOSED BOX CULVERT LOCATIONS (SEE STEP 3).

EXCAVATE ONLY AS FAR AS CAN BE BACKFILLED BY THE END OF EACH WORKDAY AND RETURN TRAFFIC TO THE EXISTING PATTERN.

STEP 3. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, BEGIN PROPOSED -L- CONSTRUCTION AND -Y- LINES AS SHOWN ON TCP-4, 5, AND 6. CONSTRUCT PROPOSED WIDENING/WEDGING UP TO, BUT NOT INCLUDING, THE FINAL LAYER OF SURFACE COURSE AND PLACE BACK MARKINGS IN THE EXISTING TRAFFIC PATTERNS.

USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, CONSTRUCT 1.0 M OF TEMPORARY PAVEMENT UP TO THE PAVEMENT ELEVATION AT EACH PROPOSED BOX CULVERT LOCATION AS SHOWN ON TCP-7, 8, AND 9.

WORK IN A CONTINUOUS MANNER TO COMPLETE THE FOLLOWING WORK IN PHASE I, STEPS 4 AND 5:

STEP 4. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, SHIFT US 158 TRAFFIC ONTO THE 1.0 M TEMPORARY PAVEMENT CONSTRUCTED IN STEP 3 AND AS SHOWN ON TCP-7, 8, AND 9.






STEP 5. OPEN US 158 TO THE TEMPORARY TWO-LANE, TWO-WAY SHIFTED TRAFFIC PATTERNS AT EACH BOX CULVERT AREA.

STEP 6. INSTALL TEMPORARY CONCRETE BARRIER FOR BOX CULVERT WORK ON EXISTING US 158 PAVEMENT AND AS SHOWN ON TCP-7, 8, AND 9.

INSTALL TEMPORARY SHORING BEHIND TEMPORARY CONCRETE BARRIER AND CONSTRUCT PROPOSED STAGE I BOX CULVERT CONSTRUCTION, UNDERCUT EXCAVATION, AND TEMPORARY/PROPOSED -L- PAVEMENT WIDENING AS SHOWN ON TCP-7, 8, AND 9.


PROPOSED -L- UNDERCUT EXCAVATION AND BACKFILL MAY CONTINUE INTO PHASE II WORK.

10/18/2011 4:58:12 PM R-2414B-TrafficControl\TCP\2414b-TCP_psh3.dgn

 <p>559 Jones Franklin Rd. Suite 164 Raleigh, N.C. 27606 Bus: 919 851 8077 Fax: 919 851 8107 License: F-0377</p> <p>TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION</p>	APPROVED: <i>Bob A. May</i> DATE: 10/21/11	<h2>PHASE I PHASING</h2>																
		<table border="1"> <tr> <td>SCALE:</td> <td>NONE</td> <td rowspan="5">  </td> <td>REVISIONS</td> </tr> <tr> <td>DATE:</td> <td>609</td> <td></td> </tr> <tr> <td>DWG. BY:</td> <td>CLM</td> <td></td> </tr> <tr> <td>DESIGN BY:</td> <td>CLM</td> <td></td> </tr> <tr> <td>REVIEWED BY:</td> <td>BAM</td> <td></td> </tr> </table>	SCALE:	NONE		REVISIONS	DATE:	609		DWG. BY:	CLM		DESIGN BY:	CLM		REVIEWED BY:	BAM	
SCALE:	NONE		REVISIONS															
DATE:	609																	
DWG. BY:	CLM																	
DESIGN BY:	CLM																	
REVIEWED BY:	BAM																	



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-4



-L- STA. 45+68.873
BEGIN STATE PROJECT R-2414B

EXISTING SIGNAL

-Y2- STA. 10+00+/-

-L- STA. 52+40+/-
EXISTING RR SIGNAL

MAINTAIN EXISTING RAILROAD SIGNALS AT CROSSING

-L- STA. 52+60+/-

-L- STA. 55+81+/-
BOX CULVERT #1
(SEE TCP-7)

-Y3- STA. 10+00+/-

-L- STA. 61+20+/-

-L- STA. 58+80+/-

EXISTING SIGNAL

MATCH LINE -L- STA. 65+60 SEE TCP-5

10/18/2011 10:53:05 AM P:\R-2414B\TrafficControl\TCP\2414b_TCP_psh4.dgn

WETHERILL ENGINEERING
 TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION


559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

APPROVED: *[Signature]* DATE: 6/21/11

SEAL

PHASE I OVERVIEW


SCALE: NONE
 DATE: 6/09
 DWG. BY: JCP
 DESIGN BY: CLM
 REVIEWED BY: BAM




REVISIONS	




PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-5



10/28/2011 8:53:55 PM
 P:\R2414B\Traffic\TrafficControl\TCP\2414b_TCP_psh5.dgn



 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *Bob A. May* DATE: *6/2/11*


PHASE I OVERVIEW



SCALE: NONE
 DATE: 6/09
 DWG. BY: JCP
 DESIGN BY: CLM
 REVIEWED BY: BAM



REVISIONS	



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-6



10/18/2011 5:22:27 PM P:\R-2414B\TrafficControl\TCP\2414b_TCP_psh6.dgn

WETHERILL ENGINEERING

559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: 6/11/11

SEAL

PROFESSIONAL ENGINEER
 SEAL 21116
 BOB A. MAY


PHASE I OVERVIEW

SCALE: NONE
 DATE: 6/09
 DWG. BY: JCP
 DESIGN BY: CLM
 REVIEWED BY: BAM

REVISIONS



NO.	DESCRIPTION

CADD FILE





PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-7



* TEMPORARY SHORING LINE #1 = EST. 33 SM

- SEE TCP-2B FOR PAVEMENT MARKING SCHEDULE
- SEE STRUCTURE PLANS FOR STAGE I BOX CULVERT
- USE TOP-MOUNTED DELINEATORS ON PORTABLE CONCRETE BARRIER

10/18/2011 1:55:42 PM P:\R-2414B\TrafficControl\TCP\2414b_TCP_psh7.dgn

W ETHERILL ENGINEERING
 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: 10/21/11

PHASE I - DETAIL A

SCALE: NONE
 DATE: 6/09
 DWG. BY: JCP
 DESIGN BY: CLM
 REVIEWED BY: BAM

SEAL: [Professional Engineer Seal for Bob A. May, License 21116]

REVISIONS	






PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-8

72

73

74

75



* TEMPORARY SHORING (LINE #2) = EST. 25 SM

- SEE TCP-2B FOR PAVEMENT MARKING SCHEDULE
- SEE STRUCTURE PLANS FOR STAGE I BOX CULVERT
- USE TOP-MOUNTED DELINEATORS ON PORTABLE CONCRETE BARRIER

10/18/2011 12:46 PM P:\R-2414B\TraficControl\TCP\2414b_TCP_psh8.dgn

WETHERILL ENGINEERING
 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: *[Date]*



SEAL
 NORTH CAROLINA PROFESSIONAL ENGINEER
 SEAL 21116
 ENGINE EX. FOR A.M.A.

PHASE I - DETAIL B

SCALE: NONE		REVISIONS
DATE: 6/09		
DESIGN BY: JCP		
REVIEWED BY: BAM		



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-9



- * TEMPORARY SHEETING (LINE #3A) = EST. 60 SM
- * TEMPORARY SHORING (LINE #3B) = EST. 26 SM

- SEE TCP-2B FOR PAVEMENT MARKING SCHEDULE
- SEE STRUCTURE PLANS FOR STAGE I BOX CULVERT
- USE TOP-MOUNTED DELINEATORS ON PORTABLE CONCRETE BARRIER

WETHERILL ENGINEERING
 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: 6/21/11

PHASE I - DETAIL C

SCALE: NONE
 DATE: 6/09
 DWG. BY: JCP
 DESIGN BY: CLM
 REVIEWED BY: BAM

SEAL: NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 21116 BOB A. MAY

REVISIONS	

10/18/2011
 P:\2414B\TrafficControl\TCP\2414b.TCP_psh9.dgn



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-10

PHASE II

STEP 1. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, COMPLETE ALL PROPOSED UNDERCUT EXCAVATION ALONG PROPOSED -L- WIDENING AREAS ACCORDING TO THE CONSTRUCTION PLANS. EXCAVATE ONLY AS FAR AS CAN BE BACKFILLED BY THE END OF EACH WORKDAY AND RETURN TRAFFIC TO THE EXISTING PATTERN.

PROPOSED -L- WIDENING MAY CONTINUE WHERE UNDERCUT EXCAVATION AND BACKFILL HAS BEEN COMPLETED ACCORDING TO PHASE II, STEP 2.

INSTALL AND COVER TEMPORARY TRAFFIC SIGNAL #2 AT SR 1139 (COUNTRY CLUB ROAD) AS SHOWN ON TCP-14 AND THE SIGNAL PLANS.

STEP 2. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, BEGIN PHASE II -L- WIDENING AND -Y- LINES AS SHOWN ON TCP-11, 12, AND 13. MAINTAIN EXISTING TRAFFIC SIGNAL OPERATIONS AT THE FOLLOWING INTERSECTION:

NC 343
SR 1145 (BELCROSS ROAD/LAMBS ROAD)

PLACE PAVEMENT MARKINGS AND MARKERS AS MUCH AS POSSIBLE FOR THE TEMPORARY TRAFFIC PATTERN FROM -L- STA. 47+20+/- TO STA. 49+00+/- AS SHOWN ON TCP-14.

WORK IN A CONTINUOUS MANNER TO COMPLETE THE FOLLOWING WORK IN PHASE II, STEPS 7 AND 8:

STEP 7. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, SHIFT US 158 TRAFFIC ONTO THE TEMPORARY DETOURS AT EACH OF THE THREE BOX CULVERT LOCATIONS AS SHOWN ON TCP-16, 17, AND 18.

INSTALL REMAINING TEMPORARY CONCRETE BARRIER FOR BOX CULVERT WORK AT EACH OF THE THREE BOX CULVERT DETOURS.

STEP 8. OPEN US 158 TO THE TEMPORARY TWO-LANE, TWO-WAY SHIFTED TRAFFIC PATTERNS AT EACH AT EACH OF THE THREE BOX CULVERT LOCATIONS.

STEP 9. CONSTRUCT PROPOSED STAGE II BOX CULVERT CONSTRUCTION, UNDERCUT EXCAVATION, AND PROPOSED -L- WIDENING AS SHOWN ON TCP-16, 17, AND 18.

WORK IN A CONTINUOUS MANNER TO COMPLETE PHASE II, STEPS 3 AND 4 ON A WEEKEND FROM SATURDAY NIGHT AT 9:00PM UNTIL MONDAY MORNING AT 7:00AM (SEE INTERMEDIATE CONTRACT TIME AND LIQUIDATED DAMAGES):

STEP 3. USING POLICE AND ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, PLACE EXISTING SIGNAL IN FLASH MODE AT THE INTERSECTION OF US 158 AND SR 1139 (COUNTRY CLUB ROAD).

STEP 4. SHIFT US 158 AND SR 1139 (COUNTRY CLUB ROAD) TRAFFIC TO THE TEMPORARY TRAFFIC PATTERN IN A TWO-LANE, TWO-WAY PATTERN AS SHOWN ON TCP-14.

ACTIVATE TEMPORARY TRAFFIC SIGNAL #2 AND OPEN US 158 AND SR 1139 (COUNTRY CLUB ROAD).






STEP 5. USING ROADWAY STANDARD DRAWING 1101.03, SHT. 1 AND 2 OF 9, AND LOCAL NOTE #2, CLOSE US 158 AND PLACE TRAFFIC ON THE TEMPORARY OFF-SITE DETOUR AS SHOWN ON TCP-18A (PROPOSED TRACK CROSSING WORK AT -L- STA. 52+40+/- WILL BE PERFORMED BY OTHERS AS SHOWN ON TPC-15).

(PARTIAL TRACK CROSSING WORK LOCATED AT -L- STA. 92+35+/- WILL BE PERFORMED BY OTHERS AS PART OF PROPOSED -L- LEFT SIDE WIDENING AND AS SHOWN ON TCP-13).

STEP 6. PLACE PAVEMENT MARKINGS AND MARKERS AS MUCH AS POSSIBLE AT EACH OF THE THREE BOX CULVERT DETOUR LOCATIONS AND AS SHOWN ON TCP-16, 17, AND 18.


INSTALL TEMPORARY CONCRETE BARRIER AS MUCH AS POSSIBLE AT EACH OF THE THREE BOX CULVERT TEMPORARY DETOURS AND AS SHOWN ON TCP-16, 17, AND 18.

10/18/2011 4:39:16 PM P:\R-2414B\TrafficControl\TCP\2414b-TCP_psh10.dgn

 <p>559 Jones Franklin Rd. Suite 164 Raleigh, N.C. 27606 Bus: 919 851 8077 Fax: 919 851 8107 License: F-0377</p> <p>TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION</p>	APPROVED: <i>Bob A. May</i> DATE: 10/21/11	<h2>PHASE II PHASING</h2>																		
		<table border="1"> <tr> <td>SCALE:</td> <td>NONE</td> <td rowspan="5">  </td> <td>REVISIONS</td> </tr> <tr> <td>DATE:</td> <td>609</td> <td></td> </tr> <tr> <td>DWG. BY:</td> <td>CLM</td> <td></td> </tr> <tr> <td>DESIGN BY:</td> <td>CLM</td> <td></td> </tr> <tr> <td>REVIEWED BY:</td> <td>BAM</td> <td></td> </tr> </table>	SCALE:	NONE		REVISIONS	DATE:	609		DWG. BY:	CLM		DESIGN BY:	CLM		REVIEWED BY:	BAM		<table border="1"> <tr> <td>CADD FILE</td> <td></td> </tr> </table>	CADD FILE
SCALE:	NONE		REVISIONS																	
DATE:	609																			
DWG. BY:	CLM																			
DESIGN BY:	CLM																			
REVIEWED BY:	BAM																			
CADD FILE																				



PROJ. REFERENCE NO. R-2414B	SHEET NO. TCP-12
--------------------------------	---------------------



10/18/2011
 4:44:07 PM
 P:\R-2414B\TrafficControl\TCP\2414b_TCP.psd(2.dgn)

559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: *6/2/11*



NORTH CAROLINA
 PROFESSIONAL
 SEAL
 21116
 ENGINEER
 FOR A MAY

SEAL


PHASE II OVERVIEW			REVISIONS
SCALE: NONE	DATE: 6/09		
DWG. BY: JCP	DESIGN BY: CLM	REVIEWED BY: BAM	
		CADD FILE	



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-13




10/18/2011 5:23:12 PM P:\R-2414B\TrafficControl\TCP\2414b-TCP_psh3.dgn



 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: 6/21/11



 SEAL
 BOB A. MAY
 ENGINEER
 21116

PHASE II OVERVIEW		REVISIONS	
SCALE:	NONE		
DATE:	6/09		
DWG. BY:	JCP		
DESIGN BY:	CLM		
REVIEWED BY:	BAM		



CADD FILE


-L- STA. 45+68.873
BEGIN STATE PROJECT R-2414B



REFER TO PROJECT R-2414A FINAL PAVEMENT MARKING PLAN FOR TRAFFIC PATTERN



-SEE SIGNAL PLANS FOR TEMPORARY SIGNAL #2 DESIGN
-SEE TCP-2B FOR PAVEMENT MARKING SCHEDULE



W W ETHERILL ENGINEERING
559 Jones Franklin Rd. Suite 164
Raleigh, N.C. 27606
Bus: 919 851 8077
Fax: 919 851 8107
License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: [Signature] DATE: 12-19-11

PHASE II - DETAIL A

SCALE: NONE
DATE: 6/09
DWG. BY: JCP
DESIGN BY: CLM
REVIEWED BY: BAM




REVISIONS

SEAL: [Professional Engineer Seal for Robert A. May, License No. 21116]

12/19/2011
 R:\2414B\Traffic\TrafficControl\TCP\2414b_TCP_psh4.dgn




PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-15




- SEE TCP-18A FOR TEMPORARY OFF-SITE DETOUR ROUTE FOR US 158 WHILE PROPOSED CONCRETE TRACK CROSSING IS INSTALLED BY OTHERS.
- SEE SIGNAL PLANS FOR WORK SEQUENCE AT EXISTING RAILROAD CROSSING BY OTHERS.

I:\18\2011
 4\4\6\6\B\B
 P:\R-2414B\Traffic\TrafficContr\TCP\2414b_TCP_psh5.dgn



 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: 6/21/11


PHASE II - DETAIL B



SCALE:	NONE
DATE:	6/09
DWG. BY:	JCP
DESIGN BY:	CLM
REVIEWED BY:	BAM



REVISIONS	



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-17



- SEE TCP-2B FOR PAVEMENT MARKING SCHEDULE
- SEE RSD 1101.03 (SHT. 3 OF 9) FOR TEMPORARY ONSITE DETOUR SIGNING
- SEE STRUCTURE PLANS FOR STAGE II BOX CULVERT
- USE TOP-MOUNTED DELINEATORS ON PORTABLE CONCRETE BARRIER

WETHERILL ENGINEERING

559 Jones Franklin Rd. Suite 164
Raleigh, N.C. 27606
Bus: 919 851 8077
Fax: 919 851 8107
License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: 1/9/12

SEAL: **PROFESSIONAL ENGINEER SEAL 21116 BOB A. MAY**




PHASE II - DETAIL D

SCALE: NONE		REVISIONS
DATE: 6/09		
DWG. BY: JCP		
DESIGN BY: CLM		
REVIEWED BY: BAM		

1/9/2012 8:33:56 AM
 P:\R-2414B\Traffic\TrafficControl\ICP\2414b_ICP_psh17.dwg




PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-18




- SEE TCP-2B FOR PAVEMENT MARKING SCHEDULE
- SEE RSD 1101.03 (SHT. 3 OF 9) FOR TEMPORARY ONSITE DETOUR SIGNING
- SEE STRUCTURE PLANS FOR STAGE II BOX CULVERT
- USE TOP-MOUNTED DELINEATORS ON PORTABLE CONCRETE BARRIER


1/9/2009 8:42:54 AM
 R:\R-2414B\TrafficControl\TCP\2414b_TCP.dwg




 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: 1/9/12
 SEAL: 

PHASE II - DETAIL E

SCALE: NONE		REVISIONS
DATE: 6/09		
DWG. BY: JCP		
DESIGN BY: CLM		
REVIEWED BY: BAM		



- LOCATE CMS APPROX. 1 MILE IN ADVANCE OF EACH DETOUR POINT ON US 158.
- TEMPORARY SIGNING TO BE PAID FOR AS "STATIONARY WORK ZONE SIGNS".
- SEE ROADWAY STANDARD DRAWING 1101.03, SHEET 1 AND 2 OF 9, FOR ADDITIONAL TEMPORARY OFF-SITE DETOUR SIGNING REQUIREMENTS.

WETHERILL ENGINEERING
 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: 10/21/11

SEAL
 NORTH CAROLINA PROFESSIONAL ENGINEER
 SEAL 21116
 BOB A. MAY

US 158 ROAD CLOSURE AND OFF-SITE DETOUR

SCALE: NONE	REVISIONS
DATE: 10/09	
DWG. BY: CLM	
DESIGN BY: CLM	
REVIEWED BY: BAM	

14-DAY COUNTDOWN SEQUENCE TO BE DISPLAYED ON BOTH SIGNS PRIOR TO CLOSING US 158 TO TRAFFIC.

10/18/2011 10:13:55 AM P:\R-2414B\TrafficControl\TCP\2414b_TCP_psh18A.dgn



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-19

PHASE III

STEP 1. INSTALL AND COVER TEMPORARY TRAFFIC SIGNAL #3 AT -Y3- (NC 343) AS SHOWN ON THE SIGNAL PLANS AND AS SHOWN ON TCP-24.

USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, REMOVE PHASE II TEMPORARY CONCRETE BARRIER AT EACH OF THE THREE BOX CULVERT LOCATIONS AND REPLACE WITH DRUMS.

WORK IN A CONTINUOUS MANNER TO COMPLETE THE FOLLOWING WORK IN PHASE III, STEP 2:

STEP 2. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, SHIFT US 158 TRAFFIC TO THE TRAFFIC PATTERNS SHOWN AT EACH OF THE THREE BOX CULVERT LOCATIONS ON TCP-23, 27, AND 28.

USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, COMPLETE -L- RIGHT SIDE CURB & GUTTER AND DRIVEWAY WORK AS SHOWN ON TCP-27.

STEP 3. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, REMOVE TEMPORARY DETOUR PAVEMENT AT EACH OF THE THREE BOX CULVERT LOCATIONS AND CONSTRUCT -L- PAVEMENT AND CURB & GUTTER, AND GUARDRAIL AS SHOWN ON TCP-23, 27, AND 28.

WORK IN A CONTINUOUS MANNER TO COMPLETE PHASE III, STEP 4 ON A WEEKEND FROM SATURDAY NIGHT AT 9:00PM UNTIL MONDAY MORNING AT 7:00AM (SEE INTERMEDIATE CONTRACT TIME AND LIQUIDATED DAMAGES):

STEP 4. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, PERFORM WORK AT THE EXISTING INTERSECTION OF US 158 AND NC 343 ACCORDING TO THE FOLLOWING WORK SEQUENCE AND TCP-24 & TCP-25:

- A) PLACE PAVEMENT MARKINGS AND MARKERS AS MUCH AS POSSIBLE FOR THE -Y3- (NC 343) TEMPORARY TRAFFIC PATTERN
- B) SHIFT -Y3- (NC 343) TRAFFIC TO THE TEMPORARY PATTERN
- C) ACTIVATE TEMPORARY TRAFFIC SIGNAL #3 AS SHOWN IN THE SIGNAL PLANS
- D) PLACE REMAINING PAVEMENT MARKINGS AND MARKERS FOR THE TEMPORARY -Y3- (NC 343) TRAFFIC PATTERN

STEP 5. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, COMPLETE -Y3- & -Y4- (NC 343) LEFT SIDE SHOULDER AND CURB & GUTTER WORK AS SHOWN ON TCP-24 AND 25.

WORK IN A CONTINUOUS MANNER TO COMPLETE THE FOLLOWING WORK IN PHASE III, STEP 6:

STEP 6. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, PERFORM WORK AT THE EXISTING INTERSECTION OF US 158 AND GUMBERRY ROAD ACCORDING TO THE FOLLOWING WORK SEQUENCE AND AS SHOWN ON TCP-26:

- A) PLACE PAVEMENT MARKINGS AND MARKERS AS MUCH AS POSSIBLE FOR THE US 158 TEMPORARY TRAFFIC PATTERN
- B) SHIFT US 158 TRAFFIC TO THE TEMPORARY PATTERN AND PLACE REMAINING PAVEMENT MARKINGS AND MARKERS FOR THE SR 1240 & SR 1142 (GUMBERRY ROAD) FINAL TRAFFIC PATTERNS
- C) COMPLETE SR 1240 (GUMBERRY ROAD) INTERSECTION WORK

STEP 7. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, CONSTRUCT TEMPORARY PAVEMENT AT THE EXISTING US 158 AND NC 34 INTERSECTION AS SHOWN ON TCP-22 AND AS SHOWN ON THE CONSTRUCTION PLANS.

PLACE PAVEMENT MARKINGS AND MARKERS AS MUCH AS POSSIBLE FOR THE TEMPORARY TRAFFIC PATTERN AT THE US 158 AND NC 34 INTERSECTION AS SHOWN ON TCP-29.

PLACE CHANGEABLE MESSAGE SIGNS ON US 158 AND NC 34 FOR -Y8- INTERSECTION WORK AS SHOWN ON TCP-28 AND 29.

STEP 8. USING POLICE AND ROADWAY STANDARD DRAWINGS 1101.02, SHT. 1 OF 9, AND 1101.03, SHT 8 OF 9, PERFORM WORK AT THE INTERSECTION OF US 158 AND NC 34 ACCORDING TO THE FOLLOWING WORK SEQUENCE AND AS SHOWN ON TCP-29:

- A) PLACE PAVEMENT MARKINGS FOR THE RELOCATED TEMPORARY INTERSECTION FOR US 158 AND NC 34. PLACE TYPE III BARRICADES TO CLOSE THE EXISTING INTERSECTION AND SIMULTANEOUSLY OPEN THE TEMPORARY INTERSECTION TO TRAFFIC. PLACE REMAINING PAVEMENT MARKINGS AND SYMBOLS FOR THE TEMPORARY INTERSECTION PATTERN.
- B) RELOCATE/ADJUST EXISTING INTERSECTION SIGNING AS REQUIRED.

STEP 9. INSTALL TEMPORARY CONCRETE BARRIER ON THE EXISTING NC 34 NORTHBOUND RAMP AND ALONG THE RIGHT SIDE OF EXISTING NC 34 AS SHOWN ON TCP-29.

STEP 10. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, CONSTRUCT PROPOSED -Y8- INTERSECTION AS MUCH AS POSSIBLE AS SHOWN ON TCP-29.

INSTALL AND COVER TEMPORARY TRAFFIC SIGNAL #1 AT US 158 AND NC 34 AS SHOWN ON TCP-30 AND THE SIGNAL PLANS.

STEP 11. INSTALL TYPE III BARRICADES AND CLOSE THE EXISTING NC 34 NORTHBOUND RAMP.

STEP 12. USING ROADWAY STANDARD DRAWINGS 1101.02, SHT. 1 OF 9, CONSTRUCT PROPOSED -L- LEFT SIDE WIDENING SECTION FROM STA. 91+47+/- TO STA. 91+67+/-, AND THE -Y8- LEFT SIDE WIDENING FROM -Y8- STA. 11+00+/- TO STA. 11+90+/- UP TO, BUT NOT INCLUDING, THE FINAL LAYER OF SURFACE COURSE AS SHOWN ON TCP-29A.

WORK IN A CONTINUOUS MANNER TO COMPLETE PHASE III, STEPS 13 & 14 ON A WEEKEND FROM SATURDAY NIGHT AT 9:00PM UNTIL MONDAY MORNING AT 7:00AM (SEE INTERMEDIATE CONTRACT TIME AND LIQUIDATED DAMAGES):

STEP 13. USING POLICE AND ROADWAY STANDARD DRAWINGS 1101.02, SHT. 1 OF 9, SIMULTANEOUSLY SHIFT US 158 EASTBOUND AND NC 34 TRAFFIC ONTO -Y8- IN A ONE-LANE, TWO-WAY PATTERN.

WEDGE AND CONSTRUCT -Y8- RIGHT SIDE WIDENING FROM -Y8- STA. 11+00+/- TO STA. 11+90+/- UP TO, BUT NOT INCLUDING, THE FINAL LAYER OF SURFACE COURSE AS SHOWN ON TCP-29B.

PLACE PAVEMENT MARKINGS AND MARKERS AS MUCH AS POSSIBLE FOR THE TEMPORARY SIGNALIZED US 158 AND NC 34 INTERSECTION AS SHOWN ON TCP-30.

STEP 14. OPEN THE TEMPORARY SIGNALIZED US 158 AND NC 34 INTERSECTION AS SHOWN ON TCP-30. PLACE TYPE III BARRICADES TO CLOSE OFF THE EXISTING NC 34 UNUSED ROADWAY SECTION TO TRAFFIC.

STEP 15. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, OBLITERATE REMAINING NC 34 PAVEMENT AS SHOWN ON TCP-30 AND THE CONSTRUCTION PLANS.

CONSTRUCT -L- RIGHT SIDE WIDENING AND CURB & GUTTER ON US 158 EASTBOUND FROM STA. 91+00+/- TO STA. 93+90+/- AS SHOWN ON TCP-30 AND IN THE CONSTRUCTION PLANS.

INSTALL & COVER PERMANENT TRAFFIC SIGNALS FOR -L- AND -Y-, -Y3-/-Y4-, AND -Y8- INTERSECTIONS AS SHOWN ON PMP-3, 7, AND 10 OF THE PAVEMENT MARKING PLAN, AND ON THE SIGNAL PLANS.

INSTALL PERMANENT GROUND MOUNTED SIGNING FOR THE PROJECT AS SHOWN IN THE SIGNING PLANS.

STEP 16. USING ROADWAY STANDARD DRAWING 1101.02, SHT. 1 OF 9, PLACE FINAL LAYER AND FINAL PAVEMENT MARKINGS AND MARKERS IN THE FINAL TRAFFIC PATTERN ON -L- AND ALL -Y- LINES AS SHOWN ON PMP-1 THRU PMP-11 OF THE PAVEMENT MARKING PLAN. CONSTRUCT PROPOSED MONOLITHIC CONCRETE ISLANDS AT LOCATIONS AS SHOWN IN THE CONSTRUCTION PLANS. ACTIVATE PERMANENT SIGNALS AT -Y-, -Y3-/-Y4- (NC 343), AND -Y8- INTERSECTIONS WITH -L- (US 158/NC 34).

REFER TO PMP-2 OF THE PAVEMENT MARKING PLAN FOR TRANSITION DETAIL WHEN TIEING FINAL 5-LANE PATTERN TO 2-LANE TRAFFIC PATTERN AT THE END OF THE WORKDAY.



STEP 17. REMOVE ALL TRAFFIC CONTROL DEVICES FROM THE PROJECT.

10/18/2011 4:44:47 PM P:\R-2414B\TrafficControl\TCP\Y-2414b_TCP_psh19.dgn


<p>559 Jones Franklin Rd. Suite 164 Raleigh, N.C. 27606 Bus: 919 851 8077 Fax: 919 851 8107 License: F-0377</p> <p>TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION</p>	APPROVED: <i>[Signature]</i> DATE: <i>[Date]</i>	<h2>PHASE III PHASING</h2>									
		SCALE: NONE DATE: 609 DWG. BY: CLM DESIGN BY: CLM REVIEWED BY: BAM		REVISIONS <table border="1"> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </table>							




PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-20





10/18/2011
 4:45:35 PM
 P:\R-2414B\TrafficControl\TCP\2414b_TCP_psh20.dgn


 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377


TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *Bob A May* DATE: *6/2/10*



PHASE III OVERVIEW		REVISIONS	
SCALE:	NONE		
DATE:	6/09		
DWG. BY:	JCP		
DESIGN BY:	CLM		
REVIEWED BY:	BAM		
			




PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-21




10/18/2011 4:46:16 PM
 P:\R-2414B\TrafficControl\TCP\2414b_TCP_psh21.dgn


 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION



APPROVED: *[Signature]* DATE: *[Date]*


PHASE III OVERVIEW

SCALE: NONE		REVISIONS
DATE: 6/09		
DWG. BY: JCP		
DESIGN BY: CLM		
REVIEWED BY: BAM		



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-22



- SEE TCP-29 FOR PAVEMENT MARKINGS FOR TEMPORARY INTERSECTION SHOWN ABOVE.

10/18/2011
 4:47:04 PM
 P:\R-2414B\TrafficControl\TCP\2414b_TCP_psh22.dgn

WETHERILL ENGINEERING

559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION


APPROVED: *M. A. May* DATE: *6/10/09*

SEAL

NORTH CAROLINA PROFESSIONAL ENGINEER
 SEAL 21116
 ENGINEER
 BOB A. MAY

PHASE III OVERVIEW

SCALE:	NONE
DATE:	6/09
DWG. BY:	JCP
DESIGN BY:	CLM
REVIEWED BY:	BAM





REVISIONS	

CADD FILE



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-23



- SEE TCP-2B FOR PAVEMENT MARKING SCHEDULE

10/18/2011 12:26:06 PM P:\R-2414B\TrafficControl\TCP\2414b-TCP_psh23.dgn

WETHERILL ENGINEERING

559 Jones Franklin Rd. Suite 164
Raleigh, N.C. 27606
Bus: 919 851 8077
Fax: 919 851 8107
License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *bl a May* DATE: *6/9/09*

SEAL

PHASE III - DETAIL A



SCALE: NONE
DATE: 6/09
DWG. BY: JCP
DESIGN BY: CLM
REVIEWED BY: BAM

REVISIONS	



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-24

MATCHLINE -Y3- STA. 10+40 SEE TCP-25



12/19/2011 2:02:37 PM P:\R-2414B\TrafficControl\TCP\Yr-2414b_TCP_psh24.dgn

TEMPORARY SIGNAL #3

- SEE TCP-2B FOR PAVEMENT MARKING SCHEDULE
- SEE SIGNAL PLANS FOR TEMPORARY SIGNAL #3 DESIGN

WETHERILL ENGINEERING

559 Jones Franklin Rd. Suite 164
Raleigh, N.C. 27606
Bus: 919 851 8077
Fax: 919 851 8107
License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION



APPROVED: *[Signature]* DATE: 12-19-11

SEAL

PHASE III - DETAIL B	
SCALE: NONE	REVISIONS
DATE: 6/09	
DWG. BY: JCP	
DESIGN BY: CLM	
REVIEWED BY: BAM	



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-25



- SEE TCP-2B FOR PAVEMENT MARKING SCHEDULE

10/18/2011
 4:48:42 PM
 P:\R-2414B\TrafficControl\TCP\Y-24\4b_TCP_psh25.dgn



559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *[Signature]* DATE: *6/10/09*




PHASE III - DETAIL C

SCALE: NONE		REVISIONS
DATE: 6/09		
DWG. BY: JCP		
DESIGN BY: CLM		
REVIEWED BY: BAM		



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-26




MESSAGE NO. 1	MESSAGE NO. 2
NEW TRAFFIC PATTERN	AT GUMBERRY ROAD
CHANGEABLE MESSAGE SIGN	

MESSAGE NO. 1	MESSAGE NO. 2
NEW TRAFFIC PATTERN	AT GUMBERRY ROAD
CHANGEABLE MESSAGE SIGN	


- LOCATE CHANGEABLE MESSAGE SIGNS APPROX. 1/2 MILE IN ADVANCE OF INTERSECTION.
- SEE TCP-2B FOR PAVEMENT MARKING SCHEDULE

12/18/2011 2:03:06 PM
 P:\R-2414B\TrafficControl\TCP\2414b_TCP_psh26.dgn


WETHERILL ENGINEERING
 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION



APPROVED: *[Signature]* DATE: 12-11-11
PHASE III - DETAIL D

SCALE: NONE		REVISIONS
DATE: 6/09		
DWG. BY: JCP		
DESIGN BY: CLM		
REVIEWED BY: BAM		


DIVISION OF HIGHWAY SAFETY
 STATE OF NORTH CAROLINA
 TRAFFIC CONTROL



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-27




71





72

73



74



- SEE TCP-2B FOR PAVEMENT MARKING SCHEDULE

10/18/2011 10:30 AM P:\R-2414B\TrafficControl\TCP-2414b-TCP_psh27.dgn

WETHERILL ENGINEERING
559 Jones Franklin Rd. Suite 164
Raleigh, N.C. 27606
Bus: 919 851 8077
Fax: 919 851 8107
License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *Bob A. May* DATE: *6/2/11*

SEAL
NORTH CAROLINA PROFESSIONAL ENGINEER
SEAL 21116
ENGINEER
BOB A. MAY



PHASE III - DETAIL E

SCALE: NONE		<table border="1"> <tr><th colspan="2">REVISIONS</th></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </table>	REVISIONS									
REVISIONS												
DATE: 6/09												
DWG. BY: JCP												
DESIGN BY: CLM												
REVIEWED BY: BAM												


CADD FILE



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-28



MESSAGE NO. 1	MESSAGE NO. 2
NEW TRAFFIC PATTERN	AT NC 34
CHANGEABLE MESSAGE SIGN	



- SEE TCP-2B FOR PAVEMENT MARKING SCHEDULE

WETHERILL ENGINEERING
 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *Rob A. May* DATE: *6/2/10*

SEAL:

PHASE III - DETAIL F



SCALE: NONE		REVISIONS
DATE: 6/09		
DWG. BY: JCP		
DESIGN BY: CLM		
REVIEWED BY: BAM		

10/18/2009
 10:18:15 AM
 P:\R-2414B\TrafficControl\TCP\2414b_TCP_psh28.dgn



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-29

MESSAGE NO. 1	MESSAGE NO. 2
NEW TRAFFIC PATTERN	AT US 158
CHANGEABLE MESSAGE SIGN	



- SEE TCP-22 FOR NC 34 TEMPORARY PAVEMENT LAYOUT ON NC 34
- RELOCATE EXISTING INTERSECTION TYPE "D", "E", AND "F" SIGNING AS DIRECTED BY THE ENGINEER
- USE TOP-MOUNTED DELINEATORS ON PORTABLE CONCRETE BARRIER

WETHERILL ENGINEERING

559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *Bob A. May* DATE: *10/2/10*

SEAL

PHASE III - DETAIL G

SCALE: NONE

DATE: _____

DWG. BY: _____

DESIGN BY: _____

REVIEWED BY: _____

REVISIONS


NO.	DESCRIPTION

CADD FILE


10/18/2010 4:59:40 PM
 P:\AR-2414B-TrafficControl\TCP\2414b_TCP_psh29.dgn



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-29A



- SEE TCP-29 FOR PAVEMENT MARKING STATIONING AND CODES EXCEPT AS NOTED.
- RELOCATE EXISTING INTERSECTION TYPE "D", "E", AND "F" SIGNING AS DIRECTED BY THE ENGINEER



WETHERILL ENGINEERING
 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION

APPROVED: *Bob A. May* DATE: *10/21/11*

SEAL
 NORTH CAROLINA
 PROFESSIONAL
 SEAL
 21116
 ENGINEER
 BOB A. MAY

PHASE III - DETAIL H

SCALE: NONE

DATE: _____

DWG. BY: _____

DESIGN BY: _____

REVIEWED BY: _____

REVISIONS



CADD FILE

10/18/2011 4:55:29 PM
 P:\R-2414B\TrafficControl\TCP-29A.dgn




PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-29B

USE ROADWAY STANDARD DWG. 1101.02, SHT. 1 OF 9



- SEE TCP-29 FOR PAVEMENT MARKING STATIONING AND CODES EXCEPT AS NOTED.
- ADJUST EXISTING INTERSECTION TYPE "D", "E", AND "F" SIGNING AS DIRECTED BY THE ENGINEER



WETHERILL ENGINEERING
 559 Jones Franklin Rd. Suite 164
 Raleigh, N.C. 27606
 Bus: 919 851 8077
 Fax: 919 851 8107
 License: F-0377

TRANSPORTATION PLANNING/DESIGN - BRIDGE/STRUCTURE DESIGN
 CIVIL/SITE DESIGN - GIS/GPS - CONSTRUCTION OBSERVATION


APPROVED: *[Signature]* DATE: 5/21/09

SEAL
 NORTH CAROLINA PROFESSIONAL ENGINEER
 SEAL 21116
 ENG. IN EX. JOB A. MAY

PHASE III - DETAIL I

SCALE: NONE		<table border="1"> <tr><th colspan="2">REVISIONS</th></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> <tr><td> </td><td> </td></tr> </table>	REVISIONS							
REVISIONS										
DATE: 5/09										
DWG. BY: CLM										
DESIGN BY: CLM										
REVIEWED BY: BAM	CADD FILE									

10/18/2011 4:51:58 PM P:\R-2414B\TrafficControl\TCP\2414b_TCP_psh29B.dgn



NOTE: WALL OR SHORING HEIGHT = A - B

FIGURE A

NOTES

- REFER TO THE TRAFFIC CONTROL PLANS FOR SHORING LOCATIONS AND SOIL PARAMETERS.
- REFER TO THE "TEMPORARY SHORING" PROJECT SPECIAL PROVISION FOR MORE INFORMATION ABOUT TEMPORARY SHORING, MEASUREMENT AND PAYMENT.
- PROVIDE PORTABLE CONCRETE BARRIER TO PROTECT TEMPORARY SHORING IF SHORING IS LOCATED WITHIN THE CLEAR ZONE AS DEFINED IN THE AASHTO ROADSIDE DESIGN GUIDE. DO NOT PLACE BARRIER DIRECTLY ON ANY SURFACE OTHER THAN ASPHALT OR CONCRETE. (CONTACT NCDOT PAVEMENT MANAGEMENT UNIT FOR APPLICABLE PAVEMENT DESIGN).
- BASED ON THE CLEAR DISTANCE, OFFSET, DESIGN SPEED AND PAVEMENT TYPE, CHOOSE AN UNANCHORED PCB, ANCHORED PCB OR AN OREGON BARRIER FROM THE TABLE SHOWN IN FIGURE B. FOR TRAFFIC LANES AND PORTABLE CONCRETE BARRIER LOCATED ABOVE AND BEHIND TEMPORARY SHORING, THE FOLLOWING ARE DEFINED AS:
 - CLEAR DISTANCE - HORIZONTAL DISTANCE FROM THE BACK FACE OF THE BARRIER TO THE EDGE OF PAVEMENT FOR TEMPORARY MSE WALL OR TO THE FACE OF NON-ANCHORED TEMPORARY SHORING AS SHOWN IN FIGURE A.
 - OFFSET - HORIZONTAL DISTANCE FROM THE FRONT FACE OF THE BARRIER TO CENTERLINE OF THE FURTHEST TRAFFIC LANE AS SHOWN IN FIGURE B FOR 3 TRAFFIC LANES.
- AT THE CONTRACTOR'S OPTION OR IF THE MINIMUM REQUIRED CLEAR DISTANCE IS NOT AVAILABLE, SET AN UNANCHORED PCB AGAINST THE TRAFFIC SIDE OF THE SHORING AND DESIGN SHORING FOR TRAFFIC IMPACT OR USE THE "SURCHARGE CASE WITH TRAFFIC IMPACT" FOR THE STANDARD TEMPORARY SHORING. DO NOT PLACE BARRIER DIRECTLY ON ANY SURFACE OTHER THAN ASPHALT OR CONCRETE. (CONTACT NCDOT PAVEMENT MANAGEMENT UNIT FOR APPLICABLE PAVEMENT DESIGN).
- USE NCDOT PORTABLE CONCRETE BARRIER (PCB) IN ACCORDANCE WITH ROADWAY STANDARD DRAWING NO. 1170.01 AND SECTION 1170 OF THE STANDARD SPECIFICATIONS.
- USE OREGON TALL F-SHAPE CONCRETE BARRIER IN ACCORDANCE WITH DETAIL DRAWING AND SPECIAL PROVISION OBTAINED FROM: WORK ZONE TRAFFIC CONTROL UNIT WEB PAGE.
- UNLESS NOTED OTHERWISE ON THE PLANS, SET PORTABLE CONCRETE BARRIER WITH A MINIMUM DISTANCE OF 2 FT BETWEEN THE FRONT FACE OF THE BARRIER AND THE EDGE OF THE NEAREST TRAFFIC LANE AS SHOWN IN FIGURE A.
- FOR PORTABLE CONCRETE BARRIER ABOVE AND BEHIND TEMPORARY MSE WALLS, PROVIDE A MINIMUM DISTANCE OF 3 FT BETWEEN THE EDGE OF PAVEMENT AND THE WALL FACE AS SHOWN IN FIGURE A. IF THESE MINIMUM REQUIRED DISTANCES ARE NOT AVAILABLE, CONTACT THE ENGINEER.
- TABLE SHOWN IN FIGURE B IS BASED ON NCDOT RESEARCH PROJECT NO. 2005-010 WITH VEHICLE TYPE USED FOR NCHRP 350 CRASH TESTS. BARRIER DEFLECTIONS AND RESULTING MINIMUM REQUIRED CLEAR DISTANCES MIGHT VARY SIGNIFICANTLY FOR LARGER HEAVIER VEHICLES, RUNS OF BARRIER LESS THAN 200' IN LENGTH AND WET OR DRY PAVEMENT.

MINIMUM REQUIRED CLEAR DISTANCE, inches

Barrier Type	Pavement Type	Offset * ft	Design Speed, mph					
			<30	31-40	41-50	51-60	61-70	71-80
Unanchored PCB	Asphalt	<8	24	26	29	32	36	40
		8-14	26	28	31	35	38	42
		14-20	27	29	34	36	39	43
		20-26	28	31	35	38	40	44
		26-32	29	32	36	39	42	45
		32-38	30	34	38	41	43	46
		38-44	31	34	41	43	45	48
		44-50	31	35	41	43	46	49
		50-56	32	36	42	44	47	50
	>56	32	36	42	45	47	51	
	Concrete	<8	17	18	21	22	25	26
		8-14	19	20	23	25	26	29
		14-20	22	22	24	26	28	31
		20-26	23	24	26	27	30	34
		26-32	24	25	27	28	32	35
		32-38	24	26	27	30	33	36
		38-44	25	26	28	30	34	37
		44-50	26	26	28	32	35	37
50-56		26	26	28	32	35	38	
>56	26	27	29	32	36	38		
Anchored PCB or Oregon Barrier	Asphalt	All Offsets	24 for All Design Speeds					
Anchored PCB or Oregon Barrier	Concrete (including bridge approach slabs)	All Offsets	12 for All Design Speeds					

* See Figure Below




FIGURE B

APPROVED: _____ DATE: _____			PORTABLE CONCRETE BARRIER AT TEMPORARY SHORING LOCATIONS

28-MAY-2010 08:52 \\D:\DOT\SR00101\GROUPS-WZTCC\WZTC\Apps\WorkZoneGeneral\ExternalWebPage\DesRes\English\TemporaryShoring\Barrier-STD.dgn mgarratt AT WZTC24747



PROJ. REFERENCE NO.	SHEET NO.
R-2414B	TCP-31A

Temporary Shoring No. 1

FOR TEMPORARY SHORING, SEE TEMPORARY SHORING PROVISION.

DO NOT USE STANDARD SHORING FROM STA. 55+70 +/- -L- TO STA. 55+90 +/- -L- 4.8 M +/- -RIGHT. USE CONTRACTOR DESIGNED SHORING FOR THIS LOCATION.

FOR CONTRACTOR DESIGNED SHORING FROM STA. 55+70 +/- TO STA. 55+90 +/- -L- 4.8 m +/- RIGHT, DESIGN SHORING FOR THE FOLLOWING SOIL PARAMETERS:

	UNIT WEIGHT (kN/m ³)	SUBMERGED UNIT WEIGHT (kN/m ³)	FRICTION ANGLE (DEGREES)	COHESION (kPa)
GROUND SURFACE TO EL. -0.3M	18.8	9.4	30	0
EL. -0.3M TO EL. -5.0M	12.6	3.2	5	7.5
EL. -5.0M TO EL. -10.0M	18.8	9.4	30	0
EL. -10.0M TO EL. -15.0M	17.3	7.9	0	25

FOR SECTIONS OF CONTRACTOR DESIGNED SHORING SUBJECT TO UNBALANCED HYDROSTATIC FORCES FROM DEWATERING, ASSUME WATER TABLE ELEVATION=+0.5M AND ASSUME THAT THE EXCAVATION WILL BE DEWATERED DOWN TO BOTTOM OF EXCAVATION.

IT MAY BE PREFERRED OR NECESSARY TO ANCHOR TEMPORARY SHORING FROM STA. 55+70 +/- TO STA. 55+90 +/- -L- 4.8 m +/- RIGHT. FOR ANCHORING TEMPORARY SHORING, SEE TEMPORARY SHORING PROVISION.

FOR CONTRACTOR DESIGNED SHORING, SURVEY THE SHORING LOCATION TO DETERMINE EXISTING ELEVATIONS AND ACTUAL DESIGN HEIGHTS BEFORE BEGINNING DESIGN.

FOR PORTABLE CONCRETE BARRIERS ABOVE AND BEHIND TEMPORARY SHORING, USE AN NCDOT PORTABLE CONCRETE BARRIER (UNANCHORED OR ANCHORED) OR AN OREGON TALL F-SHAPE CONCRETE BARRIER IN ACCORDANCE WITH THE TRAFFIC CONTROL PLANS.

LIMITED SUBSURFACE INFORMATION IS AVAILABLE IN THE VICINITY OF THE TEMPORARY SHORING FROM STA. 55+70 +/- -L- TO STA. 55+90 +/- -L- 4.8 m +/- RIGHT. THE INFORMATION PROVIDED FOR DESIGN WAS ASSUMED AND MAY NOT BE APPLICABLE TO THE ACTUAL SITE CONDITIONS ENCOUNTERED DURING CONSTRUCTION.

Temporary Shoring No. 2

FOR TEMPORARY SHORING, SEE TEMPORARY SHORING PROVISION.

DO NOT USE STANDARD SHORING FROM STA. 73+40 +/- -L- TO STA. 73+60 +/- -L- 4.1 M +/- -LEFT. USE CONTRACTOR DESIGNED SHORING FOR THIS LOCATION.

FOR CONTRACTOR DESIGNED SHORING FROM STA. 73+40 +/- TO STA. 73+60 +/- -L- 4.1 m +/- LEFT, DESIGN SHORING FOR THE FOLLOWING SOIL PARAMETERS:

	UNIT WEIGHT (kN/m ³)	SUBMERGED UNIT WEIGHT (kN/m ³)	FRICTION ANGLE (DEGREES)	COHESION (kPa)
GROUND SURFACE TO EL. -1.1M	18.8	9.4	30	0
EL. -1.1M TO EL. -3.3M	12.6	3.2	5	7.5
EL. -3.3M TO EL. -13.0M	17.3	7.9	27	0
EL. -13.0M TO EL. -18.0M	17.3	7.9	0	25

FOR SECTIONS OF CONTRACTOR DESIGNED SHORING SUBJECT TO UNBALANCED HYDROSTATIC FORCES FROM DEWATERING, ASSUME WATER TABLE ELEVATION=+0.5M AND ASSUME THAT THE EXCAVATION WILL BE DEWATERED DOWN TO BOTTOM OF EXCAVATION.

IT MAY BE PREFERRED OR NECESSARY TO ANCHOR TEMPORARY SHORING FROM STA. 73+40 +/- TO STA. 73+60 +/- -L- 4.1 m +/- LEFT. FOR ANCHORING TEMPORARY SHORING, SEE TEMPORARY SHORING PROVISION.

FOR CONTRACTOR DESIGNED SHORING, SURVEY THE SHORING LOCATION TO DETERMINE EXISTING ELEVATIONS AND ACTUAL DESIGN HEIGHTS BEFORE BEGINNING DESIGN.

FOR PORTABLE CONCRETE BARRIERS ABOVE AND BEHIND TEMPORARY SHORING, USE AN NCDOT PORTABLE CONCRETE BARRIER (UNANCHORED OR ANCHORED) OR AN OREGON TALL F-SHAPE CONCRETE BARRIER IN ACCORDANCE WITH THE TRAFFIC CONTROL PLANS.

LIMITED SUBSURFACE INFORMATION IS AVAILABLE IN THE VICINITY OF THE TEMPORARY SHORING FROM STA. 73+40 +/- -L- TO STA. 73+60 +/- -L- 4.1 m +/- LEFT. THE INFORMATION PROVIDED FOR DESIGN WAS ASSUMED AND MAY NOT BE APPLICABLE TO THE ACTUAL SITE CONDITIONS ENCOUNTERED DURING CONSTRUCTION.

Temporary Shoring No. 3A

DO NOT USE STANDARD SHORING OR CONTRACTOR DESIGNED SHORING FROM STA. 11+03 +/- -DET3- TO STA. 11+63 +/- -DET3- 7.8m +/- LEFT. USE TEMPORARY SHEETING FOR THIS LOCATION.

INSTALL TEMPORARY SHEETING FROM STA. 11+03 +/- -DET3- TO STA. 11+63 +/- -DET3- 7.8 m +/- LEFT TO A MINIMUM SHEETING EMBEDMENT OF 12.0M BELOW THE EXISTING GROUND SURFACE. TOP OF TEMPORARY SHEETING MUST EXTEND A MINIMUM OF 150 MM ABOVE THE EXISTING GROUND SURFACE.

FOR TEMPORARY SHEETING, SEE TEMPORARY SHEETING PROJECT SPECIAL PROVISION. USE SHEET PILING WITH A MINIMUM SECTION MODULUS OF 2600 CM³/M FOR TEMPORARY SHEETING.

FOR PORTABLE CONCRETE BARRIERS ABOVE AND BEHIND TEMPORARY SHORING, USE AN NCDOT PORTABLE CONCRETE BARRIER (UNANCHORED OR ANCHORED) OR AN OREGON TALL F-SHAPE CONCRETE BARRIER IN ACCORDANCE WITH THE TRAFFIC CONTROL PLANS.



Temporary Shoring No. 3B

FOR TEMPORARY SHORING, SEE TEMPORARY SHORING PROVISION.


USE A TEMPORARY MSE WALL FROM STA. 11+34 +/- -DET3- TO STA. 11+52 +/- -DET3- 5.7 m +/- LEFT.

FOR PORTABLE CONCRETE BARRIERS ABOVE AND BEHIND TEMPORARY SHORING, USE AN NCDOT PORTABLE CONCRETE BARRIER (UNANCHORED OR ANCHORED) OR AN OREGON TALL F-SHAPE CONCRETE BARRIER IN ACCORDANCE WITH THE TRAFFIC CONTROL PLANS.

10/18/2011 12:28:42 PM F:\R-2414B\TrafficControl\TCP\2414b_TCP_psh31A.dgn

APPROVED: _____	DATE: _____	TEMPORARY SHORING RECOMMENDATIONS	
			
SCALE: _____	DESIGN BY: _____		REVISIONS
DATE: _____	REVIEWED BY: _____		
DWG. BY: _____			


TWO-WAY UNDIVIDED ** (L-LINES)



POSTED SPEED LIMIT (M.P.H.)	RECOMMENDED MINIMUM SIGN SPACING
≤ 50	⊗ 152m
≥ 55	305m

STATE OF NORTH CAROLINA
DEPT. OF TRANSPORTATION
DIVISION OF HIGHWAYS
RALEIGH, N.C.

ROADWAYS INTERSECTING ALONG 2 WAY UNDIVIDED WORK ZONE (Y-LINES)



GENERAL NOTES

- USE FLUORESCENT ORANGE SHEETING (TYPE VII OR HIGHER) ON ALL ADVANCED WORK ZONE SIGNS.
- DO NOT INSTALL ADVANCE WARNING SIGNS MORE THAN 3 DAYS PRIOR TO BEGINNING OF WORK.
- SIGNS SHOWN ARE REQUIRED FOR WORK ZONES THAT WILL REMAIN IN EFFECT OVERNIGHT. FOR SHORT-TERM DAILY MAINTENANCE TYPE OPERATIONS, THIS SIGNING APPLICATION IS OPTIONAL; MAY USE ONLY APPLICABLE ROADWAY STANDARD DRAWINGS INSTEAD. HOWEVER, IF THIS SIGNING APPLICATION IS USED, SIGNS MAY BE PORTABLE MOUNTED.
- ALL SIGN SPACING DIMENSIONS ARE APPROXIMATE, FIELD ADJUST AS NECESSARY OR AS DIRECTED.
- USE 1.4Kg STEEL U-CHANNEL POST OR 90mm X 90mm WOOD POST FOR ALL WORK ZONE SIGNS. 1.4Kg STEEL U-CHANNEL POSTS MUST MEET THE REQUIREMENTS OF STANDARD SPECIFICATION SECTION 1094-1(B), MAY BE GALVANIZED STEEL, OR MAY BE PAINTED GREEN BY THE POST MANUFACTURER. SQUARE STEEL TUBING POSTS HAVING EQUIVALENT STRENGTH OF THE 1.4Kg STEEL U-CHANNEL POST ARE ALSO ACCEPTABLE FOR USE. ERECT SIGNS PER ROADWAY STANDARD DRAWING 1110.01. PAYMENT FOR WOOD POSTS, 1.4Kg STEEL U-CHANNEL AND SQUARE STEEL TUBING POSTS WITH SIGNS WILL BE MADE ACCORDING TO STANDARD SPECIFICATION "WORK ZONE SIGNS" SECTION 1110.
- WHEN NECESSARY, USE SPLICING IN ACCORDANCE WITH ROADWAY STANDARD DRAWING NO. 1110.01. REMOVE ENTIRE POST WHEN REMOVING SIGNS WITH SPLICED POSTS.
- DO NOT BACK BRACE SIGN SUPPORTS.
- ** TWO-WAY UNDIVIDED ADVANCE WARNING SIGN CONFIGURATION MAY BE USED ON URBAN MULTI-LANE FACILITIES WHERE CONDITIONS LIMIT THE USE OF DUAL MOUNTED SIGNS AS DETERMINED BY THE ENGINEER.

DETAIL DRAWING FOR
TWO-WAY UNDIVIDED
WORK ZONE WARNING SIGNS

SHEET 1 OF 1

LEGEND	
⊥	STATIONARY SIGN
◀	DIRECTION OF TRAFFIC FLOW

APPROVED: <i>Bob A May</i> DATE: <i>10/01</i>	DETAIL DRAWING FOR TWO-WAY UNDIVIDED AND URBAN FREEWAYS ADVANCED WORK ZONE WARNING SIGNS	
	SCALE: NONE	REVISIONS
	DATE: 10-98	7-98 10/01
	DWG. BY:	10-98 03/04
	DESIGN BY:	01/01 11/04
REVIEWED BY:	CADD FILE	