

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	874 CY		
0003	0255000000-E	SP	GENERIC GRADING ITEM AGGREGATE SHOULDER BORROW	80 TON		
0004	1220000000-E	545	INCIDENTAL STONE BASE	795 TON		
0005	1245000000-E	SP	SHOULDER RECONSTRUCTION	15.9 SMI		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (8")	1,370 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	320 SY		
0008	1330000000-E	607	INCIDENTAL MILLING	2,410 SY		
0009	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,625 TON		
0010	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,535 TON		
0011	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,365 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,970 TON		
0013	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	220 TON		
0014	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	697 TON		
0015	1704000000-E	SP	PATCHING EXISTING PAVEMENT	1,730 TON		
0016	1770000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #6 STONE	3,806 SY		
0017	1803000000-E	660	ASPHALT SURFACE TREATMENT, SPLIT SEAL	225,664 SY		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT CONC SURFACE COURSE, TYPE S4.75A (LEVELING COURSE)	50 TON		
0019	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0020	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	86,566 LF		
0021	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	68,500 LF		
0022	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	40 LF		
0023	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	3 EA		
0024	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	829,346 LF		
0025	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	585 EA		
0026	6000000000-E	1605	TEMPORARY SILT FENCE	800 LF		
0027	6071010000-E	SP	WATTLE	100 LF		
0028	6084000000-E	1660	SEEDING & MULCHING	7.95 ACR		
0029	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0030	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1 TON		

1105/Feb14/Q1236577.85/D86307110000/E30

Total Amount Of Bid For Entire Project :

Contract No. **C202969**

County (ies): **Chatham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General