

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	3,200 CY		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	34 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	2,000 SY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	5,700 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 2")	11,500 SY		
0007	1330000000-E	607	INCIDENTAL MILLING	533 SY		
0008	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	5,083 TON		
0009	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	9,797 TON		
001C	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	38,379 TON		
0011	1526000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S4.75A	673 TON		
0012	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	3,142 TON		
0013	1704000000-E	SP	PATCHING EXISTING PAVEMENT	255 TON		
0014	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	180,000 LF		
001E	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0016	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	234,950 LF		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	29,520	LF	
001E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	700	LF	
001E	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	8,500	LF	
002C	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	40	LF	
0021	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	13	EA	
0022	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)	3,800	LF	
002E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,800	LF	
0024	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,850	EA	
002E	6000000000-E	1605	TEMPORARY SILT FENCE	2,550	LF	
002E	6012000000-E	1610	SEDIMENT CONTROL STONE	100	TON	
0027	6030000000-E	1630	SILT EXCAVATION	300	CY	
002E	6036000000-E	1631	MATTING FOR EROSION CONTROL	680	SY	
002E	6042000000-E	1632	1/4" HARDWARE CLOTH	1,320	LF	
003C	6071010000-E	SP	WATTLE	1,224	LF	
0031	6071020000-E	SP	POLYACRYLAMIDE (PAM)	51	LB	
0032	6084000000-E	1660	SEEDING & MULCHING	42	ACR	

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	8860000000-N	SP	GENERIC STRUCTURE ITEM REMOVAL AND REPLACEMENT OF BRIDGE JOINT SEALS	Lump Sum	L.S.	

1311/Feb13/Q549739.0/D122113130000/E33

Total Amount Of Bid For Entire Project :

Contract No. **C202945**

County (ies): **Columbus**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General