

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14 + 49.00 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	500 SY		
0008	0220000000-E	SP	ROCK EMBANKMENTS	2,150 TON		
0009	0241000000-E	SP	GENERIC GRADING ITEM FILTER FABRIC FOR ROCK EMBANKMENTS	1,980 SY		
0010	0241000000-E	SP	GENERIC GRADING ITEM ROCK PLATING	190 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	5 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	20 SY		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	40 LF		
0014	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0015	1077000000-E	SP	#57 STONE	380 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	210 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	240 TON		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	30 TON		
001E	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
002C	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0022	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0023	2077000000-E	815	6" OUTLET PIPE	6 LF		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	100 LF		
0027	2570000000-N	SP	MODIFIED CONCRETE FLUME	1 EA		
002E	3030000000-E	862	STEEL BM GUARDRAIL	337.5 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003C	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	2 EA		
0031	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0032	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0033	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0034	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	465 SY		
003E	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	6 EA		
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	270 SF		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94	SF	
003E	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,600	LF	
004C	6000000000-E	1605	TEMPORARY SILT FENCE	1,255	LF	
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	25	TON	
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	85	TON	
0044	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0047	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
004E	6029000000-E	SP	SAFETY FENCE	475	LF	
004E	6030000000-E	1630	SILT EXCAVATION	30	CY	
005C	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500	SY	
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	370	LF	
0052	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	150	SY	
005E	6071030000-E	1640	COIR FIBER BAFFLE	10	LF	
0054	6084000000-E	1660	SEEDING & MULCHING	1.5	ACR	
005E	6087000000-E	1660	MOWING	1.5	ACR	

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0057	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0058	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0059	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0060	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0061	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		

---

**STRUCTURE ITEMS**


---

0062	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14 + 49.00-L-)	Lump Sum	L.S.	
0063	8112730000-N	450	PDA TESTING	1 EA		
0064	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14 + 49.00-L-)	Lump Sum	L.S.	
0065	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	50.6 CY		
0066	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14 + 49.00-L-)	Lump Sum	L.S.	
0067	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	8,542 LB		
0068	8329000000-E	450	12" PRESTRESSED CONCRETE PILES	500 LF		
0069	8333000000-E	450	16" PRESTRESSED CONCRETE PILES	600 LF		
0070	8393000000-N	450	PILE REDRIVES	12 EA		
0071	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	239.75 LF		

County : Currituck

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8590000000-E	876	RIP RAP, CLASS ** CLASS I (2'-0" THICK)	126 TON		
0073	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	141 SY		
0074	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0075	8755000000-E	430	3'-0" X 1'-6" PRESTRESSED CONC CORED SLABS	1,315.88 LF		
1117/Feb01/Q28910.68/D324615560000/E75			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202999**

**County (ies):**   **Currituck**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General