

County : Tyrrell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (26 + 90)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	1,375 CY		
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	4,010 CY		
0008	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	2,900 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	1,300 SY		
001C	0199000000-E	SP	TEMPORARY SHORING	1,500 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	77 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	210 SY		
0013	0335200000-E	305	15" DRAINAGE PIPE	44 LF		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	60 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	2 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,620 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	750 TON		

County : Tyrrell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	125 TON		
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
002C	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0023	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE	6 LF		
002E	2209000000-E	838	ENDWALLS	1.4 CY		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
002E	2462000000-E	SP	*** SLUICE GATE (15")	2 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
003C	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0034	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	275 LF		
003E	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (III MOD)	2 EA		

County : Tyrrell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3389100000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350	2	EA	
0037	3649000000-E	876	RIP RAP, CLASS B	5	TON	
003E	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	465	SY	
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	284	SF	
004C	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
0041	4430000000-N	1130	DRUMS	45	EA	
0042	4455000000-N	1150	FLAGGER	60	DAY	
004E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0044	4470000000-N	1160	RESET TEMPORARY CRASH CUSHION	2	EA	
004E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	525	LF	
004E	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	200	LF	
0047	4609000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TEMPORARY TRAFFIC SIGNAL SYSTEM	365	DAY	
004E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	166	EA	
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	25,140	LF	
005C	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,000	LF	
0051	5325600000-E	1510	6" WATER LINE	1,940	LF	
0052	5540000000-E	1515	6" VALVE	2	EA	
005E	5800000000-E	1530	ABANDON 6" UTILITY PIPE	1,900	LF	

County : Tyrrell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	1,200	LF	
005E	5871410000-E	1550	TRENCHLESS INSTALLATION OF 6" NOT IN SOIL	125	LF	
005E	6000000000-E	1605	TEMPORARY SILT FENCE	5,595	LF	
0057	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	60	TON	
005E	6012000000-E	1610	SEDIMENT CONTROL STONE	135	TON	
006C	6015000000-E	1615	TEMPORARY MULCHING	3.5	ACR	
0061	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150	LB	
0062	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1	TON	
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0064	6029000000-E	SP	SAFETY FENCE	4,300	LF	
006E	6030000000-E	1630	SILT EXCAVATION	500	CY	
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,515	SY	
0067	6037000000-E	SP	COIR FIBER MAT	770	SY	
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	560	LF	
006E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	500	SY	
007C	6071012000-E	SP	COIR FIBER WATTLE	75	LF	
0071	6071030000-E	1640	COIR FIBER BAFFLE	220	LF	
0072	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	

County : Tyrrell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6084000000-E	1660	SEEDING & MULCHING	3	ACR	
0074	6087000000-E	1660	MOWING	3	ACR	
0075	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0076	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0077	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75	LB	
0078	6108000000-E	1665	FERTILIZER TOPDRESSING	2	TON	
0079	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0080	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	
0081	6129000000-E	1670	WETLAND REFORESTATION	0.52	ACR	
0082	6135000000-E	SP	GENERIC EROSION CONTROL ITEM DISKING	0.52	ACR	
0083	6135000000-E	SP	GENERIC EROSION CONTROL ITEM RIPPING	0.52	ACR	

**STRUCTURE ITEMS**

0084	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (26 + 90.00-L-)	Lump Sum	L.S.	
008E	8112730000-N	450	PDA TESTING	2	EA	
008E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (26 + 90.00-L-)	Lump Sum	L.S.	
0087	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	115.5	CY	
008E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (26 + 90.00-L-)	Lump Sum	L.S.	

County : Tyrrell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	22,717 LB		
009C	8364000000-E	450	HP12X53 STEEL PILES	930 LF		
0091	8392000000-N	450	PIPE PILE PLATES	12 EA		
0092	8393000000-N	450	PILE REDRIVES	54 EA		
0093	8475000000-E	460	TWO BAR METAL RAIL	720.5 LF		
0094	8517000000-E	460	1'-**"X ***** CONCRETE PARA- PET (1'-2" X 2'-7 1/2")	735.5 LF		
009E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	231 TON		
009E	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	257 SY		
0097	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
009E	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	4,402.5 LF		
009E	8867000000-E	SP	GENERIC STRUCTURE ITEM HP 14 X 73 METALLIZED STEEL PI LES	2,670 LF		
010C	8867000000-E	SP	GENERIC STRUCTURE ITEM PP 24 X 0.50 METALLIZED STEEL PILES	1,080 LF		

1337/Feb02/Q99067.71/D457921532000/E100

Total Amount Of Bid For Entire Project :

**Contract No**     **C203000**

**County (ies):**   **Tyrrell**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General