

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (27+60-L-)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	350 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	6,400 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	15 CY		
0009	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	250 CY		
0010	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	600 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	17 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	54 SY		
0013	0335200000-E	305	15" DRAINAGE PIPE	140 LF		
0014	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	8 EA		
0015	0344000000-E	310	18" SIDE DRAIN PIPE	20 LF		
0016	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0017	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	200 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/4")	120 SY		
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	680 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	280 TON		
0022	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	280 TON		
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	63 TON		
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0025	2022000000-E	815	SUBDRAIN EXCAVATION	56 CY		
0026	2033000000-E	815	SUBDRAIN FINE AGGREGATE	42 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250 LF		
0028	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE	6 LF		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	250 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	250 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0036	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3649000000-E	876	RIP RAP, CLASS B	4 TON		
0038	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	740 SY		
0039	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	336 SF		
0040	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0041	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0042	6000000000-E	1605	TEMPORARY SILT FENCE	1,080 LF		
0043	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	125 TON		
0045	6012000000-E	1610	SEDIMENT CONTROL STONE	200 TON		
0046	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0048	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5 TON		
0049	6024000000-E	1622	TEMPORARY SLOPE DRAINS	460 LF		
0050	6029000000-E	SP	SAFETY FENCE	200 LF		
0051	6030000000-E	1630	SILT EXCAVATION	570 CY		
0052	6036000000-E	1631	MATTING FOR EROSION CONTROL	4,000 SY		
0053	6037000000-E	SP	COIR FIBER MAT	40 SY		
0054	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	315 SY		
0055	6042000000-E	1632	1/4" HARDWARE CLOTH	305 LF		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6070000000-N	1639	SPECIAL STILLING BASINS	4 EA		
0057	6071010000-E	SP	WATTLE	310 LF		
0058	6071020000-E	SP	POLYACRYLAMIDE (PAM)	80 LB		
0059	6071030000-E	1640	COIR FIBER BAFFLE	270 LF		
0060	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0061	6084000000-E	1660	SEEDING & MULCHING	4.5 ACR		
0062	6087000000-E	1660	MOWING	3 ACR		
0063	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0064	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0065	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0066	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0067	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0068	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		

STRUCTURE ITEMS

0069	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (27+60.00-L-)	Lump Sum	L.S.	
0070	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (27+60.00-L-)	Lump Sum	L.S.	
0071	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	41.2 LF		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	27 LF		
0073	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	17.1 LF		
0074	8113000000-N	411	SID INSPECTIONS	1 EA		
0075	8115000000-N	411	CSL TESTING	1 EA		
0076	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (27+60.00-L-)	Lump Sum	L.S.	
0077	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,243 SF		
0078	8161000000-E	420	GROOVING BRIDGE FLOORS	3,970 SF		
0079	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	80.8 CY		
0080	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (27+60.00-L-)	Lump Sum	L.S.	
0081	8217000000-E	425	REINFORCING STEEL (BRIDGE)	15,338 LB		
0082	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,457 LB		
0083	8262000000-E	430	45" PRESTRESSED CONCRETE GIRDERS	500.42 LF		
0084	8364000000-E	450	HP12X53 STEEL PILES	235 LF		
0085	8503000000-E	460	CONCRETE BARRIER RAIL	255.19 LF		
0086	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	630 TON		
0087	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	700 SY		
0088	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
1538/Feb07/Q47820.21/D402840700000/E89			Total Amount Of Bid For Entire Project :			

Contract No. **C202784**

County (ies): **Union**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General