

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000900000-N	SP	GENERIC MISCELLANEOUS ITEM GRADING FOR RAMP WIDENING	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	50 CY		
0004	0106000000-E	230	BORROW EXCAVATION	295 CY		
0005	0264000000-E	SP	GENERIC GRADING ITEM SHOULDER GRADING	53.3 SMI		
0006	1121000000-E	520	AGGREGATE BASE COURSE	1,255 TON		
0007	1220000000-E	545	INCIDENTAL STONE BASE	628 TON		
0008	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	411,688 SY		
0009	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (5-1/2")	352 SY		
001C	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	311 TON		
0011	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	169 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	41,903 TON		
0013	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	2,493 TON		
0014	1704000000-E	SP	PATCHING EXISTING PAVEMENT	500 TON		
001E	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	115,316 LF		
0016	1891000000-E	SP	GENERIC PAVING ITEM FOG SEAL	123,792 SY		
0017	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	1 EA		
001S	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
002C	4510000000-N	SP	LAW ENFORCEMENT	2,000 HR		
0021	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	246,532 LF		
0022	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	31,994 LF		
0023	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	8,912 LF		
0024	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	175 LF		
002E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12 EA		
002E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	61 EA		
0027	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,267 EA		
002E	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
002S	6000000000-E	1605	TEMPORARY SILT FENCE	3,690 LF		
003C	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,360 SY		
0031	6071010000-E	SP	WATTLE	8,430 LF		
0032	6071020000-E	SP	POLYACRYLAMIDE (PAM)	587 LB		
0033	6084000000-E	1660	SEEDING & MULCHING	31.67 ACR		
0034	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,958 LF		

**Contract No.**     **C202996**

**County (ies):**   **Wake**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General