

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (11 + 42.00-L-)	Lump Sum	L.S.	
0004	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (18 + 89.00-L-)	Lump Sum	L.S.	
000E	0043000000-N	226	GRADING	Lump Sum	L.S.	
000E	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
000E	0134000000-E	240	DRAINAGE DITCH EXCAVATION	12 CY		
000E	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
001C	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	220 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	30 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	90 SY		
0013	0335200000-E	305	15" DRAINAGE PIPE	52 LF		
0014	0335300000-E	305	18" DRAINAGE PIPE	148 LF		
001E	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	48 LF		
001E	0995000000-E	340	PIPE REMOVAL	76 LF		
0017	1099500000-E	505	SHALLOW UNDERCUT	50 CY		
001E	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	100 TON		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
002C	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	730 TON		
0021	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	630 TON		
0022	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	75 TON		
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0024	2000000000-N	806	RIGHT OF WAY MARKERS	21 EA		
002E	2022000000-E	815	SUBDRAIN EXCAVATION	25 CY		
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0027	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
002E	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE	6 LF		
003C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	220 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	187.5 LF		
0034	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25 LF		
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003E	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	7 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1	EA	
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8	EA	
003E	3628000000-E	876	RIP RAP, CLASS I	5	TON	
004C	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,570	SY	
0041	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	4	EA	
0042	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	249	LF	
0043	4096000000-N	904	SIGN ERECTION, TYPE D	6	EA	
0044	4102000000-N	904	SIGN ERECTION, TYPE E	3	EA	
004E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	14	EA	
004E	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	1	EA	
0047	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	632	SF	
004E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96	SF	
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	156	SF	
005C	4430000000-N	1130	DRUMS	30	EA	
0051	4435000000-N	1135	CONES	25	EA	
0052	4445000000-E	1145	BARRICADES (TYPE III)	112	LF	
0053	4455000000-N	1150	FLAGGER	59	DAY	
0054	4507000000-E	1170	WATER FILLED BARRIER	90	LF	
005E	4508000000-E	1170	RESET WATER FILLED BARRIER	90	LF	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	61	EA	
0057	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,687	LF	
005E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	136	LF	
005E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	480	LF	
006C	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	35	LF	
0061	6000000000-E	1605	TEMPORARY SILT FENCE	2,000	LF	
0062	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	360	TON	
0063	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	175	TON	
0064	6012000000-E	1610	SEDIMENT CONTROL STONE	450	TON	
006E	6015000000-E	1615	TEMPORARY MULCHING	4	ACR	
006E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150	LB	
0067	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5	TON	
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
006E	6029000000-E	SP	SAFETY FENCE	500	LF	
007C	6030000000-E	1630	SILT EXCAVATION	480	CY	
0071	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,000	SY	
0072	6037000000-E	SP	COIR FIBER MAT	20	SY	
0073	6042000000-E	1632	1/4" HARDWARE CLOTH	675	LF	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6070000000-N	1639	SPECIAL STILLING BASINS	12	EA	
007E	6071010000-E	SP	WATTLE	300	LF	
007E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	100	LB	
0077	6071030000-E	1640	COIR FIBER BAFFLE	135	LF	
007E	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	
007E	6084000000-E	1660	SEEDING & MULCHING	3	ACR	
008C	6087000000-E	1660	MOWING	3	ACR	
0081	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0082	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
008E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100	LB	
0084	6108000000-E	1665	FERTILIZER TOPDRESSING	2.5	TON	
008E	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
008E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18	EA	
0087	6123000000-E	1670	REFORESTATION	0.2	ACR	

STRUCTURE ITEMS

008E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (11 + 42.00-L-)	Lump Sum	L.S.	
008E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18 + 89.00-L-)	Lump Sum	L.S.	

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	64.42 LF		
0091	8105640000-E	411	3'-6" DIA DRILLED PIERS NOT IN SOIL	45 LF		
0092	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	22.15 LF		
0093	8113000000-N	411	SID INSPECTIONS	1 EA		
0094	8114000000-N	411	SPT TESTING	2 EA		
009E	8115000000-N	411	CSL TESTING	1 EA		
0096	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (11 + 42.00-L-)	Lump Sum	L.S.	
0097	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (18 + 89.00-L-)	Lump Sum	L.S.	
009E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	102.2 CY		
009E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (11 + 42.00-L-)	Lump Sum	L.S.	
010C	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18 + 89.00-L-)	Lump Sum	L.S.	
0101	8217000000-E	425	REINFORCING STEEL (BRIDGE)	28,070 LB		
0102	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,981 LB		
0103	8364000000-E	450	HP12X53 STEEL PILES	545 LF		
0104	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	401.01 LF		
010E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	759 TON		
010E	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	843 SY		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
010E	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	600 LF		
010E	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	1,400 LF		
1249/Mar08/Q78262.73/D492811370000/E109			Total Amount Of Bid For Entire Project :			

Contract No. **C202809**

County (ies): **Burke**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General