

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (25 + 83.36)	Lump Sum	L.S.	
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (26 + 15.48)	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	1,000 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	200 CY		
0009	0141000000-E	240	BERM DITCH CONSTRUCTION	1,830 LF		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	1,000 CY		
0011	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	2,200 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	355 TON		
0013	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	1,060 SY		
0014	0342000000-E	310	*** SIDE DRAIN PIPE (30")	68 LF		
0015	0342000000-E	310	*** SIDE DRAIN PIPE (36")	344 LF		
0016	0342000000-E	310	*** SIDE DRAIN PIPE (48")	128 LF		
0017	0343000000-E	310	15" SIDE DRAIN PIPE	1,508 LF		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0344000000-E	310	18" SIDE DRAIN PIPE	168		LF
001S	0345000000-E	310	24" SIDE DRAIN PIPE	388		LF
002C	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (15")	9		EA
0021	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (18")	1		EA
0022	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (24")	3		EA
0023	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	84		LF
0024	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	96		LF
002E	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	68		LF
002E	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	76		LF
0027	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	236		LF
002E	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (24", 0.250")	369		LF
002S	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (24", 0.250")	159		LF
003C	0995000000-E	340	PIPE REMOVAL	698		LF
0031	0996000000-N	350	PIPE CLEAN-OUT	2		EA
0032	1099500000-E	505	SHALLOW UNDERCUT	1,000		CY
0033	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	1,500		TON
0034	1220000000-E	545	INCIDENTAL STONE BASE	100		TON

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	660 SY		
003E	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	500 SY		
0037	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	300 TON		
003E	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	16,100 TON		
003E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	50 TON		
004C	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	6,300 TON		
0041	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	300 TON		
0042	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	5,100 TON		
0043	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,350 TON		
0044	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
004E	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	10,400 LF		
004E	1847000000-E	710	***** PORT CEM CONC PAVEMENT, THROUGH LANES (WITH DOWELS) (9")	600 SY		
0047	1891000000-E	SP	GENERIC PAVING ITEM MILLING ASPHALT PAVEMENT, VARIABLE DEPTH	4,300 SY		
004E	2000000000-N	806	RIGHT OF WAY MARKERS	5 EA		
004E	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
005C	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0051	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0052	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0053	2077000000-E	815	6" OUTLET PIPE	6 LF		
0054	2253000000-E	840	PIPE COLLARS	0.893 CY		
005E	2264000000-E	840	PIPE PLUGS	1.04 CY		
005E	2275000000-E	SP	FLOWABLE FILL	47 CY		
0057	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	34 EA		
005E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	33.627 LF		
005E	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	8 EA		
006C	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	22 EA		
0061	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	2 EA		
0062	2396000000-N	840	FRAME WITH COVER, STD 840.54	3 EA		
0063	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	500 LF		
0064	2556000000-E	846	SHOULDER BERM GUTTER	2,000 LF		
006E	2619000000-E	850	4" CONCRETE PAVED DITCH	140 SY		
006E	2815000000-N	858	ADJUSTMENT OF DROP INLETS	2 EA		
0067	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	2 EA		
006E	2938000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE	1 EA		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	2950000000-N	859	CONVERT EXISTING JUNCTION BOX TO DROP INLET	2 EA		
007C	3030000000-E	862	STEEL BM GUARDRAIL	3,200 LF		
0071	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	30 EA		
0072	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0073	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	8 EA		
0074	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	6 EA		
007E	3360000000-E	863	REMOVE EXISTING GUARDRAIL	6,345 LF		
0076	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	925 LF		
0077	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77)	3 EA		
007E	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (W-BEAM)	3 EA		
0079	3389400000-E	865	DOUBLE FACED CABLE GUIDERAIL	1,650 LF		
008C	3389600000-N	865	CABLE GUIDERAIL ANCHOR UNITS	4 EA		
0081	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	5,600 LF		
0082	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	370 EA		
0083	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	70 EA		
0084	3628000000-E	876	RIP RAP, CLASS I	200 TON		
008E	3649000000-E	876	RIP RAP, CLASS B	200 TON		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	2,110	SY	
0087	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	1	CY	
008E	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	1	CY	
008E	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	1,024	LB	
009C	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	64	LF	
0091	4078000000-E	903	SUPPORTS, 2-LB STEEL U-CHANNEL	2	EA	
0092	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
009E	4102000000-N	904	SIGN ERECTION, TYPE E	2	EA	
0094	4108000000-N	904	SIGN ERECTION, TYPE F	1	EA	
009E	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	1	EA	
009E	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	1	EA	
0097	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	2	EA	
009E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	11	EA	
009E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	920	SF	
010C	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	670	SF	
0101	4415000000-N	1115	FLASHING ARROW BOARD	2	EA	
0102	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2	EA	
010E	4430000000-N	1130	DRUMS	500	EA	

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	4435000000-N	1135	CONES	45 EA		
010E	4455000000-N	1150	FLAGGER	120 DAY		
010E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	8 EA		
0107	4470000000-N	1160	RESET TEMPORARY CRASH CUSHION	8 EA		
010E	4480000000-N	1165	TMA	2 EA		
0109	4485000000-E	1170	PORTABLE CONCRETE BARRIER	8,778 LF		
011C	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	11,710 LF		
0111	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	145 EA		
0112	4687000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 240 MILS)	384 LF		
0113	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	52,500 LF		
0114	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	15,109 LF		
011E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	10 EA		
011E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	66 EA		
0117	5325600000-E	1510	6" WATER LINE	545 LF		
011E	5540000000-E	1515	6" VALVE	1 EA		
011E	5606000000-E	1515	2" BLOW OFF	1 EA		
012C	5648000000-N	1515	RELOCATE WATER METER	1 EA		
0121	6000000000-E	1605	TEMPORARY SILT FENCE	8,400 LF		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0122	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	835 TON		
0123	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,300 TON		
0124	6012000000-E	1610	SEDIMENT CONTROL STONE	850 TON		
0125	6015000000-E	1615	TEMPORARY MULCHING	23.5 ACR		
0126	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	800 LB		
0127	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	4 TON		
0128	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,000 LF		
0129	6029000000-E	SP	SAFETY FENCE	100 LF		
0130	6030000000-E	1630	SILT EXCAVATION	2,000 CY		
0131	6036000000-E	1631	MATTING FOR EROSION CONTROL	18,500 SY		
0132	6037000000-E	SP	COIR FIBER MAT	50 SY		
0133	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	6,425 SY		
0134	6042000000-E	1632	1/4" HARDWARE CLOTH	1,665 LF		
0135	6071010000-E	SP	WATTLE	2,000 LF		
0136	6071020000-E	SP	POLYACRYLAMIDE (PAM)	670 LB		
0137	6071030000-E	1640	COIR FIBER BAFFLE	540 LF		
0138	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0139	6084000000-E	1660	SEEDING & MULCHING	24 ACR		
0140	6087000000-E	1660	MOWING	15 ACR		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0141	6090000000-E	1661	SEED FOR REPAIR SEEDING	250 LB		
0142	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75 TON		
0143	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	550 LB		
0144	6108000000-E	1665	FERTILIZER TOPDRESSING	16.5 TON		
0145	6114500000-N	1667	SPECIALIZED HAND MOWING	25 MHR		
0146	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		

STRUCTURE ITEMS

0147	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (25 + 98.15-L-LT)	Lump Sum	L.S.	
014E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (25 + 98.15-L-LT)	Lump Sum	L.S.	
014E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (25 + 98.15-L-RT)	Lump Sum	L.S.	
015C	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	10,015 SF		
0151	8161000000-E	420	GROOVING BRIDGE FLOORS	12,187 SF		
0152	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	369.3 CY		
0153	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (25 + 98.15-L-LT)	Lump Sum	L.S.	
0154	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (25 + 98.15-L-RT)	Lump Sum	L.S.	
015E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	36,864 LB		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0156	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	299,700	LS	
0157	8364000000-E	450	HP12X53 STEEL PILES	1,430	LF	
0158	8503000000-E	460	CONCRETE BARRIER RAIL	531.33	LF	
0159	8531000000-E	462	4" SLOPE PROTECTION	1,195	SY	
016C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0161	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
0162	8893000000-E	SP	GENERIC STRUCTURE ITEM REINFORCED SOIL SLOPE	955	SY	

1247/Mar08/Q586422.34/D588701010000/E162

Total Amount Of Bid For Entire Project :

Contract No. **C202812**

County (ies): **Forsyth**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General