



FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY BREAKDOWN	TOTAL QUANTITY	
PAVEMENT MARKINGS					
P4	WHITE STOPBAR (2X)	PAINT(24")	40 LF	40 LF	
			TOTAL		
CI	YELLOW DOUBLE CENTER	COLD APPLIED PLASTIC (4") Type 1-Permanent Std	180 LF	180 LF	
			TOTAL		
PA	WHITE EDGELINE (2X)	PAINT(4")	312 LF	2282 LF	
			PD 2 FT. WHITE MINISKIP (2X)		30 LF
			PI YELLOW DOUBLE CENTER (2X)		1940 LF
			TOTAL		
MARKERS					
M	YELLOW & YELLOW	PERMANENT RAISED PAVEMENT MARKERS	11 EA		

NOTE: FOR EACH PAINT PAVEMENT MARKING ITEM, '1X' IMPLIES A SINGLE APPLICATION, '2X' IMPLIES TWO APPLICATIONS, AND '3X' IMPLIES THREE APPLICATIONS.

PLANS PREPARED BY:
TGS ENGINEERS
 SUITE 141
 975 WALNUT STREET
 CARY, NC 27511
 PH (919) 319-8850
 CORP. LICENSE NO. C-0275

APPROVED: _____ DATE: _____

FINAL PAVEMENT MARKINGS & SCHEDULE

SCALE: NONE		REVISIONS
DATE: OCT10		
DWG. BY: SGM		
DESIGN BY: JLT		
REVIEWED BY: JLT		

\$\$\$\$\$SYTIME\$\$\$\$\$
 \$\$\$\$\$\$USER\$\$\$\$\$
 \$\$\$\$\$\$DATE\$\$\$\$\$