

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0004	0063000000-N	SP	GRADING	Lump Sum	L.S.	
000E	0106000000-E	230	BORROW EXCAVATION	20,000 CY		
000E	0163000000-E	250	REMOVAL OF EXISTING CONCRETE PAVEMENT	9,700 SY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
000E	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	1,400 SY		
000E	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	120 TON		
001C	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	360 SY		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	92 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	64 LF		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	784 LF		
0014	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	92 LF		
001E	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	16 LF		
001E	0453000000-E	310	*** PIPE END SECTION (15")	2 EA		
0017	0453000000-E	310	*** PIPE END SECTION (18")	4 EA		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0453000000-E	310	*** PIPE END SECTION (24")	21 EA		
001E	1099500000-E	505	SHALLOW UNDERCUT	300 CY		
002C	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	231 TON		
0022	1245000000-E	SP	SHOULDER RECONSTRUCTION	34.36 SMI		
002E	1297000000-E	607	MILLING ASPHALT PAVEMENT, *** DEPTH (2")	34,906 SY		
0024	1297000000-E	607	MILLING ASPHALT PAVEMENT, *** DEPTH (3")	117,167 SY		
002E	1297000000-E	607	MILLING ASPHALT PAVEMENT, *** DEPTH (5-1/2")	25,719 SY		
002E	1297000000-E	607	MILLING ASPHALT PAVEMENT, *** DEPTH (8")	16,662 SY		
0027	1308000000-E	607	MILLING ASPHALT PAVEMENT, *** TO ***** (0" TO 2-1/2")	14,080 SY		
002E	1308000000-E	607	MILLING ASPHALT PAVEMENT, *** TO ***** (0" TO 5")	2,640 SY		
002E	1308000000-E	607	MILLING ASPHALT PAVEMENT, *** TO ***** (2-1/2" TO 9")	2,112 SY		
003C	1330000000-E	607	INCIDENTAL MILLING	11,669 SY		
0031	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	22,678 TON		
0032	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	26,697 TON		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	95 TON		
0034	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	40,120 TON		
0035	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	330 TON		
0036	1526000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S4.75A	350 TON		
0037	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	4,718 TON		
0038	1704000000-E	SP	PATCHING EXISTING PAVEMENT	283 TON		
0039	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	180,000 LF		
004C	1880000000-E	SP	GENERIC PAVING ITEM AGGREGATE BASE COURSE, CRACK REPAIR	2,100 TON		
0041	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT CONC BASE COURSE, TYPE B25.0C, CRACK REPAIR	2,200 TON		
0042	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT CONC INTERMEDIATE COURSE TYPE I19.0C (LEVELING COURSE)	361 TON		
0043	2253000000-E	840	PIPE COLLARS	20 CY		
0044	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	18 EA		
0045	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	8 EA		
0046	2396000000-N	840	FRAME WITH COVER, STD 840.54	10 EA		
0047	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	1,800 LF		
0048	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	1,300 LF		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0049	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	2,500 SY		
005C	3030000000-E	862	STEEL BM GUARDRAIL	5,000 LF		
0051	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III MOD FOR POST & BEAM RAIL)	3 EA		
0052	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		
0053	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	28 EA		
0054	3360000000-E	863	REMOVE EXISTING GUARDRAIL	5,000 LF		
005E	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
005E	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	208,000 LF		
0057	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	31,300 LF		
005E	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	1,450 LF		
005E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	340 LF		
006C	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	12 EA		
0061	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	333 EA		
0062	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)	550 LF		
0063	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	155,000 LF		
0064	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	550 LF		

County : Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	1,750	EA	
006E	6000000000-E	1605	TEMPORARY SILT FENCE	2,900	LF	
0067	6012000000-E	1610	SEDIMENT CONTROL STONE	75	TON	
006E	6030000000-E	1630	SILT EXCAVATION	300	CY	
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	780	SY	
007C	6042000000-E	1632	1/4" HARDWARE CLOTH	1,000	LF	
0071	6071010000-E	SP	WATTLE	1,400	LF	
0072	6071020000-E	SP	POLYACRYLAMIDE (PAM)	60	LB	
007E	6084000000-E	1660	SEEDING & MULCHING	47	ACR	

1006/Mar29/Q960448.36/D173062730000/E73

Total Amount Of Bid For Entire Project :

**Contract No.**     **C202944**

**County (ies):**   **Columbus**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General