

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (19+78.00-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	16 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	362 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	65 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	210 SY		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	68 LF		
0013	0344000000-E	310	18" SIDE DRAIN PIPE	232 LF		
0014	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (15")	4 EA		
0015	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	212 LF		
0016	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	92 LF		
0017	1099500000-E	505	SHALLOW UNDERCUT	131 CY		
0018	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	250 TON		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1121000000-E	520	AGGREGATE BASE COURSE	1,410 TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0021	1275000000-E	600	PRIME COAT	950 GAL		
0022	1330000000-E	607	INCIDENTAL MILLING	250 SY		
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	500 TON		
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	490 TON		
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,020 TON		
0026	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	107 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0028	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0029	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0030	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0031	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0032	2077000000-E	815	6" OUTLET PIPE	6 LF		
0033	2209000000-E	838	ENDWALLS	6 CY		
0034	2264000000-E	840	PIPE PLUGS	0.454 CY		
0035	2275000000-E	SP	FLOWABLE FILL	72 CY		
0036	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0037	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0039	2556000000-E	846	SHOULDER BERM GUTTER	230 LF		
0040	3030000000-E	862	STEEL BM GUARDRAIL	587.5 LF		
0041	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	37.5 LF		
0042	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0043	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0044	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0045	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0046	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	687.5 LF		
0047	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (B-77)	4 EA		
0048	3389100000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0049	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (4)	160 LF		
0050	3628000000-E	876	RIP RAP, CLASS I	17 TON		
0051	3649000000-E	876	RIP RAP, CLASS B	6 TON		
0052	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	512 SY		
0053	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	392 SF		
0054	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	160 SF		
0055	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	56 SF		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4430000000-N	1130	DRUMS	71 EA		
0057	4435000000-N	1135	CONES	30 EA		
0058	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0059	4450000000-N	1150	FLAGGER	1,620 HR		
0060	4516000000-N	1180	SKINNY DRUM	30 EA		
0061	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	78 EA		
0062	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	380 LF		
0063	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	20,183 LF		
0064	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	124 LF		
0065	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	12 EA		
0066	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	5,272 LF		
0067	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	18 EA		
0068	6000000000-E	1605	TEMPORARY SILT FENCE	5,535 LF		
0069	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	315 TON		
0070	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	305 TON		
0071	6012000000-E	1610	SEDIMENT CONTROL STONE	235 TON		
0072	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0073	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0075	6024000000-E	1622	TEMPORARY SLOPE DRAINS	300 LF		
0076	6029000000-E	SP	SAFETY FENCE	200 LF		
0077	6030000000-E	1630	SILT EXCAVATION	460 CY		
0078	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,000 SY		
0079	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	230 SY		
0080	6042000000-E	1632	1/4" HARDWARE CLOTH	415 LF		
0081	6071010000-E	SP	WATTLE	540 LF		
0082	6071020000-E	SP	POLYACRYLAMIDE (PAM)	135 LB		
0083	6071030000-E	1640	COIR FIBER BAFFLE	115 LF		
0084	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0085	6087000000-E	1660	MOWING	2 ACR		
0086	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0087	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0088	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0089	6108000000-E	1665	FERTILIZER TOPDRESSING	3.5 TON		
0090	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0091	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0092	6123000000-E	1670	REFORESTATION	0.1 ACR		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0093	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (19+78.00-L-)	Lump Sum	L.S.	
0094	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (19+78.00-L-)	Lump Sum	L.S.	
0095	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+78.00-L-)	Lump Sum	L.S.	
0096	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (19+78.00-L-)	Lump Sum	L.S.	
0097	8156000000-E	SP	CONCRETE WEARING SURFACE	4,042 SF		
0098	8161000000-E	420	GROOVING BRIDGE FLOORS	5,588 SF		
0099	8196000000-E	420	CLASS A CONCRETE (CULVERT)	49.2 CY		
0100	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+78.00-L-)	Lump Sum	L.S.	
0101	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,528 LB		
0102	8364000000-E	450	HP12X53 STEEL PILES	400 LF		
0103	8391000000-N	450	STEEL PILE POINTS	10 EA		
0104	8503000000-E	460	CONCRETE BARRIER RAIL	195.21 LF		
0105	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	54 TON		
0106	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	60 SY		
0107	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0108	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
0109	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,464.06 LF		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	8892000000-E	SP	GENERIC STRUCTURE ITEM 18" STEEL SHEET PILES	1,550	SF	

0844/Apr11/Q77011.174/D459672560000/E110

Total Amount Of Bid For Entire Project :

Contract No. **C202819**

County (ies): **Watauga**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General