

County : Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	1,835 CY		
0003	1220000000-E	545	INCIDENTAL STONE BASE	923 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	93.36 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	6,433 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 1-1/2")	80,025 SY		
0007	1330000000-E	607	INCIDENTAL MILLING	6,875 SY		
0008	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	178 TON		
0009	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	55,201 TON		
0010	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	22,011 TON		
0011	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	4,793 TON		
0012	1704000000-E	SP	PATCHING EXISTING PAVEMENT	7,800 TON		
0013	2600000000-N	SP	RETROFIT EXISTING CURB RAMP	126 EA		
0014	2605000000-N	848	CONCRETE CURB RAMP	37 EA		
0015	2830000000-N	858	ADJUSTMENT OF MANHOLES	104 EA		
0016	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	97 EA		
0017	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0018	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	291,782 LF		

County : Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	374,562 LF		
0020	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	870 LF		
0021	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	5,485 LF		
0022	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	350 LF		
0023	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	2,439 LF		
0024	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	163 EA		
0025	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	554 EA		
0026	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	837,915 LF		
0027	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	280 LF		
0028	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	100 LF		
0029	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	274 LF		
0030	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	10 EA		
0031	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	5,906 EA		
0032	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0033	6000000000-E	1605	TEMPORARY SILT FENCE	4,590 LF		
0034	6036000000-E	1631	MATTING FOR EROSION CONTROL	390 SY		
0035	6071010000-E	SP	WATTLE	790 LF		

County : Cumberland, Harnett

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	6071020000-E	SP	POLYACRYLAMIDE (PAM)	33 LB		
0037	6084000000-E	1660	SEEDING & MULCHING	86.45 ACR		
0038	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	270 LF		
0039	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	2,700 LF		
0040	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	27 EA		
0041	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	27 EA		
0042	7420000000-E	1722	2" RISER WITH WEATHERHEAD	27 EA		
0043	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	32,865 LF		
0044	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	2,700 LF		

1709/May09/Q1751729.81/D183353130000/E44

Total Amount Of Bid For Entire Project :

**Contract No.     C203072**

**County (ies):    Cumberland/Harnett**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General