

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (25+99.88)	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	700 CY		
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	12,400 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	700 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	1,400 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	100 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	300 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	888 LF		
0012	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	4 EA		
0013	0995000000-E	340	PIPE REMOVAL	279 LF		
0014	1099500000-E	505	SHALLOW UNDERCUT	200 CY		
0015	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	400 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0017	1330000000-E	607	INCIDENTAL MILLING	400 SY		
0018	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,340 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	840	TON	
0020	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,090	TON	
0021	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	20	TON	
0022	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	210	TON	
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4	EA	
0024	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	4	EA	
0025	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	540	LF	
0026	3030000000-E	862	STEEL BM GUARDRAIL	2,925	LF	
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10	EA	
0028	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2	EA	
0029	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2	EA	
0030	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
0031	3360000000-E	863	REMOVE EXISTING GUARDRAIL	2,634	LF	
0032	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	1,212.5	LF	
0033	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (CAT-1)	1	EA	
0034	3435000000-N	SP	GENERIC GUARDRAIL ITEM EXTRA LENGTH GUARDRAIL POST (8' STEEL)	54	EA	
0035	3500000000-E	866	WOVEN WIRE FENCE, *** FABRIC (48")	290	LF	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3506000000-E	866	4" TIMBER FENCE POSTS, ***** LONG (8'-0")	20 EA		
0037	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	10 EA		
0038	3649000000-E	876	RIP RAP, CLASS B	4 TON		
0039	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	395 SY		
0040	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	50 LF		
0041	4096000000-N	904	SIGN ERECTION, TYPE D	1 EA		
0042	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
0043	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	2 EA		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	710 SF		
0045	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	110 SF		
0046	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	40 SF		
0047	4415000000-N	1115	FLASHING ARROW BOARD	2 EA		
0048	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
0049	4430000000-N	1130	DRUMS	210 EA		
0050	4445000000-E	1145	BARRICADES (TYPE III)	40 LF		
0051	4450000000-N	1150	FLAGGER	200 HR		
0052	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0053	4480000000-N	1165	TMA	2 EA		
0054	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,480 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4510000000-N	SP	LAW ENFORCEMENT	100 HR		
0056	4590000000-E	SP	GENERIC TRAFFIC CONTROL ITEM WORK ZONE ASPHALT ISLAND	2,158 LF		
0057	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	50 EA		
0058	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	6,721 LF		
0059	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	2,604 LF		
0060	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (II)	997 LF		
0061	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	12,500 LF		
0062	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,300 LF		
0063	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	100 LF		
0064	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	10,000 LF		
0065	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	9,000 LF		
0066	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,300 LF		
0067	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	100 LF		
0068	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	133 EA		
0069	6000000000-E	1605	TEMPORARY SILT FENCE	1,050 LF		
0070	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160 TON		
0071	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	165 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6012000000-E	1610	SEDIMENT CONTROL STONE	115 TON		
0073	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0074	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0075	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5 TON		
0076	6024000000-E	1622	TEMPORARY SLOPE DRAINS	400 LF		
0077	6030000000-E	1630	SILT EXCAVATION	300 CY		
0078	6036000000-E	1631	MATTING FOR EROSION CONTROL	4,000 SY		
0079	6037000000-E	SP	COIR FIBER MAT	10 SY		
0080	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,500 SY		
0081	6042000000-E	1632	1/4" HARDWARE CLOTH	250 LF		
0082	6071010000-E	SP	WATTLE	350 LF		
0083	6071020000-E	SP	POLYACRYLAMIDE (PAM)	50 LB		
0084	6071030000-E	1640	COIR FIBER BAFFLE	100 LF		
0085	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0086	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
0087	6087000000-E	1660	MOWING	2 ACR		
0088	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0089	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0090	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0091	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0093	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0094	7060000000-E	1705	SIGNAL CABLE	4,450 LF		
0095	7108000000-E	1705	VEHICLE SIGNAL HEAD (12", 1 SECTION)	16 EA		
0096	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	10 EA		
0097	7264000000-E	1710	MESSENGER CABLE (3/8")	530 LF		
0098	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	840 LF		
0099	7300100000-E	1715	UNPAVED TRENCHING FOR TEMP- ORARY LEAD-IN	615 LF		
0100	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	100 LF		
0101	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	9 EA		
0102	7360000000-N	1720	WOOD POLE	4 EA		
0103	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0104	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0105	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
0106	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	600 LF		
0107	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	2,162 LF		
0108	7636000000-N	1745	SIGN FOR SIGNALS	11 EA		
0109	7642300000-N	1743	TYPE III PEDESTAL WITH FOUND- ATION	4 EA		
0110	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0111	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		
0112	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	4 EA		
0113	7816000000-N	1751	DETECTOR CARD (NEMA TS-1)	2 EA		
0114	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		
0115	7912000000-N	1755	BEACON CONTROLLER ASSEMBLY & CABINET (*****) (F3)	1 EA		
0134	0199000000-E	SP	TEMPORARY SHORING	1,674 SF		
WALL ITEMS						
0116	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 1	4,300 SF		
STRUCTURE ITEMS						
0117	8014000000-N	SP	TEMPORARY RAILROAD SHORING FOR BENT ***, STATION ***** (1, 25+73.32-L)	Lump Sum	L.S.	
0118	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (25+73.32-L-)	Lump Sum	L.S.	
0119	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 25+73.32-L-)	Lump Sum	L.S.	
0120	8112730000-N	450	PDA TESTING	2 EA		
0121	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (25+73.32-L-)	Lump Sum	L.S.	
0122	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	11,194 SF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0123	8161000000-E	420	GROOVING BRIDGE FLOORS	11,066 SF		
0124	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	443.1 CY		
0125	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (25+73.32-L-)	Lump Sum	L.S.	
0126	8217000000-E	425	REINFORCING STEEL (BRIDGE)	43,605 LB		
0127	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	1,324.05 LF		
0128	8364000000-E	450	HP12X53 STEEL PILES	1,150 LF		
0129	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (24 X 0.50)	1,215 LF		
0130	8503000000-E	460	CONCRETE BARRIER RAIL	586.93 LF		
0131	8531000000-E	462	4" SLOPE PROTECTION	700 SY		
0132	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0133	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
0135	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (2, 25+73.32-L-)	Lump Sum	L.S.	

0851/Jun07/Q176036.33/D675447490000/E135

Total Amount Of Bid For Entire Project :

Contract No. **C202822**

County (ies): **Johnston**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General

Signature Sheet (Bid - Acceptance by Department)