

SPECIAL PROVISIONS**4" Check Valve Assembly with Manhole**

Furnish all labor, equipment, and materials required for installation of the 4" check valve assemblies at the locations indicated on the plans, or at the locations designated by the Engineer. The listed price shall be for full compensation of all work and expense incidental thereto for furnishing and installing complete check valve assemblies within pre-cast concrete manholes. The price listed shall include all materials required for a complete assembly, including, but not limited to: check valve, isolation valves, 401 lined ductile iron piping, 401 lined mechanical joint fittings with restrained retainer glands, flange coupling adaptors, transition fittings and gaskets, precast concrete manhole, cast iron frame and cover, bedding materials. Check valves shall be horizontal swing type with an outside weighted swing lever arm, epoxy coated cast iron body, stainless steel hardware, bronze, mounted, full opening, 125 lb. ANSI standard flanged, and suitable for at least 150 psi pressure. All materials shall be suitable for pressure sewer service and comply with Sections 1520 and 1034 of the standard specifications.

Basis of Payment:

Generic Utility Item (4" Check Valve Assembly with Manhole), per each.

Reconnect Ex. Pressure Sewer Services

Furnish all labor, equipment, and materials required for reconnection of existing pressure sewer services by means of transferring or replacing the piping from an existing pressure sewer service on an existing force main, to a new force main. All pressure sewer services on existing force mains shown to be abandoned or removed shall be reconnected to new force mains, as indicated on the plans or as directed by the Engineer. The listed price shall be for full compensation of all work and expense incidental thereto for reconnection of existing pressure sewer services. The materials used to transfer or replace existing pressure sewer services are to be of the same size and type materials of the existing pressure sewer services. The price stated shall include all materials required for complete reconnection of existing pressure sewer services and full restoration of pressure sewer service. Materials shall include, but not be limited to: tapping saddles, tapping valves, pipe, fittings, couplings, sleeves, transition fittings and gaskets, bedding materials. All materials shall be suitable for pressure sewer service and comply with Sections 1520 and 1034 of the standard specifications.

Basis of Payment:

Generic Utility Item (Reconnect Ex. Pressure Sewer Services), per each.

Ch. J. Mully



1730 Varsity Driver, Suite 500
Raleigh, NC 27606
License No. F-1222

5/10/12

UTILITY RELOCATION BY OTHERS

All utilities adjacent to SR 1200 (Lebanon Church Road) will be relocated, outside roadway construction limits, by others prior to the beginning of construction. Notify Department personnel and the utility owner 2 weeks before commencement of any work. Make investigations for determining the exact location, size and type of material of the relocated facilities as necessary to avoid conflicts during construction.