

County : Northampton

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	638 TON		
000E	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	2,000 SY		
0006	0342000000-E	310	*** SIDE DRAIN PIPE (30")	84 LF		
0007	0343000000-E	310	15" SIDE DRAIN PIPE	1,615 LF		
000E	0344000000-E	310	18" SIDE DRAIN PIPE	628 LF		
0009	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	432 LF		
001C	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	274 LF		
0011	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	20 LF		
0012	0995000000-E	340	PIPE REMOVAL	2,074 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0014	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,188 TON		
001E	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	8,500 TON		
001E	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	8,100 TON		
0017	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	982 TON		
001E	1891000000-E	SP	GENERIC PAVING ITEM FLEXIBLE PAVEMENT RECLAMATION, 12"	52,000 SY		

County : Northampton

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2209000000-E	838	ENDWALLS	2.3 CY		
002C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0021	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3 EA		
0022	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0023	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	360 LF		
0024	2612000000-E	848	6" CONCRETE DRIVEWAY	30 SY		
002E	2759000000-N	SP	GENERIC PAVING ITEM CONCRETE FLUME	5 EA		
002E	3030000000-E	862	STEEL BM GUARDRAIL	100 LF		
0027	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	30 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	3 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
003C	3360000000-E	863	REMOVE EXISTING GUARDRAIL	186 LF		
0031	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (84")	29 EA		
0032	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (84")	4 EA		
0033	3551000000-E	866	METAL GATE POSTS FOR *** CHAIN LINK FENCE, SINGLE GATE (84")	4 EA		
0034	3564000000-E	866	SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (84", 30', 24')	2 EA		

County : Northampton

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3580000000-E	866	GENERIC FENCING ITEM CHAIN LINK FENCE WITH BARBED WIRE, 84"	235 LF		
003E	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0037	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	47,822 LF		
003E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	39,901 LF		
003E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	10 EA		
004C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	90,000 LF		
0041	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	10 EA		
0042	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	390 EA		
004E	5326200000-E	1510	12" WATER LINE	3,000 LF		
0044	5538000000-E	1515	4" VALVE	5 EA		
004E	5540000000-E	1515	6" VALVE	2 EA		
004E	5558000000-E	1515	12" VALVE	4 EA		
0047	5648000000-N	1515	RELOCATE WATER METER	15 EA		
004E	5649000000-N	1515	RECONNECT WATER METER	15 EA		
004E	5672000000-N	1515	RELOCATE FIRE HYDRANT	2 EA		
005C	5709100000-E	1520	2" FORCE MAIN SEWER	20 LF		
0051	5709200000-E	1520	4" FORCE MAIN SEWER	2,575 LF		
0052	5709300000-E	1520	6" FORCE MAIN SEWER	2,470 LF		

County : Northampton

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	5798000000-E	1530	ABANDON *** UTILITY PIPE (4")	350 LF		
0054	5800000000-E	1530	ABANDON 6" UTILITY PIPE	350 LF		
005E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	2,980 LF		
005E	5816000000-N	1530	ABANDON UTILITY MANHOLE	1 EA		
0057	5835600000-E	1540	12" ENCASEMENT PIPE	180 LF		
005E	5882000000-N	SP	GENERIC UTILITY ITEM 4" CHECK VALVE ASSEMBLY WITH MANHOLE	3 EA		
005E	5882000000-N	SP	GENERIC UTILITY ITEM RECONNECT EXIST PRESSURE SEWER SERVICES	3 EA		
006C	6000000000-E	1605	TEMPORARY SILT FENCE	2,690 LF		
0061	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	260 TON		
0062	6012000000-E	1610	SEDIMENT CONTROL STONE	260 TON		
0063	6015000000-E	1615	TEMPORARY MULCHING	9 ACR		
0064	6029000000-E	SP	SAFETY FENCE	2,000 LF		
006E	6030000000-E	1630	SILT EXCAVATION	20 CY		
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,500 SY		
0067	6037000000-E	SP	COIR FIBER MAT	1,475 SY		
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	630 LF		
006E	6069000000-E	1638	STILLING BASINS	434 CY		
007C	6071012000-E	SP	COIR FIBER WATTLE	1,524 LF		
0071	6071020000-E	SP	POLYACRYLAMIDE (PAM)	115 LB		

County : Northampton

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6071030000-E	1640	COIR FIBER BAFFLE	428	LF	
0073	6084000000-E	1660	SEEDING & MULCHING	6.1	ACR	
0074	6090000000-E	1661	SEED FOR REPAIR SEEDING	420	LB	
0075	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	3	TON	
0076	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200	LB	
0077	6108000000-E	1665	FERTILIZER TOPDRESSING	2	TON	
0078	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	5	EA	

1346/May18/Q288877.4/D309118762000/E78

Total Amount Of Bid For Entire Project :

Contract No. C203056

County (ies): Northampton

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General