

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0003	1220000000-E	545	INCIDENTAL STONE BASE	2,728 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	13.64 SMI		
0005	1330000000-E	607	INCIDENTAL MILLING	1,466 SY		
0006	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	8,049 TON		
0007	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	16,437 TON		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	9,658 TON		
0009	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,723 TON		
0010	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0011	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	73,383 LF		
0012	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	45,012 LF		
0013	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	25 LF		
0014	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	118,395 LF		
0015	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	25 LF		
0016	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	400 EA		
0017	6000000000-E	1605	TEMPORARY SILT FENCE	400 LF		
0018	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	10 TON		
0019	6071010000-E	SP	WATTLE	150 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
0021	6084000000-E	1660	SEEDING & MULCHING	8 ACR		
0022	0255000000-E	SP	GENERIC GRADING ITEM AGGREGATE SHOULDER BORROW	4,640 TON		
1253/Jul11/Q282549.64/D73396130000/E21			Total Amount Of Bid For Entire Project :			

Contract No. **C203096**

County (ies): **Beaufort**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General