



PROJECT SPECIAL PROVISIONS  
Utility Construction

All proposed utility construction shall meet the applicable requirements of the NC Department of Transportation's Standard Specifications for Roads and Structures dated January 12, 2012.

Revise the *2012 Standard Specifications* as follows:

**Utility Owner's Contact Information:**

**Page 15-1, Subarticle 1500-2 Cooperation with the Utility Owner**, paragraph 2, add the following sentences:

All water lines on this project belong to Columbus County Public Utilities.

The Contractor shall provide access for the owner's representatives during construction. A preconstruction meeting shall be held with Columbus County Water, the Utility Contractor and the D.O.T prior to any work beginning. The Contractor shall notify the owner two weeks before commencement of any work and three weeks before service interruption.

The contact person for Columbus County Water is Mr. Kip McClary, he can be contacted at 910-642-5257.

**Water Testing and Sterilization:**

**Page 15-6, 1510-3(B) Subarticle Construction Methods**, after line 21, replace the allowable leakage formula with the following:

$$W=LD(\sqrt{P})\div 148,000$$

**Page 15-6, 1510-3(B) Construction Methods**, line 32, delete "concurrently or".

PROJECT SPECIAL PROVISIONS  
Utilities by Others

General:

The following utility companies have facilities that will be in conflict with the construction of this project.

A. Telephone (CenturyLink)

The conflicting facilities of these concerns will be adjusted prior to the date of availability unless noted otherwise and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owners. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

A. CenturyLink (Telephone)

See "Utilities By Others Plans" for details

Contact person: Kevin Godwin (910-366-2142)