

County : Graham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1245000000-E	SP	SHOULDER RECONSTRUCTION	6.6 SMI		
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	44,698 SY		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (5")	14,020 SY		
0005	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,187 TON		
0006	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,455 TON		
0007	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	2,142 TON		
0008	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	564 TON		
0009	2591000000-E	848	4" CONCRETE SIDEWALK	13.3 SY		
001C	2605000000-N	848	CONCRETE CURB RAMP	6 EA		
0011	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0012	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	11 EA		
0013	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	648 SF		
0014	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
001E	4415000000-N	1115	FLASHING ARROW BOARD	1 EA		
0016	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	3 EA		
0017	4430000000-N	1130	DRUMS	25 EA		
001E	4516000000-N	1180	SKINNY DRUM	100 EA		

County : Graham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	22,964	LF	
002C	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	15,175	LF	
0021	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	268	LF	
0022	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	231	LF	
0023	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	610	LF	
0024	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	69	EA	
002E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	113,296	LF	
002E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	162	EA	
0027	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1)	10	EA	
002E	7060000000-E	1705	SIGNAL CABLE	2,420	LF	
002E	7264000000-E	1710	MESSENGER CABLE (3/8")	180	LF	
003C	7300000000-E	1715	UNPAVED TRENCHING (*****)(1, 2")	90	LF	
0031	7300000000-E	1715	UNPAVED TRENCHING (*****)(2, 2")	115	LF	
0032	7360000000-N	1720	WOOD POLE	1	EA	
0033	7372000000-N	1721	GUY ASSEMBLY	2	EA	
0034	7396000000-E	1722	1/2" RISER WITH WEATHERHEAD	4	EA	
003E	7408000000-E	1722	1" RISER WITH WEATHERHEAD	5	EA	

County : Graham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	7420000000-E	1722	2" RISER WITH WEATHERHEAD	2	EA	
0037	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	870	LF	
003E	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	3,010	LF	
003E	7642200000-N	1743	TYPE II PEDESTAL WITH FOUND- ATION	4	EA	
004C	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1	EA	
0041	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1	EA	
0042	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	4	EA	
0043	7901000000-N	1753	CABINET BASE EXTENDER	1	EA	
			1443/Jun07/Q229472.9/D211876300000/E43	Total Amount Of Bid For Entire Project :		

Contract No. **C203109**

County (ies): **Graham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)