

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (15+52.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	700 CY		
0007	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	700 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	700 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	41 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	223 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	16 LF		
0012	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	28 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	290 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	300 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	35 TON		
0017	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0018	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0020	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0021	2077000000-E	815	6" OUTLET PIPE	6 LF		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	60 LF		
0025	3030000000-E	862	STEEL BM GUARDRAIL	125 LF		
0026	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0028	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0029	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	450 SY		
0030	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0031	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	6 EA		
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	336 SF		
0033	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0034	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	114 SF		
0035	4435000000-N	1135	CONES	20 EA		
0036	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0037	4455000000-N	1150	FLAGGER	10 DAY		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4810000000-E	1205	PAIN T PAVEMENT MARKING LINES (4")	4,016 LF		
0039	5326200000-E	1510	12" WATER LINE	614 LF		
0040	5558000000-E	1515	12" VALVE	2 EA		
0041	5804000000-E	1530	ABANDON 12" UTILITY PIPE	592 LF		
0042	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	513 LF		
0043	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	57 LF		
0044	6000000000-E	1605	TEMPORARY SILT FENCE	1,335 LF		
0045	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0046	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5 TON		
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	50 TON		
0048	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0049	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0050	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0051	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0052	6029000000-E	SP	SAFETY FENCE	800 LF		
0053	6030000000-E	1630	SILT EXCAVATION	100 CY		
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,525 SY		
0055	6042000000-E	1632	1/4" HARDWARE CLOTH	240 LF		
0056	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	150 SY		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0058	6087000000-E	1660	MOWING	0.5 ACR		
0059	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0060	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0061	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0062	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0063	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0064	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
0065	6123000000-E	1670	REFORESTATION	0.1 ACR		
<b>STRUCTURE ITEMS</b>						
0066	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+52.00-L-)	Lump Sum	L.S.	
0067	8112730000-N	450	PDA TESTING	1 EA		
0068	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+52.00-L-)	Lump Sum	L.S.	
0069	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	57 CY		
0070	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+52.00-L-)	Lump Sum	L.S.	
0071	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	9,648 LB		
0072	8333000000-E	450	16" PRESTRESSED CONCRETE PILES	1,050 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8364000000-E	450	HP12X53 STEEL PILES	1,050 LF		
0074	8393000000-N	450	PILE REDRIVES	16 EA		
0075	8475000000-E	460	TWO BAR METAL RAIL	244.23 LF		
0076	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 2'-10")	260.58 LF		
0077	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	185 TON		
0078	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	206 SY		
0079	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0080	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,430 LF		

1016/Jul05/Q29480.21/D367995740000/E80

Total Amount Of Bid For Entire Project :

**Contract No.**     **C202883**

**County (ies):**    **Beaufort**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General