

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+62.00-L-)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	9,900 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	150 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	15,830 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	1,200 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	2,250 SF		
0011	0241000000-E	SP	GENERIC GRADING ITEM FABRIC FOR EMBANKMENT STABIL- ZATION	500 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	80 TON		
0013	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	230 SY		
0014	0335200000-E	305	15" DRAINAGE PIPE	527 LF		
0015	0335300000-E	305	18" DRAINAGE PIPE	136 LF		
0016	0995000000-E	340	PIPE REMOVAL	265 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	1,931 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,420	TON	
0020	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	990	TON	
0021	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	130	TON	
0022	2022000000-E	815	SUBDRAIN EXCAVATION	22.4	CY	
0023	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	100	SY	
0024	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	16.8	CY	
0025	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100	LF	
0026	2070000000-N	815	SUBDRAIN PIPE OUTLET	1	EA	
0027	2077000000-E	815	6" OUTLET PIPE	6	LF	
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	12	EA	
0029	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	4.36	LF	
0030	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1	EA	
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2	EA	
0032	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	5	EA	
0033	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	4	EA	
0034	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,640	LF	
0035	2556000000-E	846	SHOULDER BERM GUTTER	11	LF	
0036	2591000000-E	848	4" CONCRETE SIDEWALK	300	SY	

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2605000000-N	848	CONCRETE CURB RAMP	2 EA		
0038	2612000000-E	848	6" CONCRETE DRIVEWAY	70 SY		
0039	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0040	3030000000-E	862	STEEL BM GUARDRAIL	12.5 LF		
0041	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	37.5 LF		
0042	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0043	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0044	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0045	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0046	3345000000-E	864	REMOVE & RESET EXISTING GUARD- RAIL	103 LF		
0047	3628000000-E	876	RIP RAP, CLASS I	130 TON		
0048	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	225 SY		
0049	5319000000-E	1505	CLASS B CONCRETE FOR ENCASING UTILITY LINES	2 CY		
0050	5325800000-E	1510	8" WATER LINE	469 LF		
0051	5326000000-E	1510	10" WATER LINE	22 LF		
0052	5546000000-E	1515	8" VALVE	1 EA		
0053	5552000000-E	1515	10" VALVE	2 EA		
0054	5804000000-E	1530	ABANDON 12" UTILITY PIPE	465 LF		
0055	5828000000-N	1530	REMOVE UTILITY MANHOLE	2 EA		

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6000000000-E	1605	TEMPORARY SILT FENCE	1,500 LF		
0057	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	10 TON		
0058	6012000000-E	1610	SEDIMENT CONTROL STONE	20 TON		
0059	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0060	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	225 LB		
0061	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.9 TON		
0062	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0063	6029000000-E	SP	SAFETY FENCE	100 LF		
0064	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,100 SY		
0065	6042000000-E	1632	1/4" HARDWARE CLOTH	350 LF		
0066	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	25 SY		
0067	6071010000-E	SP	WATTLE	150 LF		
0068	6071020000-E	SP	POLYACRYLAMIDE (PAM)	5 LB		
0069	6084000000-E	1660	SEEDING & MULCHING	4.6 ACR		
0070	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0071	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0094	6070000000-N	1639	SPECIAL STILLING BASINS	5 EA		
0095	6111000000-E	SP	IMPERVIOUS DIKE	300 LF		

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
0072	8126000000-N	414	CULVERT EXCAVATION, STA ***** (12+91.63-Y-)	Lump Sum	L.S.	
0073	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	80 TON		
0074	8196000000-E	420	CLASS A CONCRETE (CULVERT)	80.6 CY		
0075	8248000000-E	425	EPOXY COATED REINFORCING STEEL (CULVERT)	11,634 LB		
STRUCTURE ITEMS						
0076	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+62.00-L-)	Lump Sum	L.S.	
0077	8112730000-N	450	PDA TESTING	3 EA		
0078	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (14+62.00-L-)	Lump Sum	L.S.	
0079	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	154 CY		
0080	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+62.00-L-)	Lump Sum	L.S.	
0081	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	23,349 LB		
0082	8364000000-E	450	HP12X53 STEEL PILES	780 LF		
0083	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	3,200 LF		
0084	8391000000-N	450	STEEL PILE POINTS	40 EA		
0085	8393000000-N	450	PILE REDRIVES	26 EA		
0086	8475000000-E	460	TWO BAR METAL RAIL	569.1 LF		

County : Craven

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	8517000000-E	460	1'-***X ***** CONCRETE PARA-PET (1'-2" x 3'-3")	601.46	LF	
0088	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	590	TON	
0089	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	655	SY	
0090	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0091	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	3,220	LF	
0092	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	980	LF	
0093	8860000000-N	SP	GENERIC STRUCTURE ITEM ELECTRICAL CONDUIT SYSTEM AT STA14+62.00-L-	Lump Sum	L.S.	
1649/Aug15/Q93369.47/D413956760000/E95				Total Amount Of Bid For Entire Project :		

Contract No. **C202845**

County (ies): **Craven**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General