

County : Perquimans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0003	0106000000-E	230	BORROW EXCAVATION	4,862 CY		
0004	0195000000-E	265	SELECT GRANULAR MATERIAL	520 CY		
0005	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	780 SY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	150 TON		
0007	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	1,375 SY		
0008	0335300000-E	305	18" DRAINAGE PIPE	169 LF		
0009	0335400000-E	305	24" DRAINAGE PIPE	266 LF		
0010	0335500000-E	305	30" DRAINAGE PIPE	183 LF		
0011	0335600000-E	305	36" DRAINAGE PIPE	144 LF		
0012	0335700000-E	305	42" DRAINAGE PIPE	48 LF		
0013	0335800000-E	305	48" DRAINAGE PIPE	153 LF		
0014	0342000000-E	310	*** SIDE DRAIN PIPE (12")	99 LF		
0015	0343000000-E	310	15" SIDE DRAIN PIPE	868 LF		
0016	0344000000-E	310	18" SIDE DRAIN PIPE	184 LF		
0017	0345000000-E	310	24" SIDE DRAIN PIPE	40 LF		
0018	0995000000-E	340	PIPE REMOVAL	1,224 LF		
0019	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		

County : Perquimans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,480 TON		
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	6,480 TON		
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,130 TON		
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	608 TON		
0024	2209000000-E	838	ENDWALLS	6.6 CY		
0025	2612000000-E	848	6" CONCRETE DRIVEWAY	413 SY		
0026	3628000000-E	876	RIP RAP, CLASS I	68 TON		
0027	3649000000-E	876	RIP RAP, CLASS B	48 TON		
0028	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	310 SY		
0029	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0030	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	28,127 LF		
0031	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	17,252 LF		
0032	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	28,127 LF		
0033	6000000000-E	1605	TEMPORARY SILT FENCE	261 LF		
0034	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	50 TON		
0035	6012000000-E	1610	SEDIMENT CONTROL STONE	50 TON		
0036	6015000000-E	1615	TEMPORARY MULCHING	2.6 ACR		
0037	6030000000-E	1630	SILT EXCAVATION	20 CY		

County : Perquimans

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	6036000000-E	1631	MATTING FOR EROSION CONTROL	120		
				SY		
003E	6042000000-E	1632	1/4" HARDWARE CLOTH	130		
				LF		
004C	6071012000-E	SP	COIR FIBER WATTLE	360		
				LF		
0041	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10		
				LB		
0042	6084000000-E	1660	SEEDING & MULCHING	12		
				ACR		
0043	6090000000-E	1661	SEED FOR REPAIR SEEDING	130		
				LB		
0044	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.7		
				TON		
004E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	150		
				LB		
004E	6108000000-E	1665	FERTILIZER TOPDRESSING	1		
				TON		
0047	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	5		
				EA		

1021/Jul05/Q99469.9/D138089432000/E47

Total Amount Of Bid For Entire Project :

Contract No. **C203169**

County (ies): **Perquimans**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General