

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000910000-N	SP	GENERIC MISCELLANEOUS ITEM WATER TRUCK FOR DUST CONTROL	375 HR		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (14 + 42)	Lump Sum	L.S.	
000E	0043000000-N	226	GRADING	Lump Sum	L.S.	
000E	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	1,200 CY		
000E	0195000000-E	265	SELECT GRANULAR MATERIAL	1,200 CY		
000E	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	1,200 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	50 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	255 SY		
0012	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	88 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	5,100 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	450 TON		
001E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	410 TON		
001E	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	45 TON		
0017	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
001E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
002C	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0021	2077000000-E	815	6" OUTLET PIPE	6 LF		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	95 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	475 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3649000000-E	876	RIP RAP, CLASS B	1 TON		
003C	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	455 SY		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	379 SF		
0032	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0034	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
003E	4455000000-N	1150	FLAGGER	10 DAY		
003E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,600 LF		
0037	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,600 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	12 EA		
003E	5325600000-E	1510	6" WATER LINE	674 LF		
004C	5540000000-E	1515	6" VALVE	2 EA		
0041	5648000000-N	1515	RELOCATE WATER METER	1 EA		
0042	5800000000-E	1530	ABANDON 6" UTILITY PIPE	660 LF		
0043	5871400000-E	1550	TRENCHLESS INSTALLATION OF 6" IN SOIL	504 LF		
0044	5871410000-E	1550	TRENCHLESS INSTALLATION OF 6" NOT IN SOIL	56 LF		
004E	6000000000-E	1605	TEMPORARY SILT FENCE	2,220 LF		
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0047	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	25 TON		
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	60 TON		
004E	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
005C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0051	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0052	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0053	6029000000-E	SP	SAFETY FENCE	1,000 LF		
0054	6030000000-E	1630	SILT EXCAVATION	100 CY		
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	265 LF		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	275 SY		
005E	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
005E	6087000000-E	1660	MOWING	1 ACR		
006C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0064	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
006E	6123000000-E	1670	REFORESTATION	0.1 ACR		

**STRUCTURE ITEMS**

0067	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14 + 42.00-L-)	Lump Sum	L.S.	
006E	8112730000-N	450	PDA TESTING	1 EA		
006E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14 + 42.00-L-)	Lump Sum	L.S.	
007C	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	30.6 CY		
0071	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14 + 42.00-L-)	Lump Sum	L.S.	
0072	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	4,976 LB		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8329000000-E	450	12" PRESTRESSED CONCRETE PILES	525 LF		
0074	8336000000-E	450	20" PRESTRESSED CONCRETE PILES	400 LF		
007E	8355000000-E	450	HP ***X*** STEEL PILES (10 X 57)	208 LF		
007E	8393000000-N	450	PILE REDRIVES	30 EA		
0077	8475000000-E	460	TWO BAR METAL RAIL	214.32 LF		
007E	8517000000-E	460	1'-***X***** CONCRETE PARA- PET (1'-2" X 2'-10")	230.57 LF		
007E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	207 TON		
008C	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	230 SY		
0081	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0082	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,380 LF		
0083	8897000000-N	SP	GENERIC STRUCTURE ITEM PRECAST PIECE B-01	4 EA		
0084	8897000000-N	SP	GENERIC STRUCTURE ITEM PRECAST PIECE B-02	2 EA		

**Contract No.**     **C202882**

**County (ies):**   **Beaufort**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

**Contract Officer**

---

**Date**

Execution of Contract and Bonds  
Approved as to Form:

---

**Attorney General**

Signature Sheet (Bid - Acceptance by Department)