

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21+37.80-Y-)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	2,500 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	39,500 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	2,000 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	3,100 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	1,889 SF		
0011	0262000000-N	SP	GENERIC GRADING ITEM ENERGY DISSIPATOR BASIN	2 EA		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	1,080 TON		
0013	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	3,530 SY		
0014	0335200000-E	305	15" DRAINAGE PIPE	60 LF		
0015	0343000000-E	310	15" SIDE DRAIN PIPE	56 LF		
0016	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,296 LF		
0017	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	660 LF		
0018	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	200 LF		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	912 LF		
0020	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	1,012 LF		
0021	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	2,004 LF		
0022	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	732 LF		
0023	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	452 LF		
0024	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	64 LF		
0025	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	304 LF		
0026	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	752 LF		
0027	0448700000-E	310	42" RC PIPE CULVERTS, CLASS IV	32 LF		
0028	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	156 LF		
0029	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	76 LF		
0030	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	8 EA		
0031	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (18", 0.064")	2 EA		
0032	0995000000-E	340	PIPE REMOVAL	2,135 LF		
0033	1099500000-E	505	SHALLOW UNDERCUT	1,000 CY		
0034	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	2,000 TON		
0035	1110000000-E	510	STABILIZER AGGREGATE	250 TON		
0036	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	1330000000-E	607	INCIDENTAL MILLING	247 SY		
0038	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	4,480 TON		
0039	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	3,900 TON		
0040	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,250 TON		
0041	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	2,630 TON		
0042	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	4,410 TON		
0043	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	5,430 TON		
0044	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,240 TON		
0045	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	70 TON		
0046	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	10,620 LF		
0047	2000000000-N	806	RIGHT OF WAY MARKERS	55 EA		
0048	2209000000-E	838	ENDWALLS	0.672 CY		
0049	2253000000-E	840	PIPE COLLARS	1.25 CY		
0050	2264000000-E	840	PIPE PLUGS	3.72 CY		
0051	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	80 EA		
0052	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	54 LF		
0053	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	19 EA		
0054	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	4 EA		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
0056	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	11 EA		
0057	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	6 EA		
0058	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	18 EA		
0059	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	7 EA		
0060	2396000000-N	840	FRAME WITH COVER, STD 840.54	12 EA		
0061	2538000000-E	846	***.*** CONCRETE CURB & GUTTER (8" X 12")	50 LF		
0062	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	3,060 LF		
0063	2556000000-E	846	SHOULDER BERM GUTTER	700 LF		
0064	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	1,936 LF		
0065	2591000000-E	848	4" CONCRETE SIDEWALK	1,090 SY		
0066	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	1,600 SY		
0067	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	200 LF		
0068	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	1 EA		
0069	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	5 EA		
0070	3030000000-E	862	STEEL BM GUARDRAIL	8,137.5 LF		
0071	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	242.39 LF		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	1 EA		
0073	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	25 EA		
0074	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	4 EA		
0075	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	5 EA		
0076	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0077	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	11 EA		
0078	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	8 EA		
0079	3360000000-E	863	REMOVE EXISTING GUARDRAIL	37 LF		
0080	3524000000-E	SP	VINYL COATED CHAIN LINK FENCE, *** FABRIC (48")	7,539 LF		
0081	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (48")	636 EA		
0082	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (48")	66 EA		
0083	3628000000-E	876	RIP RAP, CLASS I	7 TON		
0084	3649000000-E	876	RIP RAP, CLASS B	143 TON		
0085	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	2,495 SY		
0086	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	3 EA		
0087	4048000000-E	902	REINFORCED CONCRETE SIGN FOUNDATIONS	1 CY		
0088	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDATIONS	1 CY		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	1,219 LB		
0090	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	933 LF		
0091	4096000000-N	904	SIGN ERECTION, TYPE D	7 EA		
0092	4102000000-N	904	SIGN ERECTION, TYPE E	47 EA		
0093	4108000000-N	904	SIGN ERECTION, TYPE F	5 EA		
0094	4109000000-N	904	SIGN ERECTION, TYPE *** (OVER- HEAD) (A)	2 EA		
0095	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	4 EA		
0096	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	5 EA		
0097	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	85 EA		
0098	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	5 EA		
0099	4234000000-N	907	DISPOSAL OF SIGN, A OR B (OVERHEAD)	2 EA		
0100	4251000000-N	907	DISPOSAL OF LIGHTING SYSTEM	1 EA		
0101	4263000000-N	907	DISPOSAL OF WALKWAY	1 EA		
0102	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	699 SF		
0103	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	424 SF		
0104	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	309 SF		
0105	4415000000-N	1115	FLASHING ARROW BOARD	3 EA		
0106	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	4 EA		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	4430000000-N	1130	DRUMS	528	EA	
0108	4445000000-E	1145	BARRICADES (TYPE III)	714	LF	
0109	4455000000-N	1150	FLAGGER	185	DAY	
0110	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	7	EA	
0111	4470000000-N	1160	RESET TEMPORARY CRASH CUSHION	4	EA	
0112	4480000000-N	1165	TMA	2	EA	
0113	4485000000-E	1170	PORTABLE CONCRETE BARRIER	3,952	LF	
0114	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	334	LF	
0115	4500000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER	1,641	LF	
0116	4505000000-E	1170	RESET PORTABLE CONCRETE BAR- RIER (ANCHORED)	334	LF	
0117	4510000000-N	SP	LAW ENFORCEMENT	440	HR	
0118	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	686	EA	
0119	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	11,313	LF	
0120	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	15,192	LF	
0121	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	880	LF	
0122	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,168	LF	
0123	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	3,063	LF	
0124	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	485	LF	

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0125	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	24 EA		
0126	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	67 EA		
0127	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	797 LF		
0128	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	945 LF		
0129	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (II)	86 LF		
0130	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (II)	2 EA		
0131	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (IV-REMOVEABLE)	2 EA		
0132	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	74,422 LF		
0133	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	5,138 LF		
0134	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	1,287 LF		
0135	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	36 EA		
0136	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	126 EA		
0137	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	31,700 LF		
0138	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	1,429 LF		
0139	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	273 LF		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0140	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	47 EA		
0141	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	16 EA		
0142	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	191 EA		
0143	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	6 EA		
0144	5005000000-E	1401	80' HIGH MOUNT STANDARD	3 EA		
0145	5010000000-E	1401	100' HIGH MOUNT STANDARD	1 EA		
0146	5020000000-N	1401	PORTABLE DRIVE UNIT	1 EA		
0147	5025000000-E	SP	HIGH MOUNT FOUNDATIONS	21 CY		
0148	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (400W HPS)	24 EA		
0149	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (750W HPS)	6 EA		
0150	5050000000-N	1404	LIGHT STANDARD, TYPE MTLT ***** (MTLT 45' (SA) 15')	6 EA		
0151	5050000000-N	1404	LIGHT STANDARD, TYPE MTLT ***** (MTLT 45' (TA) 15')	6 EA		
0152	5070000000-N	1405	STANDARD FOUNDATION ***** (R1)	10 EA		
0153	5070000000-N	1405	STANDARD FOUNDATION ***** (R2)	2 EA		
0154	5080000000-N	1406	LIGHT STANDARD LUMINAIRES, TYPE ***** (RDW, 250W)	18 EA		
0155	5120000000-N	1407	ELECTRIC SERVICE POLE **** ***** (30', CLASS 4)	1 EA		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0156	5125000000-E	1407	ELECTRIC SERVICE LATERAL ***** (3, #1/0 USE)	100 LF		
0157	5145000000-N	1408	LIGHT CONTROL EQUIPMENT, TYPE RW ***** (SSPM)	1 EA		
0158	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	120 LF		
0159	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (3")	210 LF		
0160	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	190 LF		
0161	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (4")	100 LF		
0162	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (6")	170 LF		
0163	5170000000-E	1410	** #8 W/G FEEDER CIRCUIT (2)	220 LF		
0164	5175000000-E	1410	** #6 W/G FEEDER CIRCUIT (2)	600 LF		
0165	5180000000-E	1410	** #4 W/G FEEDER CIRCUIT (2)	380 LF		
0166	5185000000-E	1410	** #2 W/G FEEDER CIRCUIT (2)	380 LF		
0167	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1 1/2)	2,710 LF		
0168	5210000000-E	1410	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1 1/2)	1,520 LF		
0169	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1 1/2)	2,310 LF		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0170	5220000000-E	1410	** #2 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1 1/2)	2,750 LF		
0171	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	15 EA		
0172	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC30)	2 EA		
0173	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC36)	4 EA		
0174	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0175	5325000000-E	1510	*** WATER LINE (18")	134 LF		
0176	5325600000-E	1510	6" WATER LINE	1,575 LF		
0177	5325800000-E	1510	8" WATER LINE	50 LF		
0178	5326200000-E	1510	12" WATER LINE	582 LF		
0179	5540000000-E	1515	6" VALVE	6 EA		
0180	5546000000-E	1515	8" VALVE	1 EA		
0181	5558000000-E	1515	12" VALVE	2 EA		
0182	5571600000-E	1515	6" TAPPING VALVE	1 EA		
0183	5648000000-N	1515	RELOCATE WATER METER	4 EA		
0184	5649000000-N	1515	RECONNECT WATER METER	5 EA		
0185	5672000000-N	1515	RELOCATE FIRE HYDRANT	3 EA		
0186	5691300000-E	1520	8" SANITARY GRAVITY SEWER	70 LF		
0187	5798000000-E	1530	ABANDON *** UTILITY PIPE (18")	128 LF		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0188	5804000000-E	1530	ABANDON 12" UTILITY PIPE	300 LF		
0189	5882000000-N	SP	GENERIC UTILITY ITEM BREAKDOWN AND REBUILD MANHOLE	2 EA		
0190	6000000000-E	1605	TEMPORARY SILT FENCE	2,000 LF		
0191	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	3,110 TON		
0192	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,285 TON		
0193	6012000000-E	1610	SEDIMENT CONTROL STONE	2,065 TON		
0194	6015000000-E	1615	TEMPORARY MULCHING	166 ACR		
0195	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	4,550 LB		
0196	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	18.25 TON		
0197	6024000000-E	1622	TEMPORARY SLOPE DRAINS	600 LF		
0198	6029000000-E	SP	SAFETY FENCE	100 LF		
0199	6030000000-E	1630	SILT EXCAVATION	2,780 CY		
0200	6036000000-E	1631	MATTING FOR EROSION CONTROL	30,000 SY		
0201	6037000000-E	SP	COIR FIBER MAT	15 SY		
0202	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	100 SY		
0203	6042000000-E	1632	1/4" HARDWARE CLOTH	2,660 LF		
0204	6071010000-E	SP	WATTLE	1,245 LF		
0205	6071020000-E	SP	POLYACRYLAMIDE (PAM)	665 LB		
0206	6071030000-E	1640	COIR FIBER BAFFLE	150 LF		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0207	6071050000-E	SP	*** SKIMMER (1-1/2")	1	EA	
0208	6084000000-E	1660	SEEDING & MULCHING	123	ACR	
0209	6087000000-E	1660	MOWING	80	ACR	
0210	6090000000-E	1661	SEED FOR REPAIR SEEDING	1,700	LB	
0211	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	4.5	TON	
0212	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	3,075	LB	
0213	6102000000-E	1664	SODDING	8,000	SY	
0214	6105000000-E	1664	WATER	205	M/G	
0215	6108000000-E	1665	FERTILIZER TOPDRESSING	92.25	TON	
0216	6114500000-N	1667	SPECIALIZED HAND MOWING	50	MHR	
0217	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	75	EA	
0218	6147000000-E	SP	GENERIC EROSION CONTROL ITEM TREE PROTECTION FENCE	2,800	LF	
0219	7060000000-E	1705	SIGNAL CABLE	6,485	LF	
0220	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	49	EA	
0221	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	8	EA	
0222	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	4	EA	
0223	7252000000-E	1710	MESSENGER CABLE (1/4")	80	LF	
0224	7264000000-E	1710	MESSENGER CABLE (3/8")	1,235	LF	
0225	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	150	LF	

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0226	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	1,300 LF		
0227	7300100000-E	1715	UNPAVED TRENCHING FOR TEMP- ORARY LEAD-IN	365 LF		
0228	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	175 LF		
0229	7301000000-E	1715	DIRECTIONAL DRILL (*****) (2, 2")	610 LF		
0230	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	29 EA		
0231	7360000000-N	1720	WOOD POLE	13 EA		
0232	7372000000-N	1721	GUY ASSEMBLY	20 EA		
0233	7408000000-E	1722	1" RISER WITH WEATHERHEAD	2 EA		
0234	7420000000-E	1722	2" RISER WITH WEATHERHEAD	12 EA		
0235	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	3,860 LF		
0236	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	7,710 LF		
0237	7574550000-N	SP	FURNISH WIRELESS LIGHTNING ARRESTOR	4 EA		
0238	7575142000-N	1736	900MHZ RADIO	4 EA		
0239	7588000000-N	SP	METAL POLE WITH SINGLE MAST ARM	6 EA		
0240	7590000000-N	SP	METAL POLE WITH DUAL MAST ARM	2 EA		
0241	7613000000-N	SP	SOIL TEST	8 EA		
0242	7614100000-E	SP	DRILLED PIER FOUNDATION	64 CY		
0243	7631000000-N	SP	MAST ARM WITH METAL POLE DE- SIGN	8 EA		
0244	7636000000-N	1745	SIGN FOR SIGNALS	4 EA		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0245	7684000000-N	1750	SIGNAL CABINET FOUNDATION	3 EA		
0246	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	3 EA		
0247	7768000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, POLE MOUNTED)	1 EA		
0248	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	23 EA		
0249	7901000000-N	1753	CABINET BASE EXTENDER	3 EA		
0250	7948000000-N	1757	TRAFFIC SIGNAL REMOVAL	2 EA		
0251	7980000000-N	SP	GENERIC SIGNAL ITEM POWDER COAT FOR DOUBLE MAST ARM WITH METAL POLE	1 EA		
0252	7980000000-N	SP	GENERIC SIGNAL ITEM POWDER COAT FOR SINGLE MAST ARM WITH METAL POLE	4 EA		

WALL ITEMS

0253	8802014000-E	SP	SOLDIER PILE RETAINING WALLS	6,250 SF		
0254	8839000000-E	SP	GENERIC RETAINING WALL ITEM CONCRETE BARRIER RAIL WITH MOM ENT SLAB	268 LF		
0255	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO. 3	700 SF		
0256	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO. 4	200 SF		

STRUCTURE ITEMS

0257	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21+37.80-Y6-)	Lump Sum	L.S.	
------	--------------	-----	---	----------	------	--

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0258	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 21+37.80-Y6-)	Lump Sum	L.S.	
0259	8112730000-N	450	PDA TESTING	1 EA		
0260	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (21+37.80-Y6-)	Lump Sum	L.S.	
0261	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	15,298 SF		
0262	8161000000-E	420	GROOVING BRIDGE FLOORS	14,074 SF		
0263	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	229 CY		
0264	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21+37.80-Y6-)	Lump Sum	L.S.	
0265	8217000000-E	425	REINFORCING STEEL (BRIDGE)	32,993 LB		
0266	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,902 LB		
0267	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	412,000 LS		
0268	8364000000-E	450	HP12X53 STEEL PILES	2,650 LF		
0269	8393000000-N	450	PILE REDRIVES	56 EA		
0270	8531000000-E	462	4" SLOPE PROTECTION	930 SY		
0271	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0272	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0273	8867000000-E	SP	GENERIC STRUCTURE ITEM CLASSIC CONCRETE BRIDGE RAIL	335 LF		

Contract No. **C202886**

County (ies): **Moore**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General