

PROJECT SPECIAL PROVISIONS
Utility Construction



Revise the 2012 *Standard Specifications* as follows:

Utility Owners' Contact Information:

Page 15-1, Subarticle 1500-2 Cooperation with the Utility Owner, paragraph 2, add the following sentences:

The sewer line is owned by the City of Elizabeth City. The contact for this and sewer lines is Paul Freddette (252-339-6526).

The Contractor shall provide access for the owner's representatives to all phases of construction and keep all manholes and valves accessible during construction. A preconstruction meeting shall be held with The City of Elizabeth City, the Utility Contractor, and the NCDOT prior to beginning any work. The tie-ins for relocated sewer lines may need to be accomplished during nights or weekends with scheduling for this work to be coordinated with utility owners. The Contractor shall notify utility owners two weeks before commencement of any work and three weeks before service interruption.

The Contractor shall provide a set of as-built plans to the City of Elizabeth City after all the work shown on the Utility Construction Plans is completed.

Page 15-9, Subarticle 1515-2 Materials, add the following sentences:

The proposed utility construction shall meet the applicable requirements of the NCDOT's "Standard Specifications for Roads and Structures" (January 2012), and the City of Elizabeth City's Standard Detail and Specifications Manual.

Measurement and payment for the work shall be in accordance with NCDOT's "Standard Specifications for Roads and Structures", dated January, 2012.

PROJECT SPECIAL PROVISIONS
Utilities by Others

General:

The following utility companies have facilities that will be in conflict with the construction of this project.

- A. Telephone (CenturyLink)
- B. Elizabeth City (Power)

The conflicting facilities of these concerns will be adjusted prior to the date of availability unless noted otherwise and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owners. All utilities are shown on the plans from the best available information.

The Contractor's attention is directed to Article 105.8 of the Standard Specifications.

Utilities Requiring Adjustment:

A. CenturyLink (Telephone)

1. The existing aerial telephone line will be removed right of Line -L- from STA. 15+08 to STA. 19+11. A temporary telephone line will be laid on the ground left of Line -L- during roadway construction. After roadway construction is completed, CenturyLink will install proposed aerial telephone on proposed power poles.

See "Utilities By Others Plans" for details
Contact person: Hester Jones (252-335-2678)

B. Elizabeth City (Power)

1. The existing aerial power pole line with telephone attached will be removed right of Line -L- from STA. 15+08 to STA. 19+11 and back fed during roadway construction. After the roadway construction is completed Elizabeth City will install a new power pole line with telephone attached further right of the Line -L- from STA. 15+08 to STA. 19+11. Elizabeth City power should be notified at least one week prior to construction.

See "Utilities By Others Plans" for details.
Contact person: Karl Clow (252-337-6870)