

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (24+25-L-)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	32,000 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	435 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	2,500 CY		
0010	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	4,100 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	1,995 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	140 TON		
0013	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	420 SY		
0014	0335300000-E	305	18" DRAINAGE PIPE	20 LF		
0015	0343000000-E	310	15" SIDE DRAIN PIPE	216 LF		
0016	0344000000-E	310	18" SIDE DRAIN PIPE	36 LF		
0017	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	72 LF		
0018	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	76 LF		
0019	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	104 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	264 LF		
0021	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	8 EA		
0022	0995000000-E	340	PIPE REMOVAL	90 LF		
0023	1099500000-E	505	SHALLOW UNDERCUT	850 CY		
0024	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	1,690 TON		
0025	1220000000-E	545	INCIDENTAL STONE BASE	400 TON		
0026	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,250 TON		
0027	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	1,300 TON		
0028	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,035 TON		
0029	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	290 TON		
0030	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	21 TON		
0031	2000000000-N	806	RIGHT OF WAY MARKERS	44 EA		
0032	2022000000-E	815	SUBDRAIN EXCAVATION	56 CY		
0033	2033000000-E	815	SUBDRAIN FINE AGGREGATE	42 CY		
0034	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250 LF		
0035	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0036	2077000000-E	815	6" OUTLET PIPE	6 LF		
0037	2253000000-E	840	PIPE COLLARS	3.25 CY		
0038	2264000000-E	840	PIPE PLUGS	0.5 CY		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0040	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.5 LF		
0041	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	3 EA		
0042	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0043	2495000000-E	SP	GENERIC DRAINAGE ITEM ENDWALL EXTENSION	20 CY		
0044	2556000000-E	846	SHOULDER BERM GUTTER	30 LF		
0045	3030000000-E	862	STEEL BM GUARDRAIL	1,737.5 LF		
0046	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	62.5 LF		
0047	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0048	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0049	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0050	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0051	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (W-BEAM)	1 EA		
0052	3628000000-E	876	RIP RAP, CLASS I	180 TON		
0053	3649000000-E	876	RIP RAP, CLASS B	95 TON		
0054	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,920 SY		
0055	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	217 LF		
0056	4096000000-N	904	SIGN ERECTION, TYPE D	4 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4102000000-N	904	SIGN ERECTION, TYPE E	6 EA		
0058	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	13 EA		
0059	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	587 SF		
0060	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0061	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	228 SF		
0062	4430000000-N	1130	DRUMS	130 EA		
0063	4435000000-N	1135	CONES	50 EA		
0064	4445000000-E	1145	BARRICADES (TYPE III)	160 LF		
0065	4450000000-N	1150	FLAGGER	4,320 HR		
0066	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0067	4470000000-N	1160	RESET TEMPORARY CRASH CUSHION	2 EA		
0068	4480000000-N	1165	TMA	1 EA		
0069	4485000000-E	1170	PORTABLE CONCRETE BARRIER	285 LF		
0070	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	205 LF		
0071	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	40 EA		
0072	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	144 LF		
0073	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	121 LF		
0074	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	1 EA		
0075	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	23,524 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (HIGHLY REFLECTIVE ELEMENTS)	14,675	LF	
0077	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	90	EA	
0078	6000000000-E	1605	TEMPORARY SILT FENCE	3,300	LF	
0079	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	555	TON	
0080	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,455	TON	
0081	6012000000-E	1610	SEDIMENT CONTROL STONE	500	TON	
0082	6015000000-E	1615	TEMPORARY MULCHING	6	ACR	
0083	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250	LB	
0084	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	3.75	TON	
0085	6024000000-E	1622	TEMPORARY SLOPE DRAINS	925	LF	
0086	6029000000-E	SP	SAFETY FENCE	700	LF	
0087	6030000000-E	1630	SILT EXCAVATION	2,100	CY	
0088	6036000000-E	1631	MATTING FOR EROSION CONTROL	11,000	SY	
0089	6037000000-E	SP	COIR FIBER MAT	250	SY	
0090	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,679	SY	
0091	6042000000-E	1632	1/4" HARDWARE CLOTH	300	LF	
0092	6071010000-E	SP	WATTLE	120	LF	
0093	6071020000-E	SP	POLYACRYLAMIDE (PAM)	280	LB	
0094	6071030000-E	1640	COIR FIBER BAFFLE	720	LF	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0095	6071050000-E	SP	*** SKIMMER (1-1/2")	8	EA	
0096	6084000000-E	1660	SEEDING & MULCHING	6	ACR	
0097	6087000000-E	1660	MOWING	3	ACR	
0098	6090000000-E	1661	SEED FOR REPAIR SEEDING	100	LB	
0099	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5	TON	
0100	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200	LB	
0101	6108000000-E	1665	FERTILIZER TOPDRESSING	5.25	TON	
0102	6114500000-N	1667	SPECIALIZED HAND MOWING	40	MHR	
0103	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	50	EA	
0104	6123000000-E	1670	REFORESTATION	0.25	ACR	

**STRUCTURE ITEMS**

0105	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (24+23.00-L-)	Lump Sum	L.S.	
0106	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	445	SF	
0107	8154000000-E	420	REINFORCED CONCRETE DECK SLAB (SAND LIGHTWEIGHT CONC)	3,204	SF	
0108	8161000000-E	420	GROOVING BRIDGE FLOORS	3,573	SF	
0109	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	38.2	CY	
0110	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (24+23.00-L-)	Lump Sum	L.S.	
0111	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,424	LB	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0112	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	333.5	LF	
0113	8364000000-E	450	HP12X53 STEEL PILES	355	LF	
0114	8475000000-E	460	TWO BAR METAL RAIL	205.67	LF	
0115	8517000000-E	460	1'-**"X ***** CONCRETE PARA-PET (1'-2" X 2'-6")	220.67	LF	
0116	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	740	TON	
0117	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	820	SY	
0118	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

0937/Aug01/Q142217.04/D464944010000/E118

Total Amount Of Bid For Entire Project :

**Contract No.**     **C202821**

**County (ies):**    **Rowan**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)