

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0003	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0004	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0005	0106000000-E	230	BORROW EXCAVATION	11,400 CY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	60 TON		
0007	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	170 SY		
0008	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	324 LF		
0009	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	40 LF		
0010	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	184 LF		
0011	0995000000-E	340	PIPE REMOVAL	341 LF		
0012	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0013	1330000000-E	607	INCIDENTAL MILLING	1,000 SY		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	6,500 TON		
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	3,000 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,300 TON		
0017	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	560 TON		
0018	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	51 EA		
0020	2253000000-E	840	PIPE COLLARS	2 CY		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0022	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		
0023	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	450 LF		
0024	2738000000-E	SP	GENERIC PAVING ITEM 7"-12" MONOLITHIC CONC ISLAND WITH REINFORCEMENT	510 SY		
0025	3030000000-E	862	STEEL BM GUARDRAIL	24 LF		
0026	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	2 EA		
0027	3649000000-E	876	RIP RAP, CLASS B	19 TON		
0028	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	310 SY		
0029	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	187 SF		
0030	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144 SF		
0031	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	60 SF		
0032	4430000000-N	1130	DRUMS	175 EA		
0033	4435000000-N	1135	CONES	75 EA		
0034	4455000000-N	1150	FLAGGER	180 DAY		
0035	4516000000-N	1180	SKINNY DRUM	30 EA		
0036	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	109 EA		
0037	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,100 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	9,120 LF		
0039	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	53 LF		
0040	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	89,107 LF		
0041	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	516 LF		
0042	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	588 LF		
0043	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	16 EA		
0044	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	400 LF		
0045	6000000000-E	1605	TEMPORARY SILT FENCE	3,000 LF		
0046	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	325 TON		
0047	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	600 TON		
0048	6012000000-E	1610	SEDIMENT CONTROL STONE	200 TON		
0049	6015000000-E	1615	TEMPORARY MULCHING	6 ACR		
0050	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	300 LB		
0051	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2 TON		
0052	6024000000-E	1622	TEMPORARY SLOPE DRAINS	150 LF		
0053	6030000000-E	1630	SILT EXCAVATION	1,590 CY		
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,000 SY		
0055	6037000000-E	SP	COIR FIBER MAT	30 SY		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6042000000-E	1632	1/4" HARDWARE CLOTH	100		LF
0057	6071010000-E	SP	WATTLE	840		LF
0058	6071020000-E	SP	POLYACRYLAMIDE (PAM)	100		LB
0059	6071030000-E	1640	COIR FIBER BAFFLE	65		LF
0060	6071050000-E	SP	*** SKIMMER (1-1/2")	3		EA
0061	6084000000-E	1660	SEEDING & MULCHING	7		ACR
0062	6090000000-E	1661	SEED FOR REPAIR SEEDING	100		LB
0063	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25		TON
0064	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200		LB
0065	6108000000-E	1665	FERTILIZER TOPDRESSING	5		TON
0066	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12		EA

1201/Aug08/Q145297.25/D248043210000/E66

Total Amount Of Bid For Entire Project :

Contract No. **C203124**

County (ies): **Rowan**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)