

September 14, 2010

Mr. Ethan Caldwell, LG  
North Carolina Department of Transportation  
Geotechnical Engineering Unit  
1589 Mail Service Center  
Raleigh, North Carolina 27699-1589

Reference: Preliminary Site Assessment  
Helen Faircloth Properties Property (Parcel #34)  
121 S. Bragg Blvd.  
Spring Lake, Cumberland County, North Carolina  
NCDOT Tip No. U-4444B  
WBS Element 36492.1.2  
AECOM Project No. 60158550

Dear Mr. Caldwell:

AECOM Technical Services of North Carolina, Inc., (AECOM) has completed the Preliminary Site Assessment conducted at the above-referenced property. The work was performed in accordance with the Technical and Cost proposal dated July 6, 2010, and the North Carolina Department of Transportation's (NCDOT's) Notice to Proceed dated July 7, 2010. Activities associated with the assessment consisted of conducting a geophysical investigation, collecting soil samples for laboratory analysis, and reviewing applicable North Carolina Department of Environment and Natural Resources (NCDENR) records. The purpose of this report is to document the field activities, present the laboratory analyses, and provide recommendations regarding the property.

### **Location and Description**

The Helen Faircloth Properties Property (Parcel #34) is located at 121 S. Bragg Boulevard in Spring Lake, Cumberland County, North Carolina. The property is situated on the east side of Bragg Boulevard and approximately 200 feet south of the intersection of Bragg Boulevard and Spring Avenue (Figure 1). Based on information supplied by the NCDOT and the site visit, AECOM understands that the site houses a barber shop and dry cleaning establishment (Jan's Cleaners and Alterations). No evidence of underground storage tanks (USTs) was observed during the site visit. The structures on the site include a block building with an asphalt parking lot (Figure 2). The NCDOT has advised that the proposed right-of-way/easement will affect the parking lot in front of the building (Figure 2). Because of the presence of a dry cleaning store, the NCDOT requested a Preliminary Site Assessment. The scope of work as defined in the Request for Technical and Cost Proposal was to evaluate the proposed right-of-way with respect to the

presence of known and unknown USTs and assess where contamination may exist on the right-of-way. If present, an estimate of the quantity of impacted soil was to be provided.

AECOM reviewed the on-line NCDENR Incident Management database and no Incident Number has been assigned to the property. The site is not included in the Dry-cleaning Solvent Cleanup ACT (DSCA) contamination database. AECOM also examined the UST registration database to obtain UST ownership information. No USTs are registered to the site address.

### **Geophysical Survey**

Prior to AECOM's mobilization to the site, Pyramid Environmental conducted a geophysical survey as part of this project to evaluate if USTs were present on the right-of-way/easement. The geophysical survey consisted of an electromagnetic survey using a Geonics EM61 time-domain electromagnetic induction meter to locate buried metallic objects, specifically USTs. A survey grid was laid out at the property with the X-axis oriented approximately perpendicular to Bragg Boulevard and the Y-axis oriented approximately parallel to Bragg Boulevard. The grid was located to cover the accessible portions of the proposed right-of-way. The survey lines were spaced 5 feet apart. Magnetic data was collected continuously along each survey line with a data logger. After collection, the data was reviewed in the field with graphical computer software. Following the electromagnetic survey, a ground penetrating radar (GPR) survey was conducted where needed to further evaluate any significant metallic anomalies.

Access was available to all areas of the right-of-way and several anomalies were detected with the geophysical survey. All of these anomalies were attributed to buried utility lines or conduits. A detailed report of findings and interpretations is presented in Attachment A.

### **Site Assessment Activities**

On August 10, 2010, AECOM mobilized to the site to conduct a Geoprobe<sup>®</sup> direct push investigation to evaluate soil conditions within the proposed right-of-way/easement. Continuous sampling using direct push technology (Regional Probing of Wake Forest, North Carolina) resulted in generally good recovery of soil samples from the direct-push holes. Soil samples were collected and contained in acetate sleeves inside the direct push sampler. Each of these sleeves was divided into 2-foot long sections for soil sample screening. Each 2-foot interval was placed in a resealable plastic bag and the bag was set aside for a sufficient amount of time to allow volatilization of organic compounds from the soil to the bag headspace. The probe of a flame ionization detector/photo ionization detector (FID/PID) was inserted into the bag and the reading was recorded. After terminating the sample hole, the soil sample from the depth interval with the highest FID/PID reading was submitted for analysis to SGS North America in Wilmington, North Carolina, using standard chain-of-custody procedures. The laboratory analyzed the soil samples for total petroleum hydrocarbons (TPH) in the diesel range organics (DRO) and gasoline range organics (GRO), and volatile organic compounds (VOCs) associated with dry cleaning operations using EPA Method 8260.

Two direct-push holes (HF-1 and HF-2) were advanced within the right-of-way to a depth of 10 feet as shown in Figure 2 and Attachment B. The borings were located to evaluate the conditions within the proposed right-of-way/easements (Attachment C). The lithology encountered by the direct-push samples generally was consistent throughout the site. The ground surface was covered with about 2 to 3 inches of asphalt. Below the surface to a depth of 8 feet was a medium brown, loose, coarse-grained sand. Underlying this material was a medium brown sand/clay. No bedrock was encountered in any of the borings. The “Geologic Map of North Carolina” dated 1985 indicates that the site is underlain by the Middendorf and Cape Fear Formations, each of which consists predominantly of sand and mudstone. The soil observed at the site is consistent with this parent rock. The borings were terminated at a depth of 10 feet. No groundwater was observed in any of the borings. Based on field screening, soil samples were submitted for laboratory analyses, which are summarized in Table 1. Following completion, each boring was backfilled in accordance with 15A NCAC 2C.

### **Analytical Results**

Based on the laboratory reports, summarized in Table 1 and presented in Attachment D, no petroleum hydrocarbon compounds identified as DRO and/or GRO were detected in either of the two soil samples collected from the site on August 10, 2010. The laboratory reports also indicate that no VOCs were detected in either soil sample. Consequently, no concentrations are present above applicable action levels.

### **Conclusions and Recommendations**

A Preliminary Site Assessment was conducted to evaluate the Helen Faircloth Properties Property (Parcel #34) located at 121 S. Bragg Boulevard in Spring Lake, Cumberland County, North Carolina. A geophysical investigation was conducted to evaluate the site for unknown USTs. The investigation concluded that no metallic USTs were present at the site. Two soil borings were advanced to evaluate the soil conditions throughout the proposed right-of-way. The laboratory reports of the soil samples from these borings suggest that no DRO, GRO, and/or VOC concentrations were present above the action level in either of the two soil samples analyzed.

Mr. Ethan Caldwell  
September 14, 2010  
Page 4

AECOM appreciates the opportunity to work with the NCDOT on this project. Because no compounds were detected above the method detection limits in the soil samples, no notification is required to the NCDENR. If you have any questions, please contact me at (919) 854-6238.

Sincerely,



Michael W. Branson, P.G.  
Project Manager

Attachments

c: Project File



**TABLE 1**

**SOIL FIELD SCREENING AND ANALYTICAL RESULTS  
HELEN FAIRCLOTH PROPERTIES PROPERTY (PARCEL #34)  
SPRING LAKE, CUMBERLAND COUNTY, NORTH CAROLINA  
NCDOT PROJECT NO. U-4444B  
WBS ELEMENT 36492.1.2  
AECOM PROJECT NO. 60158550**


LOCATION	DEPTH (ft)	FID READING (ppm)	SAMPLE ID	ANALYTICAL RESULTS (mg/kg)	ASSUMED ACTION LEVEL (mg/kg)
HF-1	0 - 2	4.57			
	2 - 4	5.54	HF-1	DRO (BQL) GRO (BQL) 8260 (BQL)	10 10 NA
	4 - 6	4.69			
	6 - 8	3.61			
	8 - 10	4.34			
HF-2	0 - 2	2.32			
	2 - 4	4.49			
	4 - 6	2.75			
	6 - 8	4.75	HF-2	DRO (BQL) GRO (BQL) 8260 (BQL)	10 10 NA
	8 - 10	4.51			

Soil samples were collected on August 10, 2010.


- DRO - Diesel range organics.
- GRO - Gasoline range organics.
- 8260 - Volatile organic compounds using EPA Method 8260.
- BQL - Below quantitation limit.
- NA - Not applicable.
- ppm - parts per million.
- mg/kg - milligrams per kilogram.



## **FIGURES**



SCALE 1:24,000




SOURCE: U.S. GEOLOGICAL SURVEY 7.5 MIN QUADRANGLE: MANCHESTER, NC (REV 1987)




**FIGURE 1**  
VICINITY MAP  
HELEN FAIRCLOTH PROPERTIES, INC., PROPERTY (PARCEL #34)  
SPRING LAKE, CUMBERLAND COUNTY NORTH CAROLINA  
AUGUST 2010

60158550



**LEGEND**

**HF-1**  SOIL SAMPLE LOCATION AND IDENTIFICATION



**FIGURE 2  
SITE MAP**

HELEN FAIRCLOTH PROPERTIES, INC., PROPERTY (PARCEL #34)  
SPRING LAKE, CUMBERLAND COUNTY, NORTH CAROLINA

AUGUST 2010

60158550



**ATTACHMENT A**

## **GEOPHYSICAL INVESTIGATION REPORT**

### *EM61 & GPR SURVEYS*


**HELEN FAIRCLOTH PROPERTIES INC. SITE (PARCEL 34)**

**South Bragg Boulevard  
Spring Lake, North Carolina**

**August 28, 2010**


**Report prepared for: Michael W. Branson, PG  
AECOM Environment  
701 Corporate Center Drive, Suite 475  
Raleigh, North Carolina 27607**

**Prepared by:**



**Mark J. Denil, P.G.**

**Reviewed by:**



**Douglas Canavello, P.G.**

**PYRAMID ENVIRONMENTAL & ENGINEERING, P.C.  
P.O. Box 16265  
GREENSBORO, NC 27416-0265  
(336) 335-3174**

**AECOM Environment**  
**GEOPHYSICAL INVESTIGATION REPORT**  
**HELEN FAIRCLOTH PROPERTIES INC. (PARCEL 34)**  
**Spring Lake, North Carolina**

<u>TABLE OF CONTENTS</u>	<u>PAGE</u>
1.0 INTRODUCTION .....	1
2.0 FIELD METHODOLOGY .....	1
3.0 DISCUSSION OF RESULTS .....	2
4.0 SUMMARY & CONCLUSIONS .....	3
5.0 LIMITATIONS .....	3

FIGURES

- |          |  |
|----------|--|
| Figure 1 | Geophysical Equipment & Site Photographs |
| Figure 2 | EM61 Metal Detection Results             |

## **1.0 INTRODUCTION**

Pyramid Environmental conducted a geophysical investigation for AECOM Environmental across the proposed Right-of-Way (ROW) area at the Helen Faircloth Properties Inc. (Parcel 34) located along the easterly side of South Bragg Boulevard approximately 0.2 miles south of the intersection of South Bragg Boulevard and Spring Avenue in Spring Lake, North Carolina. Conducted on July 22, 2010, the geophysical investigation was performed as part of the North Carolina Department of Transportation (NCDOT) preliminary site assessment project to determine if unknown, metallic underground storage tanks (USTs) are present beneath the proposed ROW area of the site.

The Helen Faircloth Properties Inc. site consists of a small occupied strip mall that includes a barber shop and dry cleaning facility and the proposed ROW area encompasses the asphalt pavement between the building and South Bragg Boulevard. The proposed ROW area (geophysical survey area) has a maximum length and width of 65 feet and 48 feet, respectively.

AECOM Environment representative Mr. Michael Branson, PG identified the geophysical survey area to Pyramid Environmental personnel and provided site maps showing the boundaries of the proposed survey area prior to conducting the investigation. Photographs of the geophysical equipment used in this investigation and a portion of Parcel 34 are shown in **Figure 1**.

## **2.0 FIELD METHODOLOGY**

Prior to conducting the geophysical investigation, a 10-foot by 10-foot survey grid was established across the geophysical survey area (property) using measuring tapes and water-based marking paint. These grid marks were used as X-Y coordinates for location control when collecting the geophysical data and establishing base maps for the geophysical results.

The geophysical investigation consisted of electromagnetic (EM) induction-metal detection surveys performed on July 22, 2010 using a Geonics EM61-MK1 metal detection instrument. According to the instrument specifications, the EM61 can detect a metal drum down to a maximum depth of

approximately 8 feet. Smaller objects (1-foot or less in size) can be detected to a maximum depth of 4 to 5 feet. All of the EM61 data were digitally collected at approximately 0.8 foot intervals along northerly-southerly, or easterly-westerly, parallel survey lines spaced five feet apart. All of the data were downloaded to a computer and reviewed in the field and office using the Geonics DAT61W and Surfer for Windows Version 7.0 software programs.

Due to an absence of metal detection anomalies that may be in response to potential USTs, ground penetrating radar (GPR) surveys were not conducted at this site. Contour plots of the EM61 bottom coil and differential results are presented in **Figure 2**. The bottom coil results represent the most sensitive component of the EM61 instrument and detect metal objects regardless of size. The bottom coil response can be used to delineate metal conduits or utility lines, small, isolated metal objects, and areas containing insignificant metal debris. The differential results are obtained from the difference between the top and bottom coils of the EM61 instrument. The differential results focus on the larger metal objects such as drum and UST-size objects and ignore the smaller insignificant metal objects.

Preliminary contour plots of the EM61 bottom coil and EM61 differential results obtained from the survey area were emailed to Mr. Branson during the week of August 9, 2010.

### **3.0 DISCUSSION OF RESULTS**

The linear EM61 bottom coil anomaly intersecting grid coordinates X=20 Y=30 is probably in response to a buried utility line(s). The bottom coil anomalies centered near grid coordinates X=62 Y=35, X=62 Y=47 and X=62 Y=80 are probably in response to the building and concrete walkway.

The EM61 differential anomaly centered near grid coordinates X=25 Y=73 is in response to the storm sewer grate. The differential anomaly centered near grid coordinates X=44 Y=18 is probably in response to the business sign poles, the business sign and a 6 inch diameter segment of conduit cut off at the surface. The geophysical investigation suggests the proposed ROW area at Parcel 34 does not contain unknown, metallic USTs.



#### **4.0 SUMMARY & CONCLUSIONS**

Our evaluation of the EM61 data collected across the Helen Faircloth Properties Inc. (Parcel 34) located along the east side of South Bragg Boulevard in Spring Lake, North Carolina, provides the following summary and conclusions:

- The EM61 investigation provided reliable results for the detection of metallic USTs within the surveyed portion of the site.
- The linear EM61 bottom coil anomaly intersecting grid coordinates X=20 Y=30 is probably in response to a buried utility line(s).
- The EM61 differential anomaly centered near grid coordinates X=25 Y=73 is in response to the storm sewer grate. The differential anomaly centered near grid coordinates X=44 Y=18 is probably in response to the business sign poles, the business sign and a 6 inch diameter segment of conduit cut off at the surface.
- The geophysical investigation suggests the proposed ROW area at Parcel 34 does not contain unknown, metallic USTs.

#### **5.0 LIMITATIONS**



EM61 investigation has been performed and this report prepared for AECOM Environmental in accordance with generally accepted guidelines for EM61 surveys. It is generally recognized that the results of the EM61 survey are non-unique and may not represent actual subsurface conditions. The EM61 results obtained for this project have not conclusively determined that the surveyed portion of the site does not contain unknown, metallic USTs but that none were detected.



## FIGURES

(on the following pages)

Figures shown on this page are for esthetic purposes only and are not related to the geophysical results discussed in this report.





The photograph shows the Geonics EM61 metal detector that was used to conduct the metal detection survey across the proposed ROW area at the Helen Faircloth Properties Inc. site on July 22, 2010.



The photograph shows the proposed ROW area at the Helen Faircloth Properties Inc. site located along the east side of South Bragg Boulevard in Spring Lake, North Carolina. The photograph is viewed in a southerly direction.





CLIENT	AECOM ENVIRONMENT		DATE	08/27/10	BY	MJD
SITE	HELEN FAIRCLOTH PROPERTIES INC. (PARCEL 34)		LAY		OPND	
CITY	SPRING LAKE	STATE	NORTH CAROLINA	ENG		
TITLE	GEOPHYSICAL RESULTS		PROJ	2010-176	PROJ#	

GEOPHYSICAL EQUIPMENT  
& SITE PHOTOGRAPHS


FIGURE 1





**LEGEND**

- SURVEY AREA: EM61 DATA ACQUIRED ALONG X-AXIS OR Y-AXIS TRENDING SPACED 5 FEET APART
- BUILDING
- UTILITY POLE
- BUSINESS SIGN POLE
- 6 INCH DIAMETER CUT-OFF PIPE
- WATER LINE VALVE COVER
- CINDER BLOCK RETAINING WALL
- ROAD SIGN



The contour plots show the bottom coil (most sensitive) response and the differential response of the EM61 instrument in millivolts (mV). The bottom coil response shows buried metallic objects regardless of size. The differential response focuses on larger, buried metallic objects such as drums and USTs and ignores smaller miscellaneous, buried, metal debris. The EM61 survey was collected on July 22, 2010 using a Geonics EM61 instrument. Due to an absence of EM61 differential anomalies not in response to known surface objects, ground penetrating radar (GPR) surveys were not conducted at this site.

The geophysical investigation suggests the proposed ROW area of the site does not contain metallic USTs.

EM61 METAL DETECTION RESULTS

FIGURE 2

CLIENT	AECOM ENVIRONMENT	DATE	08/27/10
SITE	HELEN FAIRCLOTH PROPERTIES INC. (PARCEL 34)	LAY	
CITY	SPRING LAKE	DWG	
TITLE	GEOPHYSICAL RESULTS	L.N.O.	2010-176
		FIGURE	
		DRWN	
		CHKD	
		MJD	
		GRAPHIC SCALE IN FEET	

**PYRAMID**  
ENVIRONMENTAL & ENGINEERING, P.C.

**ATTACHMENT B**

# TEST BORING REPORT

**PROJECT** HELEN FAIRCLOTH PROPERTIES PROPERTY (PARCEL 34)

**CLIENT** NCDOT

**PROJECT NUMBER** 60158550 (WBS 36492.1.2)

**CONTRACTOR** REGIONAL PROBING

**EQUIPMENT** GEOPROBE

**BORING NUMBER** HF-1

**PAGE** 1

**ELEVATION** \_\_\_\_\_

**DATE** 8/10/2010

**DRILLER** OPPER

**PREPARED BY** BRANSON

DEPTH IN FEET	CASING BLOWS FOOT	BLOWS PER 6 INCHES	OVA (ppm)	SAMPLE DEPTH RANGE	FIELD CLASSIFICATION AND REMARKS
			4.57		2" ASPHALT/GRAVEL, MEDIUM BROWN, LOOSE, COARSE-GRAINED SAND, DRY, NO ODOR.
			5.54		
			4.69		
5.0			3.61		
			4.34		
					MEDIUM BROWN SAND/CLAY, STIFF, DRY, NO ODOR.
10.0					
					BORING TERMINATED AT 10 FEET. NO GROUNDWATER ENCOUNTERED
15.0					
20.0					



# TEST BORING REPORT

**PROJECT** HELEN FAIRCLOTH PROPERTIES PROPERTY (PARCEL 34)

**CLIENT** NCDOT

**PROJECT NUMBER** 60158550 (WBS 36492.1.2)

**CONTRACTOR** REGIONAL PROBING

**EQUIPMENT** GEOPROBE

**BORING NUMBER** HF-2

**PAGE** 1

**ELEVATION** \_\_\_\_\_

**DATE** 8/10/2010

**DRILLER** OPPER

**PREPARED BY** BRANSON

DEPTH IN FEET	CASING BLOWS FOOT	BLOWS PER 6 INCHES	OVA (ppm)	SAMPLE DEPTH RANGE	FIELD CLASSIFICATION AND REMARKS
5.0			2.32		2" ASPHALT/GRAVEL, MEDIUM BROWN, LOOSE, COARSE-GRAINED SAND, DRY, NO ODOR.
			4.49		AS ABOVE, DRY, NO ODOR.
			2.75		AS ABOVE, DRY, NO ODOR.
10.0			4.75		AS ABOVE, DRY, NO ODOR. SUBMIT TO LABORATORY FOR ANALYSIS.
			4.51		AS ABOVE, DRY, NO ODOR.
15.0					
20.0					



**ATTACHMENT C**



PHOTO 1 - BORING IN PROPOSED R/W LOOKING NORTHEAST



PHOTO 2 - BORING IN PROPOSED R/W LOOKING EAST

**ATTACHMENT D**



Mike Branson  
AECOM  
701 Corporate Center Drive  
Suite 475  
Raleigh, NC 27607

Report Number: G1037-95

Client Project: NCDOT


Dear Mike Branson,

Enclosed are the results of the analytical services performed under the referenced project for the received samples and associated QC as applicable. The samples are certified to meet the requirements of the National Environmental Laboratory Accreditation Conference Standards. Copies of this report and supporting data will be retained in our files for a period of five years in the event they are required for future reference. Any samples submitted to our laboratory will be retained for a maximum of thirty (30) days from the date of this report unless other arrangements are requested.

If there are any questions about the report or services performed during this project, please call Barbara Hager at (910) 350-1903. We will be happy to answer any questions or concerns which you may have.

Thank you for using SGS North America, Inc. for your analytical services. We look forward to working with you again on any additional analytical needs.

Sincerely,  
SGS North America, Inc.

 Aug 20 2010  
Project Manager Date  
Barbara Hager



List of Reporting Abbreviations  
And Data Qualifiers

B = Compound also detected in batch blank

BQL = Below Quantification Limit (RL or MDL)

DF = Dilution Factor

Dup = Duplicate

D = Detected, but RPD is > 40% between results in dual column method.

E = Estimated concentration, exceeds calibration range.

J = Estimated concentration, below calibration range and above MDL

LCS(D) = Laboratory Control Spike (Duplicate)

MDL = Method Detection Limit

MS(D) = Matrix Spike (Duplicate)

PQL = Practical Quantitation Limit

RL/CL = Reporting Limit / Control Limit

RPD = Relative Percent Difference

UJ = Target analytes with recoveries that are  $10\% < \%R < LCL$ ; # of MEs are allowable and compounds are not detected in the sample.

mg/kg = milligram per kilogram, ppm, parts per million

ug/kg = micrograms per kilogram, ppb, parts per billion

mg/L = milligram per liter, ppm, parts per million

ug/L = micrograms per liter, ppb, parts per billion

% Rec = Percent Recovery

% solids = Percent Solids

Special Notes:

- 1) Metals and mercury samples are digested with a hot block; see the standard operating procedure document for details.
- 2) Uncertainty for all reported data is less than or equal to 30 percent.

**Results for Volatiles  
by GCMS 8260-5035**

Client Sample ID: HF-1  
 Client Project ID: NCDOT  
 Lab Sample ID G1037-95-1A  
 Lab Project ID: G1037-95  
 Report Basis: Dry Weight

Analyzed By: DVO  
 Date Collected: 08-10-2010 12:40  
 Date Received: 8/11/2010  
 Matrix: Soil  
 Sample Amount: 5.46 g  
 %Solids: 96.5

Report Name Compound	Result MG/KG	Quantitation Limit MG/KG	Dilution Factor	Date Analyzed
Acetone	BQL	0.0475	1	8/17/2010
Benzene	BQL	0.00475	1	8/17/2010
Bromobenzene	BQL	0.00475	1	8/17/2010
Bromochloromethane	BQL	0.00475	1	8/17/2010
Bromodichloromethane	BQL	0.00475	1	8/17/2010
Bromoform	BQL	0.00475	1	8/17/2010
Bromomethane	BQL	0.00475	1	8/17/2010
2-Butanone	BQL	0.0237	1	8/17/2010
n-Butylbenzene	BQL	0.00475	1	8/17/2010
sec-Butylbenzene	BQL	0.00475	1	8/17/2010
tert-Butylbenzene	BQL	0.00475	1	8/17/2010
Carbon disulfide	BQL	0.00475	1	8/17/2010
Carbon tetrachloride	BQL	0.00475	1	8/17/2010
Chlorobenzene	BQL	0.00475	1	8/17/2010
Chloroethane	BQL	0.00475	1	8/17/2010
Chloroform	BQL	0.00475	1	8/17/2010
Chloromethane	BQL	0.00475	1	8/17/2010
2-Chlorotoluene	BQL	0.00475	1	8/17/2010
4-Chlorotoluene	BQL	0.00475	1	8/17/2010
Dibromochloromethane	BQL	0.00475	1	8/17/2010
1,2-Dibromo-3-chloropropane	BQL	0.0237	1	8/17/2010
Dibromomethane	BQL	0.00475	1	8/17/2010
1,2-Dibromoethane (EDB)	BQL	0.00475	1	8/17/2010
1,2-Dichlorobenzene	BQL	0.00475	1	8/17/2010
1,3-Dichlorobenzene	BQL	0.00475	1	8/17/2010
1,4-Dichlorobenzene	BQL	0.00475	1	8/17/2010
trans-1,4-Dichloro-2-butene	BQL	0.0237	1	8/17/2010
1,1-Dichloroethane	BQL	0.00475	1	8/17/2010
1,1-Dichloroethene	BQL	0.00475	1	8/17/2010
1,2-Dichloroethane	BQL	0.00475	1	8/17/2010
cis-1,2-Dichloroethene	BQL	0.00475	1	8/17/2010
trans-1,2-dichloroethene	BQL	0.00475	1	8/17/2010
1,2-Dichloropropane	BQL	0.00475	1	8/17/2010
1,3-Dichloropropane	BQL	0.00475	1	8/17/2010
2,2-Dichloropropane	BQL	0.00475	1	8/17/2010
1,1-Dichloropropene	BQL	0.00475	1	8/17/2010
cis-1,3-Dichloropropene	BQL	0.00475	1	8/17/2010
trans-1,3-Dichloropropene	BQL	0.00475	1	8/17/2010
Dichlorodifluoromethane	BQL	0.00475	1	8/17/2010
Diisopropyl ether (DIPE)	BQL	0.00475	1	8/17/2010
Ethylbenzene	BQL	0.00475	1	8/17/2010
Hexachlorobutadiene	BQL	0.00475	1	8/17/2010
2-Hexanone	BQL	0.0119	1	8/17/2010
Iodomethane	BQL	0.00475	1	8/17/2010

**Results for Volatiles  
by GCMS 8260-5035**

Client Sample ID: HF-1  
 Client Project ID: NCDOT  
 Lab Sample ID G1037-95-1A  
 Lab Project ID: G1037-95  
 Report Basis: Dry Weight

Analyzed By: DVO  
 Date Collected: 08-10-2010 12:40  
 Date Received: 8/11/2010  
 Matrix: Soil  
 Sample Amount: 5.46 g  
 %Solids: 96.5

Report Name Compound	Result MG/KG	Quantitation Limit MG/KG	Dilution Factor	Date Analyzed
Isopropylbenzene	BQL	0.00475	1	8/17/2010
4-Isopropyltoluene	BQL	0.00475	1	8/17/2010
Methylene chloride	BQL	0.0190	1	8/17/2010
4-Methyl-2-pentanone	BQL	0.0119	1	8/17/2010
Methyl-tert-butyl ether (MTBE)	BQL	0.00475	1	8/17/2010
Naphthalene	BQL	0.00475	1	8/17/2010
n-Propyl benzene	BQL	0.00475	1	8/17/2010
Styrene	BQL	0.00475	1	8/17/2010
1,1,1,2-Tetrachloroethane	BQL	0.00475	1	8/17/2010
1,1,2,2-Tetrachloroethane	BQL	0.00475	1	8/17/2010
Tetrachloroethene	BQL	0.00475	1	8/17/2010
Toluene	BQL	0.00475	1	8/17/2010
1,2,3-Trichlorobenzene	BQL	0.00475	1	8/17/2010
1,2,4-Trichlorobenzene	BQL	0.00475	1	8/17/2010
Trichloroethene	BQL	0.00475	1	8/17/2010
1,1,1-Trichloroethane	BQL	0.00475	1	8/17/2010
1,1,2-Trichloroethane	BQL	0.00475	1	8/17/2010
Trichlorofluoromethane	BQL	0.00475	1	8/17/2010
1,2,3-Trichloropropane	BQL	0.00475	1	8/17/2010
1,2,4-Trimethylbenzene	BQL	0.00475	1	8/17/2010
1,3,5-Trimethylbenzene	BQL	0.00475	1	8/17/2010
Vinyl chloride	BQL	0.00475	1	8/17/2010
m-,p-Xylene	BQL	0.00949	1	8/17/2010
o-Xylene	BQL	0.00475	1	8/17/2010


	Spike Added	Spike Result	Percent Recovered
1,2-Dichloroethane-d4	0.03	0.0364	121
Toluene-d8	0.03	0.0237	79
4-Bromofluorobenzene	0.03	0.0258	86

**Comments:**

**Flags:**

BQL = Below Quantitation Limits.

Analyst: DVO

Reviewed By: 

**Results for Volatiles  
by GCMS 8260-5035**

Client Sample ID: HF-2  
 Client Project ID: NCDOT  
 Lab Sample ID G1037-95-2A  
 Lab Project ID: G1037-95  
 Report Basis: Dry Weight

Analyzed By: DVO  
 Date Collected: 08-10-2010 13:00  
 Date Received: 8/11/2010  
 Matrix: Soil  
 Sample Amount: 5.40 g  
 %Solids: 95.2

Report Name Compound	Result MG/KG	Quantitation Limit MG/KG	Dilution Factor	Date Analyzed
Acetone	BQL	0.0486	1	8/17/2010
Benzene	BQL	0.00486	1	8/17/2010
Bromobenzene	BQL	0.00486	1	8/17/2010
Bromochloromethane	BQL	0.00486	1	8/17/2010
Bromodichloromethane	BQL	0.00486	1	8/17/2010
Bromoform	BQL	0.00486	1	8/17/2010
Bromomethane	BQL	0.00486	1	8/17/2010
2-Butanone	BQL	0.0243	1	8/17/2010
n-Butylbenzene	BQL	0.00486	1	8/17/2010
sec-Butylbenzene	BQL	0.00486	1	8/17/2010
tert-Butylbenzene	BQL	0.00486	1	8/17/2010
Carbon disulfide	BQL	0.00486	1	8/17/2010
Carbon tetrachloride	BQL	0.00486	1	8/17/2010
Chlorobenzene	BQL	0.00486	1	8/17/2010
Chloroethane	BQL	0.00486	1	8/17/2010
Chloroform	BQL	0.00486	1	8/17/2010
Chloromethane	BQL	0.00486	1	8/17/2010
2-Chlorotoluene	BQL	0.00486	1	8/17/2010
4-Chlorotoluene	BQL	0.00486	1	8/17/2010
Dibromochloromethane	BQL	0.00486	1	8/17/2010
1,2-Dibromo-3-chloropropane	BQL	0.0243	1	8/17/2010
Dibromomethane	BQL	0.00486	1	8/17/2010
1,2-Dibromoethane (EDB)	BQL	0.00486	1	8/17/2010
1,2-Dichlorobenzene	BQL	0.00486	1	8/17/2010
1,3-Dichlorobenzene	BQL	0.00486	1	8/17/2010
1,4-Dichlorobenzene	BQL	0.00486	1	8/17/2010
trans-1,4-Dichloro-2-butene	BQL	0.0243	1	8/17/2010
1,1-Dichloroethane	BQL	0.00486	1	8/17/2010
1,1-Dichloroethene	BQL	0.00486	1	8/17/2010
1,2-Dichloroethane	BQL	0.00486	1	8/17/2010
cis-1,2-Dichloroethene	BQL	0.00486	1	8/17/2010
trans-1,2-dichloroethene	BQL	0.00486	1	8/17/2010
1,2-Dichloropropane	BQL	0.00486	1	8/17/2010
1,3-Dichloropropane	BQL	0.00486	1	8/17/2010
2,2-Dichloropropane	BQL	0.00486	1	8/17/2010
1,1-Dichloropropene	BQL	0.00486	1	8/17/2010
cis-1,3-Dichloropropene	BQL	0.00486	1	8/17/2010
trans-1,3-Dichloropropene	BQL	0.00486	1	8/17/2010
Dichlorodifluoromethane	BQL	0.00486	1	8/17/2010
Diisopropyl ether (DIPE)	BQL	0.00486	1	8/17/2010
Ethylbenzene	BQL	0.00486	1	8/17/2010
Hexachlorobutadiene	BQL	0.00486	1	8/17/2010
2-Hexanone	BQL	0.0122	1	8/17/2010
Iodomethane	BQL	0.00486	1	8/17/2010

**Results for Volatiles  
by GCMS 8260-5035**

Client Sample ID: HF-2  
 Client Project ID: NCDOT  
 Lab Sample ID G1037-95-2A  
 Lab Project ID: G1037-95  
 Report Basis: Dry Weight

Analyzed By: DVO  
 Date Collected: 08-10-2010 13:00  
 Date Received: 8/11/2010  
 Matrix: Soil  
 Sample Amount: 5.40 g  
 %Solids: 95.2

Report Name Compound	Result MG/KG	Quantitation Limit MG/KG	Dilution Factor	Date Analyzed
Isopropylbenzene	BQL	0.00486	1	8/17/2010
4-Isopropyltoluene	BQL	0.00486	1	8/17/2010
Methylene chloride	BQL	0.0194	1	8/17/2010
4-Methyl-2-pentanone	BQL	0.0122	1	8/17/2010
Methyl-tert-butyl ether (MTBE)	BQL	0.00486	1	8/17/2010
Naphthalene	BQL	0.00486	1	8/17/2010
n-Propyl benzene	BQL	0.00486	1	8/17/2010
Styrene	BQL	0.00486	1	8/17/2010
1,1,1,2-Tetrachloroethane	BQL	0.00486	1	8/17/2010
1,1,2,2-Tetrachloroethane	BQL	0.00486	1	8/17/2010
Tetrachloroethene	BQL	0.00486	1	8/17/2010
Toluene	BQL	0.00486	1	8/17/2010
1,2,3-Trichlorobenzene	BQL	0.00486	1	8/17/2010
1,2,4-Trichlorobenzene	BQL	0.00486	1	8/17/2010
Trichloroethene	BQL	0.00486	1	8/17/2010
1,1,1-Trichloroethane	BQL	0.00486	1	8/17/2010
1,1,2-Trichloroethane	BQL	0.00486	1	8/17/2010
Trichlorofluoromethane	BQL	0.00486	1	8/17/2010
1,2,3-Trichloropropane	BQL	0.00486	1	8/17/2010
1,2,4-Trimethylbenzene	BQL	0.00486	1	8/17/2010
1,3,5-Trimethylbenzene	BQL	0.00486	1	8/17/2010
Vinyl chloride	BQL	0.00486	1	8/17/2010
m-,p-Xylene	BQL	0.00972	1	8/17/2010
o-Xylene	BQL	0.00486	1	8/17/2010

	Spike Added	Spike Result	Percent Recovered
1,2-Dichloroethane-d4	0.03	0.0376	125
Toluene-d8	0.03	0.0239	80
4-Bromofluorobenzene	0.03	0.0258	86

**Comments:**

**Flags:**

BQL = Below Quantitation Limits.

Analyst: DVG

Reviewed By: 

**Results for Total Petroleum Hydrocarbons**  
by GC/FID 8015

Client Sample ID: HF-1  
Client Project ID: NCDOT  
Lab Sample ID: G1037-95-1E  
Lab Project ID: G1037-95  
Report Basis: Dry Weight

Analyzed By: LMC  
Date Collected: 8/10/2010 12:40  
Date Received: 8/11/2010  
Matrix: Soil  
Solids 96.46

Analyte	Result	RL	Units	Dilution Factor	Date Analyzed
Gasoline Range Organics	BQL	5.74	mg/Kg	1	08/19/10 21:54

**Surrogate Spike Results**

	Added	Result	Recovery	Flag	Limits
BFB	100	95.8	95.8		70-130

Comments:


**Batch Information**

Analytical Batch: VP081910  
Analytical Method: 8015  
Instrument ID: GC4  
Analyst: LMC

Prep Method: 5035  
Initial Wt/Vol: 5.42 g  
Final Volume: 5 mL

Analyst: LMC

NC Certification #481

Reviewed By:   
GRO.XLS

**Results for Total Petroleum Hydrocarbons**  
by GC/FID 8015

Client Sample ID: HF-2  
Client Project ID: NCDOT  
Lab Sample ID: G1037-95-2E  
Lab Project ID: G1037-95  
Report Basis: Dry Weight

Analyzed By: LMC  
Date Collected: 8/10/2010 13:00  
Date Received: 8/11/2010  
Matrix: Soil  
Solids 95.23

Analyte	Result	RL	Units	Dilution Factor	Date Analyzed
Gasoline Range Organics	BQL	5.71	mg/Kg	1	08/19/10 22:21

**Surrogate Spike Results**

	Added	Result	Recovery	Flag	Limits
BFB	100	96.5	96.5		70-130

**Comments:**

**Batch Information**

Analytical Batch: VP081910  
Analytical Method: 8015  
Instrument ID: GC4  
Analyst: LMC

Prep Method: 5035  
Initial Wt/Vol: 5.52 g  
Final Volume: 5 mL

Analyst: LMC

NC Certification #481

Reviewed By:   
GRO.XLS

**Results for Total Petroleum Hydrocarbons**  
by GC/FID 8015

Client Sample ID: HF-1  
Client Project ID: NCDOT  
Lab Sample ID: G1037-95-11  
Lab Project ID: G1037-95

Date Collected: 8/10/2010 12:40  
Date Received: 8/11/2010  
Matrix: Soil  
Solids 96.46  
Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	BQL	6.05	mg/Kg	1	08/17/10 07:10
<b>Surrogate Spike Results</b>		<b>Spike Added</b>	<b>Control Limits</b>	<b>Spike Result</b>	<b>Percent Recovery</b>
OTP		40	40-140	31.8	79.5

Comments:


**Batch Information**

Analytical Batch: EP081610  
Analytical Method: 8015  
Instrument: GC6  
Analyst: DTF

Prep batch: 17206  
Prep Method: 3541  
Prep Date: 08/13/10  
Initial Prep Wt/Vol: 34.28 G  
Prep Final Vol: 10 mL

Analyst: FX

NC Certification #481

Reviewed By:   
DRO.XLS



**Results for Total Petroleum Hydrocarbons**  
by GC/FID 8015

Client Sample ID: HF-2  
Client Project ID: NCDOT  
Lab Sample ID: G1037-95-21  
Lab Project ID: G1037-95

Date Collected: 8/10/2010 13:00  
Date Received: 8/11/2010  
Matrix: Soil  
Solids 95.23  
Report Basis: Dry Weight

Parameter	Result	RL	Units	Dilution Factor	Date Analyzed
Diesel Range Organics	BQL	6.21	mg/Kg	1	08/17/10 07:38
<b>Surrogate Spike Results</b>		<b>Spike Added</b>	<b>Control Limits</b>	<b>Spike Result</b>	<b>Percent Recovery</b>
OTP		40	40-140	32.6	81.5

Comments:

**Batch Information**

Analytical Batch: EP081610  
Analytical Method: 8015  
Instrument: GC6  
Analyst: DTF

Prep batch: 17206  
Prep Method: 3541  
Prep Date: 08/13/10  
Initial Prep Wt/Vol: 33.81 G  
Prep Final Vol: 10 mL

Analyst: FX

NC Certification #481

Reviewed By:   
DRO.XLS

