

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	4 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	83,500 CY		
0006	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (11+82.86 -Y3)	Lump Sum	L.S.	
0007	0036000000-E	225	UNDERCUT EXCAVATION	45,000 CY		
0008	0106000000-E	230	BORROW EXCAVATION	479,000 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,950 CY		
0010	0141000000-E	240	BERM DITCH CONSTRUCTION	530 LF		
0011	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	29,120 SY		
0012	0177000000-E	250	BREAKING OF EXISTING ASPHALT PAVEMENT	47,400 SY		
0013	0192000000-N	260	PROOF ROLLING	30 HR		
0014	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	56,720 CY		
0015	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	4,500 SY		
0016	0262000000-N	SP	GENERIC GRADING ITEM ENERGY DISSIPATOR BASIN	1 EA		
0017	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	3,133 TON		
0018	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	9,890 SY		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0342000000-E	310	*** SIDE DRAIN PIPE (30")	1,132 LF		
0020	0342000000-E	310	*** SIDE DRAIN PIPE (42")	556 LF		
0021	0342000000-E	310	*** SIDE DRAIN PIPE (48")	44 LF		
0022	0343000000-E	310	15" SIDE DRAIN PIPE	3,184 LF		
0023	0344000000-E	310	18" SIDE DRAIN PIPE	1,280 LF		
0024	0345000000-E	310	24" SIDE DRAIN PIPE	1,316 LF		
0025	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	8,260 LF		
0026	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,956 LF		
0027	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	2,576 LF		
0028	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	3,240 LF		
0029	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	1,096 LF		
0030	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	304 LF		
0031	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	260 LF		
0032	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	1,412 LF		
0033	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	448 LF		
0034	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	72 LF		
0035	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	296 LF		
0036	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	164 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	40 LF		
0038	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	4 EA		
0039	0974000000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE B, (UNDER RR) (15", 0.500")	100 LF		
0040	0995000000-E	340	PIPE REMOVAL	8,368 LF		
0041	1000000000-E	462	6" SLOPE PROTECTION	60 SY		
0042	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0043	1077000000-E	SP	#57 STONE	250 TON		
0044	1099500000-E	505	SHALLOW UNDERCUT	400 CY		
0045	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	750 TON		
0046	1110000000-E	510	STABILIZER AGGREGATE	250 TON		
0047	1121000000-E	520	AGGREGATE BASE COURSE	54,990 TON		
0048	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0049	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	500 SY		
0050	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	12,000 SY		
0051	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	6,950 TON		
0052	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	34,010 TON		
0053	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	40,270 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,710 TON		
0055	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	39,800 TON		
0056	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	6,430 TON		
0057	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	880 TON		
0058	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	10,000 LF		
0059	1869000000-E	710	***** PORT CEM CONC PAVEMENT, MISCELLANEOUS (WITHOUT DOWELS) (8")	380 SY		
0060	2022000000-E	815	SUBDRAIN EXCAVATION	118 CY		
0061	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	100 SY		
0062	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0063	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	17 CY		
0064	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	350 LF		
0065	2070000000-N	815	SUBDRAIN PIPE OUTLET	2 EA		
0066	2077000000-E	815	6" OUTLET PIPE	12 LF		
0067	2209000000-E	838	ENDWALLS	16.2 CY		
0068	2220000000-E	838	REINFORCED ENDWALLS	5 CY		
0069	2253000000-E	840	PIPE COLLARS	5.868 CY		
0070	2264000000-E	840	PIPE PLUGS	5.392 CY		
0071	2275000000-E	SP	FLOWABLE FILL	57.92 CY		
0072	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	286 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	164		LF
0074	2354200000-N	840	FRAME WITH GRATE, STD 840.24	2		EA
0075	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	71		EA
0076	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	7		EA
0077	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	18		EA
0078	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4		EA
0079	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	20		EA
0080	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	73		EA
0081	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	72		EA
0082	2396000000-N	840	FRAME WITH COVER, STD 840.54	27		EA
0083	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	39		EA
0084	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	27		EA
0085	2535000000-E	846	***X *** CONCRETE CURB (8" X 18")	5,850		LF
0086	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	16,600		LF
0087	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	30,200		LF
0088	2556000000-E	846	SHOULDER BERM GUTTER	50		LF
0089	2591000000-E	848	4" CONCRETE SIDEWALK	6,200		SY

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	2605000000-N	848	CONCRETE CURB RAMP	74 EA		
0091	2612000000-E	848	6" CONCRETE DRIVEWAY	680 SY		
0092	2619000000-E	850	4" CONCRETE PAVED DITCH	20 SY		
0093	2627000000-E	852	4" CONCRETE ISLAND COVER	1,730 SY		
0094	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	4,020 SY		
0095	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	200 SY		
0096	2703000000-E	854	CONCRETE BARRIER, TYPE ***** (T)	2,790 LF		
0097	2710000000-N	854	CONCRETE BARRIER TRANSITION SECTION	4 EA		
0098	2752000000-E	SP	GENERIC PAVING ITEM MEDIAN HAZARD PROTECTION	60 LF		
0099	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	17 EA		
0100	2815000000-N	858	ADJUSTMENT OF DROP INLETS	18 EA		
0101	2830000000-N	858	ADJUSTMENT OF MANHOLES	35 EA		
0102	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	85 EA		
0103	2875000000-N	859	CONVERT EXISTING CATCH BASIN TO DROP INLET	1 EA		
0104	2893000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX WITH MANHOLE	4 EA		
0105	2920000000-N	859	CONVERT EXISTING DROP INLET TO CATCH BASIN	1 EA		
0106	2938000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE	2 EA		
0107	2965000000-N	859	CONVERT EXISTING JUNCTION BOX TO CATCH BASIN	1 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	3000000000-N	SP	IMPACT ATTENUATOR UNIT, TYPE 350	5 EA		
0109	3030000000-E	862	STEEL BM GUARDRAIL	1,875 LF		
0110	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0111	3060000000-E	862	STEEL BM GUARDRAIL, DOUBLE FACED	375 LF		
0112	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0113	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0114	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	5 EA		
0115	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0116	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	1 EA		
0117	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	7 EA		
0118	3360000000-E	863	REMOVE EXISTING GUARDRAIL	750 LF		
0119	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	4,100 LF		
0120	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	260 EA		
0121	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	55 EA		
0122	3533000000-E	866	CHAIN LINK FENCE, *** FABRIC (60")	2,435 LF		
0123	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	5,200 LF		
0124	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (60")	202 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0125	3539000000-E	866	METAL LINE POSTS FOR *** CHAIN LINK FENCE (84")	240 EA		
0126	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	438 EA		
0127	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (60")	18 EA		
0128	3545000000-E	866	METAL TERMINAL POSTS FOR *** CHAIN LINK FENCE (84")	20 EA		
0129	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	27 EA		
0130	3557000000-E	866	ADDITIONAL BARBED WIRE	500 LF		
0131	3564000000-E	866	SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (84" HIGH, 20' WIDE, 20' OPEN)	1 EA		
0132	3565000000-E	866	DOUBLE GATES, *** HIGH, *** WIDE, *** OPENING (84" HIGH, 14' WIDE, 28' OPEN)	1 EA		
0133	3566000000-E	867	WOVEN WIRE FENCE RESET	50 LF		
0134	3572000000-E	867	CHAIN LINK FENCE RESET	890 LF		
0135	3575000000-E	SP	GENERIC FENCING ITEM 84" CHAIN LINK SECURITY FENCE	2,900 LF		
0136	3628000000-E	876	RIP RAP, CLASS I	590 TON		
0137	3649000000-E	876	RIP RAP, CLASS B	250 TON		
0138	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	5,865 SY		
0139	3883000000-N	SP	GENERIC TRACKWORK ITEM BRAGG BLVD CROSSING SIGNAL INSTALLATION	Lump Sum	L.S.	
0140	3883000000-N	SP	GENERIC TRACKWORK ITEM BRAGG BLVD CROSSING SURFACE INSTALLATION	Lump Sum	L.S.	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0141	3883000000-N	SP	GENERIC TRACKWORK ITEM RANDOLPH STREET CROSSING SIGNAL INSTALLATION	Lump Sum	L.S.	
0142	3883000000-N	SP	GENERIC TRACKWORK ITEM RANDOLPH STREET CROSSING SURFACE INSTALLATION	Lump Sum	L.S.	
0143	4048000000-E	902	REINFORCED CONCRETE SIGN FOUN- DATIONS	10 CY		
0144	4054000000-E	902	PLAIN CONCRETE SIGN FOUNDA- TIONS	1 CY		
0145	4057000000-E	SP	OVERHEAD FOOTING	195 CY		
0146	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	9,765 LB		
0147	4066000000-E	903	SUPPORTS, SIMPLE STEEL BEAM	183 LB		
0148	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	2,687 LF		
0149	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUC- TURE AT STA ***** (102+50 -L-)	Lump Sum	L.S.	
0150	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUC- TURE AT STA ***** (120+00 -L-)	Lump Sum	L.S.	
0151	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUC- TURE AT STA ***** (132+00 -L-)	Lump Sum	L.S.	
0152	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUC- TURE AT STA ***** (149+50 -L-)	Lump Sum	L.S.	
0153	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUC- TURE AT STA ***** (15+00 -Y7-)	Lump Sum	L.S.	
0154	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUC- TURE AT STA ***** (166+00 -L-)	Lump Sum	L.S.	
0155	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUC- TURE AT STA ***** (182+00 -L-)	Lump Sum	L.S.	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0156	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (19+50 -Y3-)	Lump Sum	L.S.	
0157	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (191+45 -L-)	Lump Sum	L.S.	
0158	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (22+00 -Y4-)	Lump Sum	L.S.	
0159	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (23+50 -Y3RPA-)	Lump Sum	L.S.	
0160	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (26+00 -Y3-)	Lump Sum	L.S.	
0161	4082100000-N	SP	SUPPORTS, OVERHEAD SIGN STRUCTURE AT STA ***** (93+00 -L-)	Lump Sum	L.S.	
0162	4096000000-N	904	SIGN ERECTION, TYPE D	5 EA		
0163	4102000000-N	904	SIGN ERECTION, TYPE E	155 EA		
0164	4108000000-N	904	SIGN ERECTION, TYPE F	6 EA		
0165	4109000000-N	904	SIGN ERECTION, TYPE *** (OVERHEAD) (A)	1 EA		
0166	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	10 EA		
0167	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	1 EA		
0168	4115000000-N	904	SIGN ERECTION, OVERLAY (OVERHEAD)	4 EA		
0169	4116000000-N	904	SIGN ERECTION, OVERLAY (GROUND MOUNTED)	1 EA		
0170	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (A)	1 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0171	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	2 EA		
0172	4149000000-N	907	DISPOSAL OF SIGN SYSTEM, OVER-HEAD	2 EA		
0173	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	3 EA		
0174	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	137 EA		
0175	4234000000-N	907	DISPOSAL OF SIGN, A OR B (OVERHEAD)	1 EA		
0176	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,130 SF		
0177	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	730 SF		
0178	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	430 SF		
0179	4415000000-N	1115	FLASHING ARROW BOARD	4 EA		
0180	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	5 EA		
0181	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	40 DAY		
0182	4430000000-N	1130	DRUMS	500 EA		
0183	4435000000-N	1135	CONES	100 EA		
0184	4445000000-E	1145	BARRICADES (TYPE III)	612 LF		
0185	4455000000-N	1150	FLAGGER	100 DAY		
0186	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	5 EA		
0187	4470000000-N	1160	RESET TEMPORARY CRASH CUSHION	8 EA		
0188	4480000000-N	1165	TMA	4 EA		
0189	4485000000-E	1170	PORTABLE CONCRETE BARRIER	5,300 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0190	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	8,300 LF		
0191	4507000000-E	1170	WATER FILLED BARRIER	1,720 LF		
0192	4508000000-E	1170	RESET WATER FILLED BARRIER	450 LF		
0193	4510000000-N	SP	LAW ENFORCEMENT	100 HR		
0194	4516000000-N	1180	SKINNY DRUM	300 EA		
0195	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	2,142 EA		
0196	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	22,420 LF		
0197	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	19,133 LF		
0198	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	26,377 LF		
0199	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	17,537 LF		
0200	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	2,377 LF		
0201	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,122 LF		
0202	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	3,458 LF		
0203	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	1,676 LF		
0204	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	374 LF		
0205	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,204 LF		
0206	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	90 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0207	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	71 EA		
0208	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	1,308 LF		
0209	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	790 LF		
0210	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	43,050 LF		
0211	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	900 LF		
0212	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	224 LF		
0213	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	360 LF		
0214	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	34 EA		
0215	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	26 EA		
0216	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	5,271 LF		
0217	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	71 EA		
0218	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	7 EA		
0219	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,640 EA		
0220	5005000000-E	1401	80' HIGH MOUNT STANDARD	2 EA		
0221	5010000000-E	1401	100' HIGH MOUNT STANDARD	3 EA		
0222	5020000000-N	1401	PORTABLE DRIVE UNIT	1 EA		
0223	5025000000-E	SP	HIGH MOUNT FOUNDATIONS	33 CY		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0224	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (400W HPS)	16 EA		
0225	5030000000-N	1403	HIGH MOUNT LUMINAIRES ***** (750W HPS)	18 EA		
0226	5120000000-N	1407	ELECTRIC SERVICE POLE **** ***** (30' CLASS 4)	1 EA		
0227	5125000000-E	1407	ELECTRIC SERVICE LATERAL ***** (3,#1/0 USE)	50 LF		
0228	5145000000-N	1408	LIGHT CONTROL EQUIPMENT, TYPE RW ***** (SSPM)	1 EA		
0229	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (2")	150 LF		
0230	5155000000-E	1409	ELECTRICAL DUCT, TYPE BD, SIZE ***** (3")	110 LF		
0231	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (3")	40 LF		
0232	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (4")	130 LF		
0233	5160000000-E	1409	ELECTRICAL DUCT, TYPE JA, SIZE ***** (6")	60 LF		
0234	5170000000-E	1410	** #8 W/G FEEDER CIRCUIT (2)	120 LF		
0235	5175000000-E	1410	** #6 W/G FEEDER CIRCUIT (2)	310 LF		
0236	5180000000-E	1410	** #4 W/G FEEDER CIRCUIT (2)	240 LF		
0237	5185000000-E	1410	** #2 W/G FEEDER CIRCUIT (2)	310 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0238	5205000000-E	1410	** #8 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	520 LF		
0239	5210000000-E	1410	** #6 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	900 LF		
0240	5215000000-E	1410	** #4 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	3,900 LF		
0241	5220000000-E	1410	** #2 W/G FEEDER CIRCUIT IN ***** CONDUIT (2, 1-1/2")	1,760 LF		
0242	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC18)	10 EA		
0243	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC30)	4 EA		
0244	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0245	5325200000-E	1510	2" WATER LINE	274 LF		
0246	5325400000-E	1510	4" WATER LINE	150 LF		
0247	5325600000-E	1510	6" WATER LINE	3,043 LF		
0248	5325800000-E	1510	8" WATER LINE	345 LF		
0249	5326200000-E	1510	12" WATER LINE	267 LF		
0250	5326600000-E	1510	16" WATER LINE	841 LF		
0251	5536000000-E	1515	2" VALVE	1 EA		
0252	5538000000-E	1515	4" VALVE	1 EA		
0253	5540000000-E	1515	6" VALVE	9 EA		
0254	5546000000-E	1515	8" VALVE	1 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0255	5558000000-E	1515	12" VALVE	1 EA		
0256	5648000000-N	1515	RELOCATE WATER METER	35 EA		
0257	5649000000-N	1515	RECONNECT WATER METER	7 EA		
0258	5672000000-N	1515	RELOCATE FIRE HYDRANT	9 EA		
0259	5691400000-E	1520	10" SANITARY GRAVITY SEWER	779 LF		
0260	5709100000-E	1520	2" FORCE MAIN SEWER	510 LF		
0261	5775000000-E	1525	4' DIA UTILITY MANHOLE	10 EA		
0262	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	36 LF		
0263	5802000000-E	1530	ABANDON 10" UTILITY PIPE	947 LF		
0264	5804000000-E	1530	ABANDON 12" UTILITY PIPE	254 LF		
0265	5810000000-E	1530	ABANDON 16" UTILITY PIPE	7,150 LF		
0266	5815000000-N	1530	REMOVE WATER METER	6 EA		
0267	5816000000-N	1530	ABANDON UTILITY MANHOLE	4 EA		
0268	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE VALVE VAULT	1 EA		
0269	5882000000-N	SP	GENERIC UTILITY ITEM REMOVE UTILITY VAULT	2 EA		
0270	6000000000-E	1605	TEMPORARY SILT FENCE	52,100 LF		
0271	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	3,370 TON		
0272	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	9,085 TON		
0273	6012000000-E	1610	SEDIMENT CONTROL STONE	8,060 TON		
0274	6015000000-E	1615	TEMPORARY MULCHING	85 ACR		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0275	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	2,150	LB	
0276	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	11.25	TON	
0277	6024000000-E	1622	TEMPORARY SLOPE DRAINS	7,500	LF	
0278	6029000000-E	SP	SAFETY FENCE	3,000	LF	
0279	6030000000-E	1630	SILT EXCAVATION	10,750	CY	
0280	6036000000-E	1631	MATTING FOR EROSION CONTROL	69,000	SY	
0281	6037000000-E	SP	COIR FIBER MAT	1,650	SY	
0282	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	6,210	SY	
0283	6042000000-E	1632	1/4" HARDWARE CLOTH	15,350	LF	
0284	6070000000-N	1639	SPECIAL STILLING BASINS	8	EA	
0285	6071010000-E	SP	WATTLE	3,900	LF	
0286	6071020000-E	SP	POLYACRYLAMIDE (PAM)	2,425	LB	
0287	6071030000-E	1640	COIR FIBER BAFFLE	3,500	LF	
0288	6071050000-E	SP	*** SKIMMER (1-1/2")	18	EA	
0289	6084000000-E	1660	SEEDING & MULCHING	75	ACR	
0290	6087000000-E	1660	MOWING	35	ACR	
0291	6090000000-E	1661	SEED FOR REPAIR SEEDING	900	LB	
0292	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	3.75	TON	
0293	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	2,250	LB	
0294	6108000000-E	1665	FERTILIZER TOPDRESSING	66.75	TON	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0295	6111000000-E	SP	IMPERVIOUS DIKE	100 LF		
0296	6114500000-N	1667	SPECIALIZED HAND MOWING	100 MHR		
0297	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	175 EA		
0298	6123000000-E	1670	REFORESTATION	1 ACR		
0299	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION DEVICE	75 EA		
0300	7048500000-E	1705	PEDESTRIAN SIGNAL HEAD (16", 1 SECTION W/COUNTDOWN)	4 EA		
0301	7060000000-E	1705	SIGNAL CABLE	10,400 LF		
0302	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	71 EA		
0303	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	7 EA		
0304	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2 EA		
0305	7204000000-N	1705	LOUVER	2 EA		
0306	7216000000-N	1705	MODIFY EXISTING VEHICLE SIGNAL HEAD	3 EA		
0307	7252000000-E	1710	MESSENGER CABLE (1/4")	250 LF		
0308	7264000000-E	1710	MESSENGER CABLE (3/8")	3,570 LF		
0309	7288000000-E	1715	PAVED TRENCHING (***** (1,2"))	60 LF		
0310	7300000000-E	1715	UNPAVED TRENCHING (***** (1,2"))	1,280 LF		
0311	7300100000-E	1715	UNPAVED TRENCHING FOR TEMP- ORARY LEAD-IN	590 LF		
0312	7301000000-E	1715	DIRECTIONAL DRILL (***** (1,2"))	400 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0313	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	16 EA		
0314	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEAVY DUTY)	6 EA		
0315	7360000000-N	1720	WOOD POLE	15 EA		
0316	7372000000-N	1721	GUY ASSEMBLY	26 EA		
0317	7408000000-E	1722	1" RISER WITH WEATHERHEAD	6 EA		
0318	7420000000-E	1722	2" RISER WITH WEATHERHEAD	26 EA		
0319	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	10,620 LF		
0320	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	21,610 LF		
0321	7528000000-E	1730	DROP CABLE	400 LF		
0322	7541000000-N	1731	MODIFY SPLICE ENCLOSURE	1 EA		
0323	7575142000-N	1736	900MHZ RADIO	3 EA		
0324	7576000000-N	SP	METAL STRAIN SIGNAL POLE	12 EA		
0325	7613000000-N	SP	SOIL TEST	12 EA		
0326	7614100000-E	SP	DRILLED PIER FOUNDATION	72 CY		
0327	7636000000-N	1745	SIGN FOR SIGNALS	12 EA		
0328	7642100000-N	1743	TYPE I POST WITH FOUNDATION	1 EA		
0329	7684000000-N	1750	SIGNAL CABINET FOUNDATION	4 EA		
0330	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	4 EA		
0331	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	31 EA		
0332	7948000000-N	1757	TRAFFIC SIGNAL REMOVAL	1 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0333	7960000000-N	SP	METAL POLE FOUNDATION REMOVAL	4 EA		
0334	7972000000-N	SP	METAL POLE REMOVAL	4 EA		
0335	7980000000-N	SP	GENERIC SIGNAL ITEM 900MHZ WIRELESS REPEATER STANDALONE RADIO SYSTEM	1 EA		
0336	7980000000-N	SP	GENERIC SIGNAL ITEM CCTV ASSEMBLY	1 EA		
0337	7980000000-N	SP	GENERIC SIGNAL ITEM VIDEO ENCODER TRANSMITTER	1 EA		
0338	7985000000-N	SP	GENERIC SIGNAL ITEM CENTRAL SOFTWARE MODIFICATIONS	Lump Sum	L.S.	
0369	0248000000-N	SP	GENERIC GRADING ITEM REMOVAL & DISPOSAL OF EXISTING MEDIAN BARRIER	Lump Sum	L.S.	
WALL ITEMS						
0339	8802014000-E	SP	SOLDIER PILE RETAINING WALLS	830 SF		
0340	8839000000-E	SP	GENERIC RETAINING WALL ITEM CONCRETE BARRIER RAIL WITH MOMENT SLAB	275 LF		
0341	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 1	10,450 SF		
0342	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 2	6,470 SF		
0343	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 3	12,500 SF		
0344	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 4	4,420 SF		
0345	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 5	4,160 SF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0346	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 7	1,080 SF		
0347	8847000000-E	SP	GENERIC RETAINING WALL ITEM MSE RETAINING WALL NO 8	1,060 SF		
STRUCTURE ITEMS						
0348	8112730000-N	450	PDA TESTING	2 EA		
0349	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	24,355 SF		
0350	8161000000-E	420	GROOVING BRIDGE FLOORS	24,889 SF		
0351	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	229 CY		
0352	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (132+79.28 -L-)	Lump Sum	L.S.	
0353	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (172+95.63 -L-)	Lump Sum	L.S.	
0354	8217000000-E	425	REINFORCING STEEL (BRIDGE)	35,335 LB		
0355	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	1,007.88 LF		
0356	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	1,083,400 LS		
0357	8364000000-E	450	HP12X53 STEEL PILES	3,595 LF		
0358	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (24 X 0.50)	450 LF		
0359	8392000000-N	450	PIPE PILE PLATES	6 EA		
0360	8393000000-N	450	PILE REDRIVES	41 EA		
0361	8482000000-E	460	THREE BAR METAL RAIL	323.7 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0362	8503000000-E	460	CONCRETE BARRIER RAIL	472.77 LF		
0363	8524000000-E	SP	*** CHAIN LINK FENCE (104")	333.7 LF		
0364	8531000000-E	462	4" SLOPE PROTECTION	1,646 SY		
0365	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0366	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0367	8692000000-N	SP	FOAM JOINT SEALS	Lump Sum	L.S.	
0368	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
0832/Oct05/Q2784881.18/D1617269696000/E369			Total Amount Of Bid For Entire Project :			

Contract No. **C202826**

County (ies): **Cumberland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)