

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+16.00-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	400 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	5 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	15 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	32 LF		
0012	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0013	1330000000-E	607	INCIDENTAL MILLING	250 SY		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	300 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	400 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	40 TON		
0017	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0018	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	100 SY		

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	17 CY		
0020	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0021	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0022	2077000000-E	815	6" OUTLET PIPE	6 LF		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0025	2556000000-E	846	SHOULDER BERM GUTTER	70 LF		
0026	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0028	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0029	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0030	3649000000-E	876	RIP RAP, CLASS B	4 TON		
0031	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	514 SY		
0032	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	63 LF		
0033	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0034	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	5 EA		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	389 SF		
0036	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144 SF		
0037	4445000000-E	1145	BARRICADES (TYPE III)	112 LF		

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,800 LF		
0039	6000000000-E	1605	TEMPORARY SILT FENCE	1,000 LF		
0040	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160 TON		
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	80 TON		
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	105 TON		
0043	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0045	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0046	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0047	6029000000-E	SP	SAFETY FENCE	400 LF		
0048	6030000000-E	1630	SILT EXCAVATION	100 CY		
0049	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,500 SY		
0050	6037000000-E	SP	COIR FIBER MAT	200 SY		
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	220 LF		
0052	6070000000-N	1639	SPECIAL STILLING BASINS	2 EA		
0053	6071010000-E	SP	WATTLE	150 LF		
0054	6071012000-E	SP	COIR FIBER WATTLE	40 LF		
0055	6071020000-E	SP	POLYACRYLAMIDE (PAM)	30 LB		
0056	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0057	6087000000-E	1660	MOWING	0.5 ACR		

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0059	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0060	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0061	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0062	6114500000-N	1667	SPECIALIZED HAND MOWING	15 MHR		
0063	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	15 EA		

STRUCTURE ITEMS

0064	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+16.00-L-)	Lump Sum	L.S.	
0065	8112730000-N	450	PDA TESTING	1 EA		
0066	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (17+16.00-L-)	Lump Sum	L.S.	
0067	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	29 CY		
0068	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+16.00-L-)	Lump Sum	L.S.	
0069	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,254 LB		
0070	8364000000-E	450	HP12X53 STEEL PILES	630 LF		
0071	8393000000-N	450	PILE REDRIVES	8 EA		
0072	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	140.25 LF		
0073	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	99 TON		
0074	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	109 SY		

County : Bladen, Columbus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0076	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	770 LF		
1044/Oct02/Q19999.5/D338665972000/E76			Total Amount Of Bid For Entire Project :			

Contract No. **C202956**

County (ies): **Bladen-Columbus**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General