

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (17+95.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	1,500 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	5 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	20 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	16 LF		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	32 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	75 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	230 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	260 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	160 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	290 TON		

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	40 TON		
0020	2000000000-N	806	RIGHT OF WAY MARKERS	12 EA		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0023	2556000000-E	846	SHOULDER BERM GUTTER	29.5 LF		
0024	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	3 EA		
0026	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0028	3635000000-E	876	RIP RAP, CLASS II	140 TON		
0029	3649000000-E	876	RIP RAP, CLASS B	217 TON		
0030	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,780 SY		
0031	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0032	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	90 LF		
0033	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0034	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
0035	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	3 EA		
0036	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0037	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	1 EA		

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	517 SF		
0039	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144 SF		
0040	4445000000-E	1145	BARRICADES (TYPE III)	112 LF		
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,600 LF		
0042	6000000000-E	1605	TEMPORARY SILT FENCE	760 LF		
0043	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160 TON		
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	75 TON		
0045	6012000000-E	1610	SEDIMENT CONTROL STONE	255 TON		
0046	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0048	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
0049	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0050	6029000000-E	SP	SAFETY FENCE	300 LF		
0051	6030000000-E	1630	SILT EXCAVATION	150 CY		
0052	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,200 SY		
0053	6037000000-E	SP	COIR FIBER MAT	750 SY		
0054	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	250 SY		
0055	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
0056	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	160 SY		

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6070000000-N	1639	SPECIAL STILLING BASINS	12 EA		
0058	6071012000-E	SP	COIR FIBER WATTLE	40 LF		
0059	6071030000-E	1640	COIR FIBER BAFFLE	110 LF		
0060	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0061	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0062	6087000000-E	1660	MOWING	0.5 ACR		
0063	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0064	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0065	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0066	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0067	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0068	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0069	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

0070	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+95.00-L-)	Lump Sum	L.S.	
0071	8096000000-E	450	PILE EXCAVATION IN SOIL	33 LF		
0072	8097000000-E	450	PILE EXCAVATION NOT IN SOIL	37 LF		
0073	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	65 LF		

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	37 LF		
0075	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	62 LF		
0076	8113000000-N	411	SID INSPECTIONS	1 EA		
0077	8114000000-N	411	SPT TESTING	1 EA		
0078	8115000000-N	411	CSL TESTING	1 EA		
0079	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (17+95.00-L-)	Lump Sum	L.S.	
0080	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	57.1 CY		
0081	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+95.00-L-)	Lump Sum	L.S.	
0082	8217000000-E	425	REINFORCING STEEL (BRIDGE)	18,701 LB		
0083	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,105 LB		
0084	8364000000-E	450	HP12X53 STEEL PILES	210 LF		
0085	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	280.75 LF		
0086	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	175 TON		
0087	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	200 SY		
0088	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0089	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,540 LF		

Contract No. **C202952**

County (ies): **Franklin**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)