

County : Hoke, Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+45.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	2,000 CY		
0006	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	3,500 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	3,600 SY		
0008	0199000000-E	SP	TEMPORARY SHORING	2,659 SF		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	30 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	70 SY		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	168 LF		
0012	0348000000-E	310	*** SIDE DRAIN PIPE ELBOWS (15")	2 EA		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	40 LF		
0014	0995000000-E	340	PIPE REMOVAL	132 LF		
0015	1330000000-E	607	INCIDENTAL MILLING	125 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,730 TON		
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	620 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,370 TON		

County : Hoke, Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	190 TON		
0020	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	20 TON		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0023	2556000000-E	846	SHOULDER BERM GUTTER	19 LF		
0024	3030000000-E	862	STEEL BM GUARDRAIL	2,475 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0026	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0027	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0028	3360000000-E	863	REMOVE EXISTING GUARDRAIL	2,202 LF		
0029	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	1,062.5 LF		
0030	3389000000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (350)	3 EA		
0031	3649000000-E	876	RIP RAP, CLASS B	9 TON		
0032	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	565 SY		
0033	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	114 LF		
0034	4096000000-N	904	SIGN ERECTION, TYPE D	4 EA		
0035	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	4 EA		
0036	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	132 SF		
0037	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		

County : Hoke, Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	24 SF		
0039	4430000000-N	1130	DRUMS	36 EA		
0040	4435000000-N	1135	CONES	25 EA		
0041	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0042	4450000000-N	1150	FLAGGER	200 HR		
0043	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0044	4480000000-N	1165	TMA	2 EA		
0045	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	339 LF		
0046	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	95 EA		
0047	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,230 LF		
0048	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,295 LF		
0049	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	1,144 LF		
0050	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	30,400 LF		
0051	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	7,200 LF		
0052	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	24 EA		
0053	6000000000-E	1605	TEMPORARY SILT FENCE	6,300 LF		
0054	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	370 TON		
0055	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	470 TON		

County : Hoke, Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6012000000-E	1610	SEDIMENT CONTROL STONE	680 TON		
0057	6015000000-E	1615	TEMPORARY MULCHING	7.5 ACR		
0058	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250 LB		
0059	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2 TON		
0060	6024000000-E	1622	TEMPORARY SLOPE DRAINS	1,550 LF		
0061	6029000000-E	SP	SAFETY FENCE	1,400 LF		
0062	6030000000-E	1630	SILT EXCAVATION	1,150 CY		
0063	6036000000-E	1631	MATTING FOR EROSION CONTROL	12,000 SY		
0064	6037000000-E	SP	COIR FIBER MAT	40 SY		
0065	6042000000-E	1632	1/4" HARDWARE CLOTH	2,350 LF		
0066	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	430 SY		
0067	6071012000-E	SP	COIR FIBER WATTLE	350 LF		
0068	6071020000-E	SP	POLYACRYLAMIDE (PAM)	100 LB		
0069	6071030000-E	1640	COIR FIBER BAFFLE	270 LF		
0070	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
0071	6084000000-E	1660	SEEDING & MULCHING	6 ACR		
0072	6087000000-E	1660	MOWING	3 ACR		
0073	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0074	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0075	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	175 LB		

County : Hoke, Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6108000000-E	1665	FERTILIZER TOPDRESSING	5 TON		
0077	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0078	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	40 EA		
0079	6123000000-E	1670	REFORESTATION	0.5 ACR		
STRUCTURE ITEMS						
0080	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (22+45.00-L-)	Lump Sum	L.S.	
0081	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (22+45.00-L-)	Lump Sum	L.S.	
0082	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22+45.00-L-)	Lump Sum	L.S.	
0083	8112730000-N	450	PDA TESTING	2 EA		
0084	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (22+45.00-L-)	Lump Sum	L.S.	
0085	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	11,756 SF		
0086	8161000000-E	420	GROOVING BRIDGE FLOORS	11,597 SF		
0087	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	99.7 CY		
0088	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+45.00-L-)	Lump Sum	L.S.	
0089	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,824 LB		
0090	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	1,402.92 LF		

County : Hoke, Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	8364000000-E	450	HP12X53 STEEL PILES	600 LF		
0092	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (16 X 0.50)	1,540 LF		
0093	8392000000-N	450	PIPE PILE PLATES	22 EA		
0094	8393000000-N	450	PILE REDRIVES	32 EA		
0095	8503000000-E	460	CONCRETE BARRIER RAIL	566.67 LF		
0096	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	525 TON		
0097	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	580 SY		
0098	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

1232/Oct04/Q140641.04/D461057842000/E98

Total Amount Of Bid For Entire Project :

Contract No. **C202949**

County (ies): **Scotland and Hoke**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)