

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (24 + 47.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	250 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	54 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	350 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20 TON		
001C	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	60 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	76 LF		
0012	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	88 LF		
0014	0995000000-E	340	PIPE REMOVAL	40 LF		
0015	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0016	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	200 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0018	1330000000-E	607	INCIDENTAL MILLING	40 SY		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	410	TON	
0020	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	370	TON	
0021	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	280	TON	
0022	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	55	TON	
0023	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50	TON	
0024	2022000000-E	815	SUBDRAIN EXCAVATION	56	CY	
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	42	CY	
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250	LF	
0027	2070000000-N	815	SUBDRAIN PIPE OUTLET	1	EA	
0028	2077000000-E	815	6" OUTLET PIPE	6	LF	
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3	EA	
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3	EA	
0031	2556000000-E	846	SHOULDER BERM GUTTER	282	LF	
0032	3030000000-E	862	STEEL BM GUARDRAIL	625	LF	
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	3	EA	
0034	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0036	3569000000-E	867	BARBED WIRE FENCE RESET	140	LF	

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3628000000-E	876	RIP RAP, CLASS I	275 TON		
003E	3649000000-E	876	RIP RAP, CLASS B	22 TON		
003E	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	2,070 SY		
004C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	415 SF		
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	141 SF		
0042	4430000000-N	1130	DRUMS	10 EA		
004E	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0044	6000000000-E	1605	TEMPORARY SILT FENCE	2,350 LF		
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	355 TON		
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	510 TON		
004E	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
005C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.5 TON		
0051	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0052	6029000000-E	SP	SAFETY FENCE	500 LF		
005E	6030000000-E	1630	SILT EXCAVATION	430 CY		
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,500 SY		
005E	6037000000-E	SP	COIR FIBER MAT	350 SY		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
0057	6070000000-N	1639	SPECIAL STILLING BASINS	18 EA		
005E	6071010000-E	SP	WATTLE	50 LF		
005E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	70 LB		
006C	6071030000-E	1640	COIR FIBER BAFFLE	200 LF		
0061	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0062	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
006E	6087000000-E	1660	MOWING	1.5 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
006E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
006E	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		

**STRUCTURE ITEMS**

007C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (24 + 47.50-L-)	Lump Sum	L.S.	
0071	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	55 LF		
0072	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	77 LF		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	54 LF		
0074	8115000000-N	411	CSL TESTING	1 EA		
007E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (24 + 47.50-L-)	Lump Sum	L.S.	
007E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	73.7 CY		
0077	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (24 + 47.50-L-)	Lump Sum	L.S.	
007E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	28,275 LB		
007E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,683 LB		
008C	8364000000-E	450	HP12X53 STEEL PILES	155 LF		
0081	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	351 LF		
0082	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	210 TON		
0083	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	230 SY		
0084	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
008E	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,750 LF		

1439/Oct02/Q55092.7/D36839770000/E85

Total Amount Of Bid For Entire Project :

**Contract No.**     **C202954**

**County (ies):**    **Union**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General