

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (21 + 18.61-L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	300 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	2 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	5 SY		
0010	0335200000-E	305	15" DRAINAGE PIPE	12 LF		
0011	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0012	1330000000-E	607	INCIDENTAL MILLING	280 SY		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	180 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	150 TON		
0015	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	20 TON		
0016	2022000000-E	815	SUBDRAIN EXCAVATION	25 CY		
0017	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0018	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2070000000-N	815	SUBDRAIN PIPE OUTLET	1	EA	
0020	2077000000-E	815	6" OUTLET PIPE	6	LF	
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1	EA	
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1	EA	
0023	2556000000-E	846	SHOULDER BERM GUTTER	10	LF	
0024	3030000000-E	862	STEEL BM GUARDRAIL	50	LF	
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0026	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0028	3649000000-E	876	RIP RAP, CLASS B	1	TON	
0029	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	465	SY	
0030	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	74	LF	
0031	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
0032	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	8	EA	
0033	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	376	SF	
0034	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119	SF	
0035	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	
0036	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,010	LF	
0037	6000000000-E	1605	TEMPORARY SILT FENCE	730	LF	

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	30 TON		
004C	6012000000-E	1610	SEDIMENT CONTROL STONE	70 TON		
0041	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0044	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
004E	6029000000-E	SP	SAFETY FENCE	100 LF		
004E	6030000000-E	1630	SILT EXCAVATION	100 CY		
0047	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500 SY		
004E	6037000000-E	SP	COIR FIBER MAT	200 SY		
004E	6042000000-E	1632	1/4" HARDWARE CLOTH	325 LF		
005C	6071010000-E	SP	WATTLE	50 LF		
0051	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
0052	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
005E	6087000000-E	1660	MOWING	0.5 ACR		
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
005E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
005E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
STRUCTURE ITEMS						
006C	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21 + 18.61-L-)	Lump Sum	L.S.	
0061	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (21 + 18.61-L-)	Lump Sum	L.S.	
0062	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	26.6 CY		
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21 + 18.61-L-)	Lump Sum	L.S.	
0064	8217000000-E	425	REINFORCING STEEL (BRIDGE)	3,954 LB		
006E	8364000000-E	450	HP12X53 STEEL PILES	205 LF		
006E	8391000000-N	450	STEEL PILE POINTS	10 EA		
0067	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	140.25 LF		
006E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	125 TON		
006E	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	140 SY		
007C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0071	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	700 LF		

Contract No. **C203019**

County (ies): **Caswell**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General