

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15+40)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	150 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	100 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	12 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	40 SY		
0010	0335200000-E	305	15" DRAINAGE PIPE	24 LF		
0011	0335300000-E	305	18" DRAINAGE PIPE	84 LF		
0012	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0013	1330000000-E	607	INCIDENTAL MILLING	90 SY		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	490 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	180 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	35 TON		
0017	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2355000000-N	840	FRAME WITH GRATE, STD 840.29	1		
				EA		
002C	2396000000-N	840	FRAME WITH COVER, STD 840.54	1		
				EA		
0021	2556000000-E	846	SHOULDER BERM GUTTER	35		
				LF		
0022	3030000000-E	862	STEEL BM GUARDRAIL	50		
				LF		
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		
				EA		
0024	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4		
				EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4		
				EA		
002E	3628000000-E	876	RIP RAP, CLASS I	4		
				TON		
0027	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	830		
				SY		
002E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	61		
				LF		
002E	4096000000-N	904	SIGN ERECTION, TYPE D	2		
				EA		
003C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	4		
				EA		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	345		
				SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	131		
				SF		
0033	4445000000-E	1145	BARRICADES (TYPE III)	96		
				LF		
0034	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,440		
				LF		
003E	6000000000-E	1605	TEMPORARY SILT FENCE	850		
				LF		
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	190		
				TON		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
003E	6012000000-E	1610	SEDIMENT CONTROL STONE	240 TON		
003E	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
004C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0041	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0042	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
004E	6029000000-E	SP	SAFETY FENCE	100 LF		
0044	6030000000-E	1630	SILT EXCAVATION	100 CY		
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,750 SY		
004E	6037000000-E	SP	COIR FIBER MAT	250 SY		
0047	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	200 SY		
004E	6042000000-E	1632	1/4" HARDWARE CLOTH	425 LF		
004E	6070000000-N	1639	SPECIAL STILLING BASINS	6 EA		
005C	6071010000-E	SP	WATTLE	30 LF		
0051	6071020000-E	SP	POLYACRYLAMIDE (PAM)	30 LB		
0052	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
005E	6087000000-E	1660	MOWING	0.5 ACR		
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
005E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
005E	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
005E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
STRUCTURE ITEMS						
006C	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+40.00-L-)	Lump Sum	L.S.	
0061	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+40.00-L-)	Lump Sum	L.S.	
0062	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	24 LF		
006E	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	18 LF		
0064	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	24 LF		
006E	8113000000-N	411	SID INSPECTIONS	1 EA		
006E	8115000000-N	411	CSL TESTING	1 EA		
0067	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+40.00-L-)	Lump Sum	L.S.	
006E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	45.5 CY		
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15+40.00-L-)	Lump Sum	L.S.	
007C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,248 LB		

County : Chatham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,471 LB		
0072	8364000000-E	450	HP12X53 STEEL PILES	150 LF		
0073	8391000000-N	450	STEEL PILE POINTS	10 EA		
0074	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	260.5 LF		
007E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	340 TON		
007E	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	375 SY		
0077	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
007E	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	1,300 LF		
1419/Nov02/Q29259.75/D378863320000/E78				Total Amount Of Bid For Entire Project :		

Contract No. **C203020**

County (ies): **Chatham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)