

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (23+40.00 -L-)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	1,380 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	500 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	69 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	3,916 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	196 LF		
0013	0335400000-E	305	24" DRAINAGE PIPE	24 LF		
0014	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (15", V)	32 LF		
0015	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	132 LF		
0016	0995000000-E	340	PIPE REMOVAL	15 LF		
0017	1330000000-E	607	INCIDENTAL MILLING	370 SY		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	790 TON		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	530 TON		
0020	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	67 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0024	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE	6 LF		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0027	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	4.5 LF		
0028	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0029	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2 EA		
0030	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	3 EA		
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	2 EA		
0032	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	880 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	62.5 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0038	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	510 SY		
0039	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	9 SF		
0040	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	27 LF		
0041	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0042	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	1 EA		
0043	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	6 EA		
0044	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	1 EA		
0045	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	458 SF		
0047	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0048	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	96 SF		
0049	4435000000-N	1135	CONES	25 EA		
0050	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0051	4455000000-N	1150	FLAGGER	40 DAY		
0052	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	850 LF		
0053	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,472 LF		
0054	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	9 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	5325800000-E	1510	8" WATER LINE	408 LF		
0056	5326600000-E	1510	16" WATER LINE	663 LF		
0057	5546000000-E	1515	8" VALVE	2 EA		
0058	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0059	5691500000-E	1520	12" SANITARY GRAVITY SEWER	413 LF		
0060	5775000000-E	1525	4' DIA UTILITY MANHOLE	1 EA		
0061	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	14 LF		
0062	5801000000-E	1530	ABANDON 8" UTILITY PIPE	274 LF		
0063	5804000000-E	1530	ABANDON 12" UTILITY PIPE	102 LF		
0064	5828000000-N	1530	REMOVE UTILITY MANHOLE	2 EA		
0065	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	143 LF		
0066	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	142 LF		
0067	5876000000-N	SP	STEEL PILE PIERS	5 EA		
0068	6000000000-E	1605	TEMPORARY SILT FENCE	1,150 LF		
0069	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160 TON		
0070	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	65 TON		
0071	6012000000-E	1610	SEDIMENT CONTROL STONE	130 TON		
0072	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0073	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0075	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100 LF		
0076	6029000000-E	SP	SAFETY FENCE	300 LF		
0077	6030000000-E	1630	SILT EXCAVATION	130 CY		
0078	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,400 SY		
0079	6037000000-E	SP	COIR FIBER MAT	400 SY		
0080	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	40 SY		
0081	6042000000-E	1632	1/4" HARDWARE CLOTH	370 LF		
0082	6070000000-N	1639	SPECIAL STILLING BASINS	2 EA		
0083	6071010000-E	SP	WATTLE	165 LF		
0084	6071012000-E	SP	COIR FIBER WATTLE	40 LF		
0085	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
0086	6071030000-E	1640	COIR FIBER BAFFLE	40 LF		
0087	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0088	6084000000-E	1660	SEEDING & MULCHING	1.5 ACR		
0089	6087000000-E	1660	MOWING	1 ACR		
0090	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0091	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0092	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0093	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0095	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	15 EA		
STRUCTURE ITEMS						
0096	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (23+40.00-L-)	Lump Sum	L.S.	
0097	8112730000-N	450	PDA TESTING	1 EA		
0098	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (23+40.00-L-)	Lump Sum	L.S.	
0099	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	31.7 CY		
0100	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	52.6 CY		
0101	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (23+40.00-L-)	Lump Sum	L.S.	
0102	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,269 LB		
0103	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	1,380 LB		
0104	8364000000-E	450	HP12X53 STEEL PILES	640 LF		
0105	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	650 LF		
0106	8393000000-N	450	PILE REDRIVES	13 EA		
0107	8475000000-E	460	TWO BAR METAL RAIL	185.25 LF		
0108	8517000000-E	460	1'***X ***** CONCRETE PARA- PET (1'-2" X 3'-5 3/8")	200.25 LF		
0109	8594000000-E	876	RIP RAP, CLASS B	34 TON		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	135 TON		
0111	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	155 SY		
0112	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0113	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,600 LF		
1432/Nov02/Q34994.55/D520556062000/E113			Total Amount Of Bid For Entire Project :			

Contract No. **C203017**

County (ies): **Cumberland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General