

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (23+51.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	55 CY		
0006	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA-TION	500 SY		
0007	0335200000-E	305	15" DRAINAGE PIPE	36 LF		
0008	0335300000-E	305	18" DRAINAGE PIPE	208 LF		
0009	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	44 LF		
0010	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	40 LF		
0011	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0012	0995000000-E	340	PIPE REMOVAL	225 LF		
0013	1099500000-E	505	SHALLOW UNDERCUT	175 CY		
0014	1099700000-E	505	CLASS IV SUBGRADE STABILIZA-TION	350 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	125 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	295 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	230 TON		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	245 TON		
0020	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	40 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	56 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	42 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	250 LF		
0024	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE	6 LF		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0028	2556000000-E	846	SHOULDER BERM GUTTER	20 LF		
0029	3030000000-E	862	STEEL BM GUARDRAIL	87.5 LF		
0030	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0034	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0035	3628000000-E	876	RIP RAP, CLASS I	185 TON		
0036	3635000000-E	876	RIP RAP, CLASS II	50 TON		
0037	3649000000-E	876	RIP RAP, CLASS B	10 TON		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,015		SY
0039	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	100		LF
0040	4096000000-N	904	SIGN ERECTION, TYPE D	3		EA
0041	4102000000-N	904	SIGN ERECTION, TYPE E	4		EA
0042	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	1		EA
0043	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	10		EA
0044	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1		EA
0045	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	374		SF
0046	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	104		SF
0047	4430000000-N	1130	DRUMS	12		EA
0048	4445000000-E	1145	BARRICADES (TYPE III)	104		LF
0049	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,200		LF
0050	6000000000-E	1605	TEMPORARY SILT FENCE	915		LF
0051	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160		TON
0052	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	285		TON
0053	6012000000-E	1610	SEDIMENT CONTROL STONE	185		TON
0054	6015000000-E	1615	TEMPORARY MULCHING	1		ACR
0055	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50		LB
0056	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25		TON

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200		
					LF	
0058	6029000000-E	SP	SAFETY FENCE	100		
					LF	
0059	6030000000-E	1630	SILT EXCAVATION	130		
					CY	
0060	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500		
					SY	
0061	6037000000-E	SP	COIR FIBER MAT	80		
					SY	
0062	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	150		
					SY	
0063	6042000000-E	1632	1/4" HARDWARE CLOTH	170		
					LF	
0064	6070000000-N	1639	SPECIAL STILLING BASINS	4		
					EA	
0065	6071020000-E	SP	POLYACRYLAMIDE (PAM)	80		
					LB	
0066	6084000000-E	1660	SEEDING & MULCHING	1.5		
					ACR	
0067	6087000000-E	1660	MOWING	0.5		
					ACR	
0068	6090000000-E	1661	SEED FOR REPAIR SEEDING	50		
					LB	
0069	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25		
					TON	
0070	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50		
					LB	
0071	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75		
					TON	
0072	6114500000-N	1667	SPECIALIZED HAND MOWING	20		
					MHR	
0073	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18		
					EA	

STRUCTURE ITEMS

0074	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (23+51.50-L-)	Lump Sum	L.S.	
------	--------------	----	--	----------	------	--

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	9 LF		
0076	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	18 LF		
0077	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	9 LF		
0078	8113000000-N	411	SID INSPECTIONS	1 EA		
0079	8114000000-N	411	SPT TESTING	1 EA		
0080	8115000000-N	411	CSL TESTING	1 EA		
0081	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (23+51.50-L-)	Lump Sum	L.S.	
0082	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,090 SF		
0083	8161000000-E	420	GROOVING BRIDGE FLOORS	4,581 SF		
0084	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	52.2 CY		
0085	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (23+51.50-L-)	Lump Sum	L.S.	
0086	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,372 LB		
0087	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	846 LB		
0088	8262000000-E	430	45" PRESTRESSED CONCRETE GIRDERS	481 LF		
0089	8364000000-E	450	HP12X53 STEEL PILES	215 LF		
0090	8503000000-E	460	CONCRETE BARRIER RAIL	242.67 LF		
0091	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	490 TON		
0092	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	545 SY		

County : Gaston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

1152/Nov05/Q36587.62/D423097960000/E93

Total Amount Of Bid For Entire Project :

Contract No. **C202814**

County (ies): **Gaston**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General