

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0996000000-N	350	PIPE CLEAN-OUT	20 EA		
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	111,411 SY		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	1,557 SY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4-1/2")	173,888 SY		
0006	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	293 TON		
0007	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	31,188 TON		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	13,327 TON		
0009	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	16,154 TON		
001C	1525100000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A (LEVELING COURSE)	1,439 TON		
0011	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	2,320 TON		
0012	1577000000-E	620	POLYMER MODIFIED ASPHALT BIN- DER FOR PLANT MIX	1,664 TON		
0013	1662000000-E	650	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-1 MODIFIED	12,168 TON		
0014	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	120,384 LF		
0015	2995000000-N	SP	GENERIC DRAINAGE ITEM DRAINAGE STRUCTURE CLEAN-OUT	20 EA		
0016	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	421 SF		

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	400	SF	
001E	4415000000-N	1115	FLASHING ARROW BOARD	2	EA	
001E	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	5	EA	
002C	4430000000-N	1130	DRUMS	200	EA	
0021	4480000000-N	1165	TMA	2	EA	
0022	4516000000-N	1180	SKINNY DRUM	1,550	EA	
0023	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	10,203	LF	
0024	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	131,328	LF	
002E	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	15,048	LF	
002E	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	1,418	LF	
0027	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	96	EA	
002E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	6	EA	
002E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	141,968	LF	
003C	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	153,648	LF	
0031	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	1,200	LF	
0032	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	200	LF	
0033	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,035	EA	

County : Haywood

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	4960000000-N	SP	GENERIC TRAFFIC CONTROL ITEM ALUMINUM CORRUGATED DELINEATOR	150 EA		
003E	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
1329/Nov07/Q944715.0/D115792400000/E35			Total Amount Of Bid For Entire Project :			

Contract No. **C203137**

County (ies): **Haywood**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General