

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	39,800 CY		
0006	0036000000-E	225	UNDERCUT EXCAVATION	4,400 CY		
0007	0106000000-E	230	BORROW EXCAVATION	21,200 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	460 CY		
0009	0141000000-E	240	BERM DITCH CONSTRUCTION	640 LF		
0010	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	3,110 SY		
0011	0192000000-N	260	PROOF ROLLING	5 HR		
0012	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	5,500 SY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	860 TON		
0014	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	2,660 SY		
0015	0335200000-E	305	15" DRAINAGE PIPE	568 LF		
0016	0335300000-E	305	18" DRAINAGE PIPE	476 LF		
0017	0335400000-E	305	24" DRAINAGE PIPE	448 LF		
0018	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	60 LF		
0019	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	252 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	1,262 LF		
0021	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	600 LF		
0022	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	364 LF		
0023	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	184 LF		
0024	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	16 LF		
0025	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	140 LF		
0026	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (24", 0.064")	4 EA		
0027	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (36", 0.5")	46 LF		
0028	0973300000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B NOT IN SOIL (36", 0.5")	46 LF		
0029	0974000000-E	SP	*** WELDED STEEL PIPE, ***** THICK, GRADE B, (UNDER RR) (24", 0.5")	72 LF		
0030	0986000000-E	SP	GENERIC PIPE ITEM 18" BIT COAT CS PIPE, 0.079" THICK (UNDER RAILROAD)	80 LF		
0031	0995000000-E	340	PIPE REMOVAL	807 LF		
0032	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0033	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0034	1330000000-E	607	INCIDENTAL MILLING	1,175 SY		
0035	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,350 TON		
0036	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,870 TON		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,540 TON		
0038	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	440 TON		
0039	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	400 TON		
0040	2000000000-N	806	RIGHT OF WAY MARKERS	61 EA		
0041	2022000000-E	815	SUBDRAIN EXCAVATION	90 CY		
0042	2033000000-E	815	SUBDRAIN FINE AGGREGATE	70 CY		
0043	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	400 LF		
0044	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0045	2077000000-E	815	6" OUTLET PIPE	6 LF		
0046	2209000000-E	838	ENDWALLS	1.4 CY		
0047	2253000000-E	840	PIPE COLLARS	1.5 CY		
0048	2275000000-E	SP	FLOWABLE FILL	30 CY		
0049	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	63 EA		
0050	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	13.9 LF		
0051	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	4 EA		
0052	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	5 EA		
0053	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	7 EA		
0054	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0055	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	20 EA		
0057	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	19 EA		
0058	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0059	2535000000-E	846	***X *** CONCRETE CURB (8" X 12")	240 LF		
0060	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	50 LF		
0061	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	6,760 LF		
0062	2591000000-E	848	4" CONCRETE SIDEWALK	3,370 SY		
0063	2605000000-N	848	CONCRETE CURB RAMP	20 EA		
0064	2612000000-E	848	6" CONCRETE DRIVEWAY	320 SY		
0065	2619000000-E	850	4" CONCRETE PAVED DITCH	130 SY		
0066	2724000000-E	857	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	495 LF		
0067	2830000000-N	858	ADJUSTMENT OF MANHOLES	4 EA		
0068	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
0069	3030000000-E	862	STEEL BM GUARDRAIL	675 LF		
0070	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	162.5 LF		
0071	3105000000-N	862	STEEL BM GUARDRAIL TERMINAL SECTIONS	6 EA		
0072	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0073	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	7 EA		
0075	3360000000-E	863	REMOVE EXISTING GUARDRAIL	160 LF		
0076	3536000000-E	866	CHAIN LINK FENCE, 48" FABRIC	276 LF		
0077	3542000000-E	866	METAL LINE POSTS FOR 48" CHAIN LINK FENCE	24 EA		
0078	3548000000-E	866	METAL TERMINAL POSTS FOR 48" CHAIN LINK FENCE	7 EA		
0079	3649000000-E	876	RIP RAP, CLASS B	175 TON		
0080	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,780 SY		
0081	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0082	3804000000-E	SP	AGGREGATE BASE COURSE (SUB-BALLAST)	8,700 TON		
0083	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	25 SF		
0084	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	157 SF		
0085	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	263 SF		
0086	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	675 LF		
0087	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0088	4102000000-N	904	SIGN ERECTION, TYPE E	20 EA		
0089	4108000000-N	904	SIGN ERECTION, TYPE F	12 EA		
0090	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	16 EA		
0091	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	12 EA		

County: Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	469 SF		
0093	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	261 SF		
0094	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	211 SF		
0095	4430000000-N	1130	DRUMS	91 EA		
0096	4435000000-N	1135	CONES	68 EA		
0097	4445000000-E	1145	BARRICADES (TYPE III)	575 LF		
0098	4450000000-N	1150	FLAGGER	624 HR		
0099	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0100	4485000000-E	1170	PORTABLE CONCRETE BARRIER	620 LF		
0101	4516000000-N	1180	SKINNY DRUM	30 EA		
0102	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	721 LF		
0103	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	9,943 LF		
0104	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	430 LF		
0105	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	294 LF		
0106	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	18 EA		
0107	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	30,176 LF		
0108	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	598 LF		
0109	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	2,298 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0110	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	9 EA		
0111	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	137 LF		
0112	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	164 EA		
0113	4915000000-E	1264	7' U-CHANNEL POSTS	3 EA		
0114	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3 EA		
0115	5325600000-E	1510	6" WATER LINE	659 LF		
0116	5325800000-E	1510	8" WATER LINE	67 LF		
0117	5326200000-E	1510	12" WATER LINE	112 LF		
0118	5540000000-E	1515	6" VALVE	2 EA		
0119	5558000000-E	1515	12" VALVE	2 EA		
0120	5606000000-E	1515	2" BLOW OFF	2 EA		
0121	5648000000-N	1515	RELOCATE WATER METER	4 EA		
0122	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0123	5691300000-E	1520	8" SANITARY GRAVITY SEWER	2,607 LF		
0124	5775000000-E	1525	4' DIA UTILITY MANHOLE	10 EA		
0125	5776000000-E	1525	5' DIA UTILITY MANHOLE	4 EA		
0126	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	2.79 LF		
0127	5782000000-E	1525	UTILITY MANHOLE WALL, 5' DIA	14.64 LF		
0128	5800000000-E	1530	ABANDON 6" UTILITY PIPE	532 LF		
0129	5801000000-E	1530	ABANDON 8" UTILITY PIPE	1,102 LF		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0130	5804000000-E	1530	ABANDON 12" UTILITY PIPE	309		LF
0131	5815500000-N	1530	REMOVE FIRE HYDRANT	1		EA
0132	5816000000-N	1530	ABANDON UTILITY MANHOLE	1		EA
0133	5828000000-N	1530	REMOVE UTILITY MANHOLE	2		EA
0134	5835700000-E	1540	16" ENCASEMENT PIPE	76		LF
0135	5835800000-E	1540	18" ENCASEMENT PIPE	162		LF
0136	5872000000-E	1550	TRENCHLESS INSTALLATION OF 18" IN SOIL	40		LF
0137	5872010000-E	1550	TRENCHLESS INSTALLATION OF 18" NOT IN SOIL	40		LF
0138	6000000000-E	1605	TEMPORARY SILT FENCE	18,210		LF
0139	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	345		TON
0140	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	3,095		TON
0141	6012000000-E	1610	SEDIMENT CONTROL STONE	1,760		TON
0142	6015000000-E	1615	TEMPORARY MULCHING	24		ACR
0143	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	500		LB
0144	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	3		TON
0145	6024000000-E	1622	TEMPORARY SLOPE DRAINS	793		LF
0146	6030000000-E	1630	SILT EXCAVATION	5,610		CY
0147	6036000000-E	1631	MATTING FOR EROSION CONTROL	18,850		SY
0148	6037000000-E	SP	COIR FIBER MAT	60		SY

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0149	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,575	SY	
0150	6042000000-E	1632	1/4" HARDWARE CLOTH	3,900	LF	
0151	6070000000-N	1639	SPECIAL STILLING BASINS	4	EA	
0152	6071012000-E	SP	COIR FIBER WATTLE	1,975	LF	
0153	6071020000-E	SP	POLYACRYLAMIDE (PAM)	865	LB	
0154	6071030000-E	1640	COIR FIBER BAFFLE	905	LF	
0155	6071050000-E	SP	*** SKIMMER (1-1/2")	4	EA	
0156	6084000000-E	1660	SEEDING & MULCHING	15	ACR	
0157	6087000000-E	1660	MOWING	18	ACR	
0158	6090000000-E	1661	SEED FOR REPAIR SEEDING	250	LB	
0159	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75	TON	
0160	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	350	LB	
0161	6108000000-E	1665	FERTILIZER TOPDRESSING	11	TON	
0162	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0163	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	150	EA	
0164	7060000000-E	1705	SIGNAL CABLE	2,300	LF	
0165	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	21	EA	
0166	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	2	EA	
0167	7252000000-E	1710	MESSENGER CABLE (1/4")	1,050	LF	
0168	7264000000-E	1710	MESSENGER CABLE (3/8")	960	LF	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0169	7279000000-E	1715	TRACER WIRE	3,525	LF	
0170	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	3,470	LF	
0171	7300100000-E	1715	UNPAVED TRENCHING FOR TEMP- ORARY LEAD-IN	30	LF	
0172	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1, 2")	500	LF	
0173	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	10	EA	
0174	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	11	EA	
0175	7360000000-N	1720	WOOD POLE	7	EA	
0176	7372000000-N	1721	GUY ASSEMBLY	18	EA	
0177	7396000000-E	1722	1/2" RISER WITH WEATHERHEAD	2	EA	
0178	7408000000-E	1722	1" RISER WITH WEATHERHEAD	2	EA	
0179	7420000000-E	1722	2" RISER WITH WEATHERHEAD	10	EA	
0180	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,400	LF	
0181	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	4,150	LF	
0182	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	3,650	LF	
0183	7528000000-E	1730	DROP CABLE	1,100	LF	
0184	7540000000-N	1731	SPLICE ENCLOSURE	2	EA	
0185	7552000000-N	1731	INTERCONNECT CENTER	1	EA	
0186	7566000000-N	1733	DELINEATOR MARKER	4	EA	
0187	7568000000-N	SP	FURNISH FIBER-OPTIC RESTORA- TION KIT	1	EA	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0188	7570000000-N	SP	FURNISH FIBER-OPTIC POWER ME- TER	1 EA		
0189	7572000000-N	SP	FURNISH OPTICAL LIGHT GENERA- TOR	1 EA		
0190	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	1,000 LF		
0191	7575180000-N	1735	CABLE TRANSFER	7 EA		
0192	7576000000-N	SP	METAL STRAIN SIGNAL POLE	2 EA		
0193	7613000000-N	SP	SOIL TEST	2 EA		
0194	7614100000-E	SP	DRILLED PIER FOUNDATION	16 CY		
0195	7636000000-N	1745	SIGN FOR SIGNALS	2 EA		
0196	7642200000-N	1743	TYPE II PEDESTAL WITH FOUND- ATION	1 EA		
0197	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2 EA		
0198	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		
0199	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	6 EA		
0200	7828000000-N	1751	CONTROLLER WITH CABINET (NEMA TS-2, TYPE 2 CONTROLLER, TYPE 1 CABINET, BASE MOUNTED)	1 EA		
0201	7852000000-N	1751	DETECTOR CARD (NEMA TS-2)	6 EA		
0202	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		
0203	7948000000-N	1757	TRAFFIC SIGNAL REMOVAL	1 EA		

WALL ITEMS

0204	8802014000-E	SP	SOLDIER PILE RETAINING WALLS	2,806 SF		
------	--------------	----	------------------------------	-------------	--	--

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0205	8839000000-E	SP	GENERIC RETAINING WALL ITEM RETAINING WALL SAFETY RAIL	97 LF		
STRUCTURE ITEMS						
0206	8112730000-N	450	PDA TESTING	1 EA		
0207	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,182 SF		
0208	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	374.6 CY		
0209	8217000000-E	425	REINFORCING STEEL (BRIDGE)	64,412 LB		
0210	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,644 LB		
0211	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	428,600 LS		
0212	8294000000-N	442	PAINTING OF STRUCTURAL STEEL	Lump Sum	L.S.	
0213	8364000000-E	450	HP12X53 STEEL PILES	6,149 LF		
0214	8453000000-E	454	METHOD B DAMPPROOFING	470 SY		
0215	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-0" X 2'-1")	287.9 LF		
0216	8531000000-E	462	4" SLOPE PROTECTION	425 SY		
0217	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (8916+54.58-MAIN1-)	Lump Sum	L.S.	
0218	8860000000-N	SP	GENERIC STRUCTURE ITEM FOUND EXCAV FOR ABUTMENT 1 AT STA 8916+54.582-MAIN1-	Lump Sum	L.S.	
0219	8860000000-N	SP	GENERIC STRUCTURE ITEM FOUND EXCAV FOR ABUTMENT 2 AT STA 8916+54.582-MAIN1-	Lump Sum	L.S.	

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0220	8860000000-N	SP	GENERIC STRUCTURE ITEM FOUND EXCAV FOR PIER 1 AT STA 8916+54.582-MAIN1-	Lump Sum	L.S.	
0221	8860000000-N	SP	GENERIC STRUCTURE ITEM FOUND EXCAV FOR PIER 2 AT STA 8916+54.582-MAIN1-	Lump Sum	L.S.	
0222	8860000000-N	SP	GENERIC STRUCTURE ITEM SELF-LUBRICATING EXPANSION BEARING ASSEMBLIES	Lump Sum	L.S.	
0223	8860000000-N	SP	GENERIC STRUCTURE ITEM TEMPORARY RAILROAD SHORING	Lump Sum	L.S.	
0224	8867000000-E	SP	GENERIC STRUCTURE ITEM METAL HANDRAIL	365.3 LF		
0225	8893000000-E	SP	GENERIC STRUCTURE ITEM 1" ASPHALT PLANKING PRO- TECTIVE COURSE FOR DECK	525 SY		
0226	8893000000-E	SP	GENERIC STRUCTURE ITEM MEMBRANE LAYER WATER-PROOFING FOR DECK	545 SY		
0227	8893000000-E	SP	GENERIC STRUCTURE ITEM TWO PART MEMBRANE WATER- PROOFING SYSTEM	70 SY		
0911/Oct17/Q770415.88/D1078529206000/E227			Total Amount Of Bid For Entire Project :			

Contract No. **C203127**

County (ies): **Rowan**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)