

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (16 + 19.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	200 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	10 TON		
0009	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	10 SY		
0010	0335200000-E	305	15" DRAINAGE PIPE	24 LF		
0011	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	260 TON		
0013	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	150 TON		
0014	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	270 TON		
0015	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	35 TON		
0016	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	40 TON		
0017	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8	CY	
001E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100	LF	
002C	2070000000-N	815	SUBDRAIN PIPE OUTLET	1	EA	
0021	2077000000-E	815	6" OUTLET PIPE	6	LF	
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2	EA	
0024	2556000000-E	846	SHOULDER BERM GUTTER	75	LF	
002E	3030000000-E	862	STEEL BM GUARDRAIL	100	LF	
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
002E	3649000000-E	876	RIP RAP, CLASS B	2	TON	
003C	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	385	SY	
0031	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	61	LF	
0032	4096000000-N	904	SIGN ERECTION, TYPE D	2	EA	
0033	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	6	EA	
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	506	SF	
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	134	SF	
003E	4445000000-E	1145	BARRICADES (TYPE III)	112	LF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	690	LF	
003E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	690	LF	
0039	5810000000-E	1530	ABANDON 16" UTILITY PIPE	318	LF	
004C	6000000000-E	1605	TEMPORARY SILT FENCE	800	LF	
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160	TON	
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5	TON	
0043	6012000000-E	1610	SEDIMENT CONTROL STONE	50	TON	
0044	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0047	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
004E	6029000000-E	SP	SAFETY FENCE	300	LF	
004E	6030000000-E	1630	SILT EXCAVATION	100	CY	
005C	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000	SY	
0051	6037000000-E	SP	COIR FIBER MAT	50	SY	
0052	6042000000-E	1632	1/4" HARDWARE CLOTH	250	LF	
0053	6084000000-E	1660	SEEDING & MULCHING	0.5	ACR	
0054	6087000000-E	1660	MOWING	0.25	ACR	
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0057	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0058	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0059	6114500000-N	1667	SPECIALIZED HAND MOWING	5 MHR		
0060	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0061	6123000000-E	1670	REFORESTATION	0.1 ACR		

**STRUCTURE ITEMS**

0062	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 19.29 -L-)	Lump Sum	L.S.	
0063	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16 + 19.29 -L-)	Lump Sum	L.S.	
0064	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	29 CY		
0065	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 19.29 -L-)	Lump Sum	L.S.	
0066	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,270 LB		
0067	8364000000-E	450	HP12X53 STEEL PILES	550 LF		
0068	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	140.25 LF		
0069	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	90 TON		
0070	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	100 SY		
0071	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	770 LF		

0917/Oct31/Q14735.8/D314183800000/E72

Total Amount Of Bid For Entire Project :

**Contract No.**     **C203023**

**County (ies):**    **Wake**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

**Contract Officer**

---

**Date**

Execution of Contract and Bonds  
Approved as to Form:

---

**Attorney General**