

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0106000000-E	230	BORROW EXCAVATION	3,985 CY		
0004	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0005	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	10 SY		
0006	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (12")	212 LF		
0007	1220000000-E	545	INCIDENTAL STONE BASE	889 TON		
0008	1245000000-E	SP	SHOULDER RECONSTRUCTION	18.04 SMI		
0009	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1/2")	2,358 SY		
001C	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	243,989 SY		
0011	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	218,634 SY		
0012	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	126,009 SY		
0013	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	65,250 SY		
0014	1330000000-E	607	INCIDENTAL MILLING	19,780 SY		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	8,368 TON		
0016	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,954 TON		

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	18,961	TON	
001E	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	9,897	TON	
001S	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	28,626	TON	
002C	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	49,063	TON	
0021	1524000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5C (LEVELING COURSE)	125	TON	
0022	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	7,965	TON	
0023	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	7,004	TON	
0024	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT CONC SURFACE COURSE, TYPE S4.75A (LEVELING COURSE)	255	TON	
002E	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)	425	TON	
002E	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT I19.0B (MILL PATCH)	325	TON	
0027	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT S9.5B (MILL PATCH)	1,575	TON	
002E	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (MILL)	935	TON	
002S	1891000000-E	SP	GENERIC PAVING ITEM PAVEMENT INTERLAYER	30,828	SY	
003C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7	EA	
0031	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	6	EA	

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0032	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0033	2396000000-N	840	FRAME WITH COVER, STD 840.54	7 EA		
0034	2473000000-N	SP	GENERIC DRAINAGE ITEM FRAME W/GRATE & HOOD, STD 840.03, TYPE E (REMOVE & RE- PLACE)	1 EA		
003E	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	13 LF		
003E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	280 LF		
0037	2591000000-E	848	4" CONCRETE SIDEWALK	98 SY		
003E	2600000000-N	SP	RETROFIT EXISTING CURB RAMP	18 EA		
003E	2605000000-N	848	CONCRETE CURB RAMP	14 EA		
004C	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	110 SY		
0041	2738000000-E	SP	GENERIC PAVING ITEM REMOVAL OF CONCRETE ISLAND	77 SY		
0042	2752000000-E	SP	GENERIC PAVING ITEM REMOVAL OF 1'-6" CURB & GUTTER	28 LF		
0043	2752000000-E	SP	GENERIC PAVING ITEM REMOVE & REPLACE 2'-6" CURB & GUTTER	320 LF		
0044	2759000000-N	SP	GENERIC PAVING ITEM REMOVAL OF CURB RAMPS	6 EA		
004E	2759000000-N	SP	GENERIC PAVING ITEM REMOVE & REPLACE CURB RAMP	46 EA		
004E	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
0047	2830000000-N	858	ADJUSTMENT OF MANHOLES	63 EA		

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
004E	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	77 EA		
004E	2938000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE	7 EA		
005C	2995000000-N	SP	GENERIC DRAINAGE ITEM ADJUSTMENT OF MEDIAN DROP INLET	4 EA		
0051	2995000000-N	SP	GENERIC DRAINAGE ITEM ADJUSTMENT OF MONUMENTS	6 EA		
0052	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
005E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	224 SF		
0054	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	416 SF		
005E	4415000000-N	1115	FLASHING ARROW BOARD	6 EA		
005E	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	6 EA		
0057	4430000000-N	1130	DRUMS	350 EA		
005E	4480000000-N	1165	TMA	6 EA		
005E	4510000000-N	SP	LAW ENFORCEMENT	540 HR		
006C	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	232,907 LF		
0061	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	255,657 LF		
0062	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	9,770 LF		
006E	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,798 LF		
0064	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	1,907 LF		

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	1,724 LF		
006E	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	200 LF		
0067	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	6,863 LF		
006E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	100 EA		
006E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	898 EA		
007C	4726000000-E	1205	HEATED-IN-PLACE THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	696 LF		
0071	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	1,200 LF		
0072	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (IV)	200 LF		
007E	4795000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (24") (IV)	100 LF		
0074	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (IV)	5 EA		
007E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	831,776 LF		
007E	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	51,756 LF		
0077	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	11,323 LF		
007E	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	3,581 LF		

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0079	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	6,599 LF		
008C	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	92 EA		
0081	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	887 EA		
0082	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)	53,894 LF		
0083	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,650 LF		
0084	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	925 LF		
008E	4865000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (12")	480 LF		
008E	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	900 LF		
0087	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	43 EA		
008E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	808 EA		
008E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	5,741 EA		
009C	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0091	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0092	6000000000-E	1605	TEMPORARY SILT FENCE	1,997 LF		
0093	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	450 TON		
0094	6012000000-E	1610	SEDIMENT CONTROL STONE	455 TON		
009E	6015000000-E	1615	TEMPORARY MULCHING	14.24 ACR		

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0097	6030000000-E	1630	SILT EXCAVATION	2 CY		
009E	6036000000-E	1631	MATTING FOR EROSION CONTROL	120 SY		
009E	6042000000-E	1632	1/4" HARDWARE CLOTH	921 LF		
010C	6071010000-E	SP	WATTLE	280 LF		
0101	6084000000-E	1660	SEEDING & MULCHING	13.22 ACR		
0102	6090000000-E	1661	SEED FOR REPAIR SEEDING	899 LB		
010E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	4.5 TON		
0104	7060000000-E	1705	SIGNAL CABLE	1,000 LF		
010E	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	6 EA		
010E	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2 EA		
0107	7264000000-E	1710	MESSENGER CABLE (3/8")	460 LF		
010E	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	180 LF		
010E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	17 EA		
011C	7360000000-N	1720	WOOD POLE	2 EA		
0111	7372000000-N	1721	GUY ASSEMBLY	4 EA		
0112	7420000000-E	1722	2" RISER WITH WEATHERHEAD	1 EA		
011E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	22,840 LF		
0114	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	9,965 LF		

County : Brunswick, New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
011E	7636000000-N	1745	SIGN FOR SIGNALS	1		
				EA		
011E	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	3		
				EA		
1111/Dec11/Q2376360.0/D453274210000/E116			Total Amount Of Bid For Entire Project :			



**Contract No.**     **C203192**

**County (ies):**    **New Hanover, Brunswick, Pender**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)