

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (17+94.00-L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	950 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	950 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	1,050 SY		
0008	0248000000-N	SP	GENERIC GRADING ITEM VIBRATION MONITORING	Lump Sum	L.S.	
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	40 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	16 LF		
0012	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0013	0344000000-E	310	18" SIDE DRAIN PIPE	32 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	28 LF		
0015	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	28 LF		
0016	1121000000-E	520	AGGREGATE BASE COURSE	2,757 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0018	1275000000-E	600	PRIME COAT	1,575 GAL		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	360 TON		
0020	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	730 TON		
0021	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	68 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	19 EA		
0024	2253000000-E	840	PIPE COLLARS	1.5 CY		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0026	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	34 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	262.5 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3360000000-E	863	REMOVE EXISTING GUARDRAIL	366 LF		
0033	3649000000-E	876	RIP RAP, CLASS B	73 TON		
0034	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,320 SY		
0035	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	3 EA		
0036	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	65 LF		
0037	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6 EA		
0039	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	430 SF		
0040	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144 SF		
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	116 SF		
0042	4435000000-N	1135	CONES	50 EA		
0043	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0044	4455000000-N	1150	FLAGGER	40 DAY		
0045	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	18,679 LF		
0046	6000000000-E	1605	TEMPORARY SILT FENCE	2,700 LF		
0047	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	495 TON		
0048	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	740 TON		
0049	6012000000-E	1610	SEDIMENT CONTROL STONE	280 TON		
0050	6015000000-E	1615	TEMPORARY MULCHING	3.5 ACR		
0051	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0052	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5 TON		
0053	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0054	6029000000-E	SP	SAFETY FENCE	600 LF		
0055	6030000000-E	1630	SILT EXCAVATION	850 CY		
0056	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,000 SY		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6037000000-E	SP	COIR FIBER MAT	400 SY		
0058	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,300 SY		
0059	6042000000-E	1632	1/4" HARDWARE CLOTH	455 LF		
0060	6071020000-E	SP	POLYACRYLAMIDE (PAM)	115 LB		
0061	6071030000-E	1640	COIR FIBER BAFFLE	240 LF		
0062	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0063	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0064	6087000000-E	1660	MOWING	1.5 ACR		
0065	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0066	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0068	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0069	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0070	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		

**STRUCTURE ITEMS**

0071	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+94.00-L-)	Lump Sum	L.S.	
0072	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+94.00-L-)	Lump Sum	L.S.	
0073	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	38.4 CY		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+94.00-L-)	Lump Sum	L.S.	
0075	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,044 LB		
0076	8364000000-E	450	HP12X53 STEEL PILES	260 LF		
0077	8391000000-N	450	STEEL PILE POINTS	8 EA		
0078	8475000000-E	460	TWO BAR METAL RAIL	184.04 LF		
0079	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 3'-1")	199.67 LF		
0080	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	260 TON		
0081	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	290 SY		
0082	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0083	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,000 LF		
1154/Dec07/Q52401.61/D355796150000/E83			Total Amount Of Bid For Entire Project :			

**Contract No.**     **C203030**

**County (ies):**    **Randolph**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General