

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (13+83.50)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0106000000-E	230	BORROW EXCAVATION	4,100 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	466 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	400 SY		
001C	0199000000-E	SP	TEMPORARY SHORING	75 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	30 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	70 SY		
0013	0335200000-E	305	15" DRAINAGE PIPE	32 LF		
0014	0335300000-E	305	18" DRAINAGE PIPE	104 LF		
0015	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0016	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (18")	2 EA		
0017	0354000000-E	310	**** RC PIPE CULVERTS, CLASS ***** (18", V)	72 LF		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0995000000-E	340	PIPE REMOVAL	33	LF	
001E	1099500000-E	505	SHALLOW UNDERCUT	100	CY	
002C	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	189	TON	
0021	1121000000-E	520	AGGREGATE BASE COURSE	180	TON	
0022	1220000000-E	545	INCIDENTAL STONE BASE	100	TON	
002E	1275000000-E	600	PRIME COAT	160	GAL	
0024	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	430	TON	
002E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	460	TON	
002E	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	50	TON	
0027	2022000000-E	815	SUBDRAIN EXCAVATION	22.4	CY	
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8	CY	
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100	LF	
003C	2070000000-N	815	SUBDRAIN PIPE OUTLET	1	EA	
0031	2077000000-E	815	6" OUTLET PIPE	6	LF	
003E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
003E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2	EA	
0034	2556000000-E	846	SHOULDER BERM GUTTER	130	LF	
003E	3030000000-E	862	STEEL BM GUARDRAIL	50	LF	
003E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100	LF	

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
003E	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	4	EA	
003E	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III SHOP CURVED)	2	EA	
004C	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2	EA	
0041	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	12.5	LF	
0042	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	62.5	LF	
004E	3387000000-N	862	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (W-BEAM, SHOP CURVED)	1	EA	
0044	3389000000-N	SP	TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	1	EA	
004E	3628000000-E	876	RIP RAP, CLASS I	62	TON	
004E	3649000000-E	876	RIP RAP, CLASS B	7	TON	
0047	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,385	SY	
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	86	LF	
004E	4102000000-N	904	SIGN ERECTION, TYPE E	9	EA	
005C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	8	EA	
0051	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	76	SF	
0052	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144	SF	
005E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	20	SF	

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4430000000-N	1130	DRUMS	77	EA	
005E	4435000000-N	1135	CONES	77	EA	
005E	4445000000-E	1145	BARRICADES (TYPE III)	36	LF	
0057	4455000000-N	1150	FLAGGER	270	DAY	
005E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	22	EA	
005E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,926	LF	
006C	6000000000-E	1605	TEMPORARY SILT FENCE	2,050	LF	
0061	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225	TON	
0062	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	165	TON	
006E	6012000000-E	1610	SEDIMENT CONTROL STONE	345	TON	
0064	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	
006E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
006E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25	TON	
0067	6024000000-E	1622	TEMPORARY SLOPE DRAINS	260	LF	
006E	6029000000-E	SP	SAFETY FENCE	700	LF	
006E	6030000000-E	1630	SILT EXCAVATION	470	CY	
007C	6036000000-E	1631	MATTING FOR EROSION CONTROL	4,000	SY	
0071	6037000000-E	SP	COIR FIBER MAT	950	SY	
0072	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	250	SY	

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		
0074	6070000000-N	1639	SPECIAL STILLING BASINS	12 EA		
007E	6071010000-E	SP	WATTLE	350 LF		
007E	6071012000-E	SP	COIR FIBER WATTLE	75 LF		
0077	6071020000-E	SP	POLYACRYLAMIDE (PAM)	105 LB		
007E	6071030000-E	1640	COIR FIBER BAFFLE	170 LF		
007E	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
008C	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0081	6087000000-E	1660	MOWING	1.5 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0083	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
008E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
008E	6114500000-N	1667	SPECIALIZED HAND MOWING	15 MHR		
0087	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
008E	6123000000-E	1670	REFORESTATION	0.25 ACR		
008E	6126000000-E	SP	STREAMBANK REFORESTATION	0.14 ACR		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
009C	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (13+83.50-L-)	Lump Sum	L.S.	
009I	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+83.50-L-)	Lump Sum	L.S.	
009J	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	91.8 LF		
009K	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	85 LF		
009L	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	79.8 LF		
009M	8113000000-N	411	SID INSPECTIONS	1 EA		
009N	8114000000-N	411	SPT TESTING	1 EA		
009O	8115000000-N	411	CSL TESTING	1 EA		
009P	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	79.9 CY		
009Q	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+83.50-L-)	Lump Sum	L.S.	
010C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	32,173 LB		
010I	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,835 LB		
010J	8364000000-E	450	HP12X53 STEEL PILES	225 LF		
010K	8468000000-E	460	ONE BAR METAL RAIL	415.25 LF		
010L	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (0" X 1'-10.5")	430.75 LF		
010M	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	890 TON		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	990 SY		
0107	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0108	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,450 LF		
0109	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	700 LF		

1449/Nov29/Q72066.59/D476334462000/E109

Total Amount Of Bid For Entire Project :

Contract No. **C203034**

County (ies): **Watauga**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General

Signature Sheet (Bid - Acceptance by Department)