

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (12 + 02.50 -L-)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	100 SY		
0008	1099500000-E	505	SHALLOW UNDERCUT	75 CY		
0009	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	125 TON		
0010	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0011	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	130 TON		
0012	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	110 TON		
0013	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	15 TON		
0014	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0015	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0016	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0017	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0018	2077000000-E	815	6" OUTLET PIPE	6 LF		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2556000000-E	846	SHOULDER BERM GUTTER	22 LF		
0020	3030000000-E	862	STEEL BM GUARDRAIL	87.5 LF		
0021	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25 LF		
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0023	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350, TL-2)	2 EA		
0024	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III - SHOP CURVED)	1 EA		
0025	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0026	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		
0027	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	490 SY		
0028	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	375 SF		
0029	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	73 SF		
0030	4430000000-N	1130	DRUMS	27 EA		
0031	4445000000-E	1145	BARRICADES (TYPE III)	72 LF		
0032	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,721 LF		
0033	6000000000-E	1605	TEMPORARY SILT FENCE	900 LF		
0034	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160 TON		
0035	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	40 TON		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	6012000000-E	1610	SEDIMENT CONTROL STONE	85	TON	
0037	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	
003E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0039	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
004C	6024000000-E	1622	TEMPORARY SLOPE DRAINS	100	LF	
0041	6029000000-E	SP	SAFETY FENCE	100	LF	
0042	6030000000-E	1630	SILT EXCAVATION	60	CY	
0043	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,500	SY	
0044	6037000000-E	SP	COIR FIBER MAT	125	SY	
004E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	200	SY	
004E	6042000000-E	1632	1/4" HARDWARE CLOTH	190	LF	
0047	6070000000-N	1639	SPECIAL STILLING BASINS	2	EA	
004E	6071010000-E	SP	WATTLE	65	LF	
004E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10	LB	
005C	6084000000-E	1660	SEEDING & MULCHING	0.5	ACR	
0051	6087000000-E	1660	MOWING	0.5	ACR	
0052	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0053	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0054	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5	TON	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6114500000-N	1667	SPECIALIZED HAND MOWING	10		
				MHR		
0057	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	15		
				EA		

**STRUCTURE ITEMS**

005E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+02.50-L-)	Lump Sum	L.S.	
005E	8096000000-E	450	PILE EXCAVATION IN SOIL	55		
				LF		
006C	8097000000-E	450	PILE EXCAVATION NOT IN SOIL	50		
				LF		
0061	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (12+02.50-L-)	Lump Sum	L.S.	
0062	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	39.8		
				CY		
0063	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+02.50-L-)	Lump Sum	L.S.	
0064	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,694		
				LB		
006E	8364000000-E	450	HP12X53 STEEL PILES	125		
				LF		
006E	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	110.25		
				LF		
0067	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	105		
				TON		
006E	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	115		
				SY		
006E	8657000000-N	430	ELASTOMERIC BEARINGS (12+02.50-L-)	Lump Sum	L.S.	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	495 LF		

1539/Nov29/Q14367.25/D329292830000/E70

Total Amount Of Bid For Entire Project :

**Contract No.**     **C203029**

**County (ies):**   **Wilkes**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General