

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|-------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0030000000-N | SP | BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (17+86.50) | Lump Sum | L.S. | |
| 0004 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 0005 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB-BING | 1 ACR | | |
| 0006 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 400 CY | | |
| 0007 | 0134000000-E | 240 | DRAINAGE DITCH EXCAVATION | 1,281 CY | | |
| 0008 | 0196000000-E | 270 | GEOTEXTILE FOR SOIL STABILIZATION | 400 SY | | |
| 0009 | 0199000000-E | SP | TEMPORARY SHORING | 205 SF | | |
| 0010 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES | 60 TON | | |
| 0011 | 0320000000-E | 300 | FOUNDATION CONDITIONING GEOTEXTILE | 170 SY | | |
| 0012 | 0335100000-E | 305 | 12" DRAINAGE PIPE | 80 LF | | |
| 0013 | 0343000000-E | 310 | 15" SIDE DRAIN PIPE | 148 LF | | |
| 0014 | 0344000000-E | 310 | 18" SIDE DRAIN PIPE | 28 LF | | |
| 0015 | 0360000000-E | 310 | 12" RC PIPE CULVERTS, CLASS III | 16 LF | | |
| 0016 | 0582000000-E | 310 | 15" CS PIPE CULVERTS, 0.064" THICK | 220 LF | | |
| 0017 | 0636000000-E | 310 | *** CS PIPE ELBOWS, ***** THICK (15", 0.064") | 2 EA | | |
| 0018 | 0995000000-E | 340 | PIPE REMOVAL | 360 LF | | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|------------|-----------|--------|
| 0019 | 1099500000-E | 505 | SHALLOW UNDERCUT | 70 CY | | |
| 0020 | 1099700000-E | 505 | CLASS IV SUBGRADE STABILIZATION | 380 TON | | |
| 0021 | 1121000000-E | 520 | AGGREGATE BASE COURSE | 640 TON | | |
| 0022 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 400 TON | | |
| 0023 | 1275000000-E | 600 | PRIME COAT | 539 GAL | | |
| 0024 | 1330000000-E | 607 | INCIDENTAL MILLING | 100 SY | | |
| 0025 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 460 TON | | |
| 0026 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 200 TON | | |
| 0027 | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 680 TON | | |
| 0028 | 1575000000-E | 620 | ASPHALT BINDER FOR PLANT MIX | 80 TON | | |
| 0029 | 1693000000-E | 654 | ASPHALT PLANT MIX, PAVEMENT REPAIR | 10 TON | | |
| 0030 | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 15 EA | | |
| 0031 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 2 EA | | |
| 0032 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 1 EA | | |
| 0033 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 34 LF | | |
| 0034 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 100 LF | | |
| 0035 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0036 | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 4 EA | | |
| 0037 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0038 | 3380000000-E | 862 | TEMPORARY STEEL BM GUARDRAIL | 150 LF | | |
| 0039 | 3387000000-N | 862 | TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE ***** (III) | 4 EA | | |
| 0040 | 3389100000-N | SP | TEMPORARY GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |
| 0041 | 3628000000-E | 876 | RIP RAP, CLASS I | 550 TON | | |
| 0042 | 3656000000-E | 876 | GEOTEXTILE FOR DRAINAGE | 2,180 SY | | |
| 0043 | 4072000000-E | 903 | SUPPORTS, 3-LB STEEL U-CHANNEL | 83 LF | | |
| 0044 | 4096000000-N | 904 | SIGN ERECTION, TYPE D | 2 EA | | |
| 0045 | 4102000000-N | 904 | SIGN ERECTION, TYPE E | 3 EA | | |
| 0046 | 4155000000-N | 907 | DISPOSAL OF SIGN SYSTEM, U- CHANNEL | 9 EA | | |
| 0047 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 446 SF | | |
| 0048 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 110 SF | | |
| 0049 | 4430000000-N | 1130 | DRUMS | 40 EA | | |
| 0050 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 80 LF | | |
| 0051 | 4455000000-N | 1150 | FLAGGER | 60 DAY | | |
| 0052 | 4650000000-N | 1251 | TEMPORARY RAISED PAVEMENT MARKERS | 66 EA | | |
| 0053 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 18,440 LF | | |
| 0054 | 4850000000-E | 1205 | REMOVAL OF PAVEMENT MARKING LINES (4") | 3,610 LF | | |
| 0055 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 1,715 LF | | |
| 0056 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 225 TON | | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---------------------------------------|-------------|-----------|--------|
| 0057 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 430 TON | | |
| 0058 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 445 TON | | |
| 0059 | 6015000000-E | 1615 | TEMPORARY MULCHING | 3 ACR | | |
| 0060 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 150 LB | | |
| 0061 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 1.5 TON | | |
| 0062 | 6024000000-E | 1622 | TEMPORARY SLOPE DRAINS | 500 LF | | |
| 0063 | 6029000000-E | SP | SAFETY FENCE | 100 LF | | |
| 0064 | 6030000000-E | 1630 | SILT EXCAVATION | 860 CY | | |
| 0065 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 4,000 SY | | |
| 0066 | 6037000000-E | SP | COIR FIBER MAT | 1,850 SY | | |
| 0067 | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 1,100 SY | | |
| 0068 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 300 LF | | |
| 0069 | 6070000000-N | 1639 | SPECIAL STILLING BASINS | 14 EA | | |
| 0070 | 6071012000-E | SP | COIR FIBER WATTLE | 150 LF | | |
| 0071 | 6071020000-E | SP | POLYACRYLAMIDE (PAM) | 45 LB | | |
| 0072 | 6071030000-E | 1640 | COIR FIBER BAFFLE | 400 LF | | |
| 0073 | 6071050000-E | SP | *** SKIMMER (1-1/2") | 5 EA | | |
| 0074 | 6084000000-E | 1660 | SEEDING & MULCHING | 4.5 ACR | | |
| 0075 | 6087000000-E | 1660 | MOWING | 2 ACR | | |
| 0076 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|------------------------|--------------|-------|--|-------------|-----------|--------|
| 0077 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0078 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 100 LB | | |
| 0079 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 2.5 TON | | |
| 0080 | 6114500000-N | 1667 | SPECIALIZED HAND MOWING | 10 MHR | | |
| 0081 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 25 EA | | |
| STRUCTURE ITEMS | | | | | | |
| 0082 | 8007000000-N | SP | CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (17+86.50-L-) | Lump Sum | L.S. | |
| 0083 | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+86.50-L-) | Lump Sum | L.S. | |
| 0084 | 8105520000-E | 411 | 3'-0" DIA DRILLED PIERS IN SOIL | 49.75 LF | | |
| 0085 | 8105620000-E | 411 | 3'-0" DIA DRILLED PIERS NOT IN SOIL | 44 LF | | |
| 0086 | 8111200000-E | 411 | PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER | 48.5 LF | | |
| 0087 | 8113000000-N | 411 | SID INSPECTIONS | 1 EA | | |
| 0088 | 8114000000-N | 411 | SPT TESTING | 1 EA | | |
| 0089 | 8115000000-N | 411 | CSL TESTING | 1 EA | | |
| 0090 | 8121000000-N | 412 | UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+86.50-L-) | Lump Sum | L.S. | |
| 0091 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 71.1 CY | | |
| 0092 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (17+86.50-L-) | Lump Sum | L.S. | |

County : Forsyth

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0093 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 23,923 LB | | |
| 0094 | 8238000000-E | 425 | SPIRAL COLUMN REINFORCING STEEL (BRIDGE) | 3,708 LB | | |
| 0095 | 8364000000-E | 450 | HP12X53 STEEL PILES | 265 LF | | |
| 0096 | 8475000000-E | 460 | TWO BAR METAL RAIL | 335 LF | | |
| 0097 | 8517000000-E | 460 | 1'-**"X *****" CONCRETE PARA- PET (1'-2" X 2'-11 1/4") | 350.5 LF | | |
| 0098 | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 890 TON | | |
| 0099 | 8622000000-E | 876 | GEOTEXTILE FOR DRAINAGE | 985 SY | | |
| 0100 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0101 | 8762000000-E | 430 | 3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS | 450 LF | | |
| 0102 | 8763000000-E | 430 | 3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS | 1,300 LF | | |

1256/Jan04/Q77851.6/D449959852000/E102

Total Amount Of Bid For Entire Project :

Contract No. **C203039**

County (ies): **Forsyth**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General