Law Enforcement:

2-19-09 SPI

Description

Furnish Law Enforcement Officers and marked Law Enforcement vehicles to direct traffic in accordance with the contract.

Construction Methods

Use uniformed Law Enforcement Officers and marked Law Enforcement vehicles equipped with blue lights mounted on top of the vehicle, and Law Enforcement vehicle emblems to direct or control traffic as required by the plans or by the Engineer.

Measurement and Payment

Law Enforcement will be measured and paid for in the actual number of hours that each Law Enforcement Officer is provided during the life of the project as approved by the Engineer. There will be no direct payment for marked Law Enforcement vehicles as they are considered incidental to the pay item.

Payment will be made under:

Pay Item
Law Enforcement
Hour



TIP#: U-0209B Date: 09-27-12 Revised Date:

Temporary Sidewalk Protective Canopy:

Description

The Contractor shall provide 6 (six) protective canopies (two per proposed bridge) to protect pedestrians from falling debris along both proposed sidewalks on Independence Blvd. (-L-) beneath the proposed Sharon Amity (-Y1-), proposed Idlewild Rd. (-Y15-) and the proposed Conference Dr. (-Y18-) bridge at all times during construction of the bridge.

92

Construction Methods

Each protective canopy shall be constructed in accordance with local governing building codes and requirements of the Americans with Disabilities Act (ADA). Each protective canopy shall be adequately lit for nighttime use. At no time shall materials or equipment be stored on a canopy roof. All waste or falling debris is to be removed from canopy roofs on a daily basis or as directed by the engineer.

Measurement and Payment

The measurement and payment for the Temporary Sidewalk Protective Canopies shall be Lump Sum. The Lump Sum price shall include any costs associated with the installation, maintenance and removal.

Pay Item	Pay Unit
Protective Canopy	Lump Sum

