

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	6,579 SY		
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	12,604 SY		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	2,225 SY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	312 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** (0" TO 3")	2,270 SY		
0007	1330000000-E	607	INCIDENTAL MILLING	1,904 SY		
0008	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	2,265 TON		
0009	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	22,680 TON		
0010	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	3,405 TON		
0011	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	1,698 TON		
0012	1771000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #6M STONE	120,275 SY		
0013	1880000000-E	SP	GENERIC PAVING ITEM JOINT REPAIR	230 TON		
0014	1891000000-E	SP	GENERIC PAVING ITEM FLEXIBLE PAVEMENT RECLAMATION (12")	23,373 SY		
0015	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0016	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	6 EA		

County : Montgomery

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	4399000000-N	1105	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0018	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	81,350 LF		
0019	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	80,320 LF		
0020	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	4,400 LF		
0021	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	150 LF		
0022	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	412 LF		
0023	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	18 EA		
0024	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	26 EA		
0025	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	231,000 LF		
0026	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	955 EA		
0027	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,600 LF		
0028	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	150 LF		
1259/Jan14/Q600210.0/D87096100000/E28			Total Amount Of Bid For Entire Project :			

Contract No. **C203268**

County (ies): **Montgomery**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General