

County : Richmond

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (12+30.00 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	270 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	50 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	20 LF		
0013	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	76 LF		
0015	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	40 LF		
0016	0995000000-E	340	PIPE REMOVAL	62 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	84 TON		
0018	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		
0019	1330000000-E	607	INCIDENTAL MILLING	260 SY		

County : Richmond

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	440 TON		
0021	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	380 TON		
0022	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	45 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	9 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	67.2 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	50.4 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300 LF		
0027	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0028	2077000000-E	815	6" OUTLET PIPE	6 LF		
0029	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0031	2556000000-E	846	SHOULDER BERM GUTTER	25 LF		
0032	2830000000-N	858	ADJUSTMENT OF MANHOLES	3 EA		
0033	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350, TL-2)	4 EA		
0036	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0037	3628000000-E	876	RIP RAP, CLASS I	10 TON		
0038	3649000000-E	876	RIP RAP, CLASS B	2 TON		

County : Richmond

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,390 SY		
0040	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	71 LF		
0041	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0042	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0043	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6 EA		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	435 SF		
0045	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	63 SF		
0046	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0047	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,050 LF		
0048	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	35 LF		
0049	6000000000-E	1605	TEMPORARY SILT FENCE	610 LF		
0050	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	285 TON		
0051	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	85 TON		
0052	6012000000-E	1610	SEDIMENT CONTROL STONE	305 TON		
0053	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0054	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0055	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
0056	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0057	6029000000-E	SP	SAFETY FENCE	100 LF		

County : Richmond

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	603000000-E	1630	SILT EXCAVATION	260 CY		
0059	603600000-E	1631	MATTING FOR EROSION CONTROL	2,300 SY		
0060	603700000-E	SP	COIR FIBER MAT	835 SY		
0061	604200000-E	1632	1/4" HARDWARE CLOTH	85 LF		
0062	604800000-E	SP	FLOATING TURBIDITY CURTAIN	55 SY		
0063	607000000-N	1639	SPECIAL STILLING BASINS	12 EA		
0064	6071012000-E	SP	COIR FIBER WATTLE	240 LF		
0065	6071030000-E	1640	COIR FIBER BAFFLE	150 LF		
0066	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0067	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
0068	6087000000-E	1660	MOWING	0.5 ACR		
0069	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0070	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0071	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0072	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0073	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0074	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	18 EA		
<b>STRUCTURE ITEMS</b>						
0075	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (12+30.00-L-)	Lump Sum	L.S.	

County : Richmond

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	803500000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+30.00-L-)	Lump Sum	L.S.	
0077	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	148 LF		
0078	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	47 LF		
0079	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	72 LF		
0080	8113000000-N	411	SID INSPECTIONS	1 EA		
0081	8114000000-N	411	SPT TESTING	6 EA		
0082	8115000000-N	411	CSL TESTING	1 EA		
0083	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (12+30.00-L-)	Lump Sum	L.S.	
0084	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	87 CY		
0085	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+30.00-L-)	Lump Sum	L.S.	
0086	8217000000-E	425	REINFORCING STEEL (BRIDGE)	27,206 LB		
0087	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,603 LB		
0088	8364000000-E	450	HP12X53 STEEL PILES	210 LF		
0089	8391000000-N	450	STEEL PILE POINTS	12 EA		
0090	8475000000-E	460	TWO BAR METAL RAIL	285.5 LF		
0091	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 3'-5")	300.5 LF		
0092	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	490 TON		
0093	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	550 SY		

County : Richmond

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0095	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,200 LF		
0096	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	1,050 LF		
1241/Jan04/Q48124.35/D437324482000/E96			Total Amount Of Bid For Entire Project :			

**Contract No.**     C203037

**County (ies):**   Richmond

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General